



Materiel and Procurement Services  
200 Kent Street, Station 9W070  
Ottawa, Ontario  
K1A 0E6

January 23, 2017

**Subject:** Invitation to Tender: FP802-160275

**Title:** Marginal wharf construction.

**Work site location:** Barre-de-Cocagne, NB

**ADDENDUM: No. 7**

Further to the above mentioned Invitation to Tender documentation previously posted on the Government Electronic Tendering Site (GETS), BuyandSell.gc.ca, Addendum (#7) is hereby issued.

**Department of Fisheries and Oceans**

**Bid Closing Date:** Thursday, January 26, 2017  
**Time:** 14:00 Hours (2:00 pm) Eastern Standard Time (EST)  
**RFP File No:** FP802-160275

---

**\*\* THE FOLLOWING QUESTIONS WERE SUBMITTED BY POTENTIAL BIDDERS  
TO THE CONTRACTING AUTHORITY IN RELATION TO THE SUBJECT ITT\*\***

**Q.1 I am still unclear about the “new” poles P5, P6 and P7. Addendum No. 3 contains Q.8 asking if these poles are new or existing. Your answer only adds more confusion. Please simply answer this question: Is this Contractor to supply and install the three poles P5, P6 and P7?**

A.1 Yes.

**Q.2 With all these tender closing delay, will it affect the completion date of the project? Will the completion date of the project be extended?**

A.2 No.



**Q.3 Following the publication of the new LUMP SUM pricing table and the addition of Item 5. Removal and disposal of containment cell materials, we would like to have details on these materials to be moved: are they materials from Excavation above and below the 1.22m level which must be removed from the site AFTER the drying of these? Is the materials currently in place on the site?**

A.3 Yes the materials to be excavated, above and below the +1.22m elevation are presently in place and are located where the existing wharf is. Any material above the + 1.22m level is considered dry and uncontaminated and must be taken off-site. Materials above the + 1.22m level may be transported directly off site to a location determined by the Contractor if drying is not required; As directed by the project manager. All materials under the + 1.22m level are considered wet and contaminated with salt and will be placed in the containment cell that is on site and will remain there. The containment cell is currently full, so before excavating materials below the +1.22m level, the cell will need to be cleaned, as identified on addendum # 5, to make room for the excavation identified below the +1.22m, as discussed.

**Q.4 In the excavation of above elev. +1.22m, why does the material have to be stock piled before transporting?**

A.4 It does not need to be stock piled, but it is anticipated that the material could be wet and drying of the material might be needed prior to transportation off site.

**Q.5 Does the material have to be analyzed to the regulation with the Department of Environment of New Brunswick before transporting the material to a local pit?**

A.5 No. The material above +1.22m does not need to be analysed prior to transportation off site.

---

**All other Terms and Conditions for this requirement remain unchanged.**

**Tenderers are to acknowledge this Addendum by signing in the space provided below and enclosing a copy of this document with their tender submission.**

Regards

Gricha Zurita  
Senior Contracting Officer  
Telephone: (613) 993-2807  
Email: [Gricha.Zurita@dfo-mpo.gc.ca](mailto:Gricha.Zurita@dfo-mpo.gc.ca)

---



***RECEIPT ACKNOWLEDGED***

**Name of Company** \_\_\_\_\_

**Signature** \_\_\_\_\_