



RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Public Works and Government Services Canada
ATB Place North Tower
10025 Jasper Ave./10025 ave. Jasper
5th floor/5e étage
Edmonton
Alberta
T5J 1S6
Bid Fax: (780) 497-3510

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada
ATB Place North Tower
10025 Jasper Ave./10025 ave Jasper
5th floor/5e étage
Edmonton
Alberta
T5J 1S6

Title - Sujet AAFC Facility System Renovation	
Solicitation No. - N° de l'invitation EP922-172162/B	Amendment No. - N° modif. 003
Client Reference No. - N° de référence du client AAFC EP922-172162	Date 2017-02-06
GETS Reference No. - N° de référence de SEAG PW-\$PWU-066-10951	
File No. - N° de dossier PWU-6-39263 (066)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2017-02-13	Time Zone Fuseau horaire Mountain Standard Time MST
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Lee, Mony	Buyer Id - Id de l'acheteur pwu066
Telephone No. - N° de téléphone (780) 224-6675 ()	FAX No. - N° de FAX (780) 497-3510
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

The Bidding Documents are amended as noted in this Addendum, which consists of one (1) page and the following attachments:

1. Q&A
2. Added Specifications: None added.
3. Drawings: None added.

This addendum is issued prior to bid closing to amend the bid documents. This Addendum will form part of the Contract Documents. Include in the Bid price all such revisions which will become part of the Work. Perform all such Work in accordance with the contract documents.

Acknowledge receipt of this Addendum by reference in the Bid Form submitted by the bidding Contractors. Ensure that all parties submitting bids are aware of all items included in this addendum.

1. Q&A

1	Q	HVAC coring, what it's going through and how thick?
	A	The walls on the second floor boiler/mechanical/electrical rooms are maximum 4" masonry walls. The floor coring to the new mechanical room on the main floor will be done through wood. Coring thickness and materials will be field verified.
2	Q	The heating coil detail has a rectangular dashed line hanging from the drain valve left of the coil. Please clarify what this is.
	A	Dashed rectangular is not to be considered in the scope of work.
3	Q	Please clarify what is the model of the SDP Breakers
	A	<p>For the breakers in the new panel (Panel H) our recommendation would be one of the following:</p> <ul style="list-style-type: none">• Eaton/Cutler-Hammer type BAB• Schneider Electric/Square D type QO• Siemens type BL <p>The new breaker (125A – 3pole) required in the CDP will need to be selected by the contractor to ensure compatibility with the panel. The existing breakers are Westinghouse and understood to be no longer available.</p>
4	Q	Clarifying the questions 7 and 8 on the last addendum the scale 1:50 is not correct on an 11 x 17 drawing size. The original drawing would be larger size like A1. So you cannot get piping lengths using this scale. In short none of your drawings have lengths shown including the HVAC ducting detail on drawing H102. The only Item that has length dimensions is the concrete extension detail A on H102. Question 8 answer is incorrect as the only dimensions shown on schematic H104 are just for Expansion loop. There are no other length dimensions shown. Please clarify piping & HVAC ducting length dimensions.

Meat Research and Abattoir (MRA) Facility
Lacombe Research Center, Lacombe, Alberta
Stantec Engineering Ltd.

Addendum #02
PWGSC No. R.073123.001
February 6, 2017

	A	Drawings are to scale if printed out in an A1 format. To clarify the actual sizes of the project's rooms, see the following measurements: New Mechanical Room 136A: 3.60x5.72m Main Floor Workshop 136B: 2.51x5.78m Second Floor Electrical Room 203: 2.23x7.02m Second Floor Boiler Room 201: 3.96x6.33m Distance between Boiler Room 201 and Electrical Room 203: 5.85m
--	----------	--

END OF ADDENDUM #02