



Procurement Hub – Ottawa Office
200 Kent Street, Station 9S018
Ottawa, Ontario
K1A 0E6

February 9, 2017

Subject: Invitation to Tender: FP802-160404

Title: FRP Grating System

Work site location: Kingsclear, NB

ADDENDUM: No. 3

Further to the above mentioned Invitation to Tender documentation previously posted on the Government Electronic Tendering Site (GETS), BuyandSell.gc.ca, Addendum (#3) is hereby issued.

Department of Fisheries and Oceans

Bid Closing Date: Tuesday, February 14, 2017
Time: 14:00 Hours (2:00 pm) Eastern Standard Time (EST)
RFP File No: FP802-160404

****PLEASE NOTE THE FOLLOWING CHANGES TO THIS SOLICITATION****

Please Note:

Q.1 Drawing No. A-1, Specifications Part 1, Section 1.1.2.5, please note how many wheels on the feed cart, the wheel construction and the width of the wheels.

A.1 The feed cart has 4 wheels which are made of rubber, the wheel width is between 1.5"-3".

Q.2 Drawing No. A-1, Specifications Part 2, Section 2.2.1.2 notes the resin as CF (Chemical Proof) which is a vinyl ester resin system, please advise if an Isophthalic resin would be suitable for the intended use.

A.2 Isophthalic resin will not be suitable for this intended use.



Q.3 Drawing No. A-1, Specifications Part 2, Section 2.2.2 mentions FRP stair treads, stair treads are not shown on the drawings, please clarify where the FRP stair treads would be required.

A.3 Stair treads are not to be included in the scope.

Q.4 The Statement of Work notes the contractor is to provide the as-built drawings in one-week following the project substantial completion inspection, are general arrangement drawings required for review and acceptance prior to the start -up of the project? If no, what type of submission is required on the part of the contractor to obtain acceptance for the materials being used and the general design?

A.4 Yes, the contractor is to submit a sample of the products and shop drawings for approval.

Q.5 The Statement of Work notes the project to be completed by March 31, 2017, but no mention of when a PO will be issued. Please advise.

A.5 A PO will be issued upon project completion to the satisfaction of the Project Authority and an invoice is submitted according to invoicing instructions

Q.6 Could the project be staged to allow for a longer lead time to complete? If yes, would there be penalties for completing beyond the suggested date of March 31, 2017 and what would these penalties be?

A.6 No, the project completion cannot exceed March 31, 2017.

Q.7 The original spec says removal of all steel angle and steel bracing and the addendum says: Section 2 under “Demolition General Notes” in document “FP802-160404 - Drawings - Revision 1.pdf” is to be removed; the existing steel supports are not to be removed or replaced; question : Which is it ? Leave the old angle and steel posts or remove it all?

A.7 Leave the old angles and steel posts.

Q.8 In the addendum under Demolition Work:

- i. Remove components of existing building, as indicated and required, to permit new construction;**
- ii. Prevent movement, settlement, and other damage to parts of building to remain in place. Provide bracing and shoring required;**
The demolition seems to indicate removal of over 200 steel posts and all of the angle. These posts are supporting the steel walkway.
Do these steel posts support the cantilevered concrete fish tanks in any way?
Is the vendor responsible for replacing new steel posts to support the concrete tanks ?

A.8 The existing steel posts and angles are to remain.



All other Terms and Conditions for this requirement remain unchanged.

Tenderers are to acknowledge this Addendum by signing in the space provided below and enclosing a copy of this document with their tender submission.

Regards

Michael Vanek
Senior Contracting Officer
Telephone: (613) 993-8935
Email: michael.vanek@dfo-mpo.gc.ca

RECEIPT ACKNOWLEDGED

Name of Company _____

Signature _____