



**RETURN BIDS TO:  
RETOURNER LES SOUMISSIONS A:  
Bid Receiving/Réception des  
sousmissions**

**RCMP / GRC  
Procurement & Contracting services  
c/o Commissionaires, F Division  
6101 Dewdney Avenue  
Regina, SK S4P 3K7**

**Facsimile Number for Amendments:  
(306) 780-5232**

**SOLICITATION AMENDMENT  
MODIFICATION DE L'INVITATION**

**The referenced document is hereby  
revised; unless otherwise indicated, all  
other terms and conditions remain the  
same.**

**Ce document est par la présente révisé;  
sauf indication contraire, les modalités  
de l'invitation demeurent les memes.**

**Comments - Commentaries**

**Vendor/Firm Name and Address  
Raison sociale et adresse du  
fournisseur/de l'entrepreneur**

**Facsimile No. - No de télécopieur:**

**Telephone No. - no de téléphone:**

Title-Sujet <b>HVAC Upgrade, Multi Purpose Training Facility</b>	
Solicitation No. - No. de l'invitation <b>M5000-17-6163/A</b>	Date <b>15 February 2017</b>
Amendment No. - No modif. <b>05</b>	
Client Reference No. - No. De Référence du Client <b>M5000-17-6163/A</b>	
GETS Reference No. - No. de Référence de SEAG <b>PW-17-00766242</b>	
Solicitation Closes -L'invitation prend fin <b>at - à 2 :00 pm Central Standard Time on - le 23 February 2017</b>	
F.O.B. - F.A.B. Destination	
Address Enquiries to: - Adresser toutes questions à: <b>Teresa Hengen, Contracting Officer</b>	
Telephone No. - No de téléphone <b>(639) 625-3449</b>	Fax No. - N° de FAX: <b>(306) 780-5232</b>
Destination of Goods, Services, and Construction: Destinations des biens, services et construction: <b>Royal Canadian Mounted Police Academy, Depot Division 5600 - 11<sup>th</sup> Ave Regina, SK S4P 3J7</b>	
<b>This document does not contain a PERSONNEL SECURITY Clearance requirements</b>	
Delivery Required - Livraison exigée: <b>See Herein Voir aux présentes</b>	Delivery Offered - Livraison proposée <b>See Herein Voir aux présentes</b>
Name and title of person authorized to sign on behalf of Vendor/Firm Nom et titre de la personne autorisée à signer au nom du fournisseur/de l'entrepreneur	



The purpose of this amendment is to add an addendum: ADDENDUM M-3, ADDENDUM NO. 2 and ADDENDUM NO. 4, attached separately and to address the following:

Q2) Drawing A1.1 demolition key notes tag #6 call up new opening in existing wall, for example, 600x300 opening in the wall, is 600 the length way dimension of opening?

A2) Yes

Q3) Steel angle lintels are required at masonry block wall, but from drawings, I can't figure out which walls are block wall, are all the walls block wall?

A3) Some are block, some are brick

Q4) Are there only 4 pcs of masonry anchors required at each opening or will the anchors required at required space along the steel lintel length?

A4) We only require anchors at the bearing locations for the angles as shown on the drawings

Q5) Can the painting scope of work be clarified? The items to be painted that I can find within the drawings and specifications are as follows:

- Note 4 on A1.2
- Note 12 on A1.2 (interior and exterior)
- New Door and Frame on pages A1.2 & A1.3 both items #8 - to be painted to match existing

A5) This list should also include AHU stands shown on Mech drawing M-8

Q6) I have been asked about the following items, and am not sure if they are to be included, or if any other items that I did not note above are to be included. Please advise.

- All wall duct penetrations.
- All new ductwork.
- Ceilings at new duct locations

A6) - All wall duct penetrations. Addendum to follow.

- All new ductwork. Not included
- Ceilings at new duct locations. Not included

Q7) I have received a question regarding the structural scope of work. Drawing S1 shows the required lintels for the CMU and brick walls. On drawing M-9, detail 3 shows structural information for the new exterior wall louvres (approximately 40 locations)

A7) There are approximately 40 existing louvres to be in-filled - details found Pages A1.2 & A1.3 item # 12.

Q8) Are these items to be included by the structural contractor, or is this a mechanical item? I ask because typically all structural elements are shown in the structural drawings, and these structural items are not shown at all within the structural drawings. Please confirm.

A8) Refer to Lintel Schedule on S1. Angle iron on all sides as referenced on detail 3/M-9 to be 3 ½" x 3 ½" x ¼", painted.

ALL OTHER TERMS AND CONDITIONS REMAIN THE SAME