

## Addendum / Addenda

Project Description / Description de projet			
U	66 Chiller Replacemen	t.	
Solicitation No./N° de solicitation	Project No./N° de projet		W.O. No./N° d'ordre de travail
16-22146	520	)1	A1-006954-06-01
Departmental Representative / représentar	nt ministériel		Date
Μ	aurice Richard		February 20, 2017
Notice: This addendum shall form part of the tende hall apply and be read in conjunction with pecifications.	er documents and all conditions		<b>Nota</b> : grale des dossiers d'appel; toutes les conditions s et appliquées en conjonction avec les plans et les

- 1 IT room 244 requires access at all time. Provide hoarding when working in that area to ensure room is always accessible.
- 2 Question submitted during tender:

**Q:** We have been asked to quote the mechanical equipment on U-66 Chiller Replacement. I have noticed the equipment has been named but I do not see any additional approved manufacturers. Is this an open specification or do we need to go for written approval prior to tender closing?

**A:** Yes, in cases where a specific make/model has been referenced in the specifications or on the drawings a formal request for equivalency must be submitted during the tender period as described in the specification. Submissions must respect the required by dates noted in the specification.

- **3** Rooms 154, 156 and adjacent corridor will be made available for a maximum duration of 6 weeks. Work in these spaces cannot begin until May 1, 2017. Stationary equipment within rooms 154 & 156 will need to be adequately protected during construction. NRC will remove mobile equipment such as furniture, chairs, computer workstations and shelving units. In room 154 NRC will remove rack mounted computer equipment and associated racks prior to work commencing.
- 4 One or both of the cooling tower louvres will need to be removed to remove the old cooling tower. There is an asbestos containing wall finish material beneath the EIFS. Follow standard asbestos precautionary measures if it is necessary to disturb the existing ACM beneath the EIFS. The extent of precautionary measures is fully dependent on the method the contractor chooses to use to remove the material. The consultant will be available during construction to review the options with the contractor.





No./No


- 5 Remove requirement for ceiling mounted return grilles in the ceiling of the 2nd floor offices and meeting rooms where the ceiling is being replaced. The existing return air openings (below the new ceiling) are to remain and reinstated with new return air grilles. Provide new return air grilles and connect to the new return air ductwork; Grilles to be similar to the following basis of design;
  - 1. EH Price Model Louvered Face Return Grilles, 45 Deg deflection, ½" spacing, long blade in the horizontal position
  - 2. Model No. 535 / N / S / A
  - 3. Size to match return air ductwork indicated on drawings
- 6 Add the following perimeter heating control valve work to the scope of work:
  - a. The existing pneumatic control valves are to be demolished at each perimeter heating unit located on the 2nd floor within the area of work. Reconnect rads to heating water supply. These are located in the following rooms: 221, 225, 229, 230, 232, 233, 237, 238, 241, 242, 267, 268, 271, 272, 275, 276, 279.
  - b. The existing pneumatic tubing is to be demolished back to the nearest main line.
  - c. A new DDC temperature sensor and DDC hydronic control valve will be provided for each new perimeter heating unit (provided by Airtron), the contractor is to allow for installation of the temperature sensor and the control valve. New hydronic heating control valves are to be located in the ceiling space of the floor below. Contractor to allow for scaffolding as required.
  - d. Provide new insulation and jacketing to match existing
  - e. All control wiring to be installed in EMT conduit. Set-up and programming by controls contractor.
  - f. Patching and painting to be included in contractor's scope.
  - g. Refer to attached photos showing typical existing pneumatic control valves within perimeter heating unit and heating water supply pipes in the ceiling below.
  - h. Total quantity of control valves is 19.
- 7 Refer to attached typical photos of existing perimeter heating control valves and the ceiling spaces below.
- 8 Add the following new AHU heating system work to the scope of work:
  - a. Demolish the existing heating water supply and return piping that serves the heating coil of the existing AHU and the existing unit heater. Cap at main branch and keep for re-use.
  - b. Provide new heating water supply and return piping to feed the new heating coil in the new AHU. Provide a new isolation valves at the branch connection and heating control valve and hydronic specialities per the detail (typical coil detail attached) at the unit.
    Connect new piping to existing unit heater, complete with all hydronic specialities.
  - c. Provide new insulation and jacketing for the new heating piping to match existing.
- **9** Electrical drawings 5201-E05 and 5201-E06 call for the reuse of 5 fluorescent light fixtures in room 245 and the adjacent corridor. In their place provide 5 type A LED light fixtures.
- **10** Electrical drawings 5201-E05 and 5201-E06 call for the fluorescent light fixture outside the elevator to remain in place. Instead provide 1 type A LED light fixture. Switching to remain as-is.
- **11** Electrical drawings 5201-E05 and 5201-E06 call for the light switch in room 245 to remain in place. Instead install LED dimming switch specified in specifications section 26 27 26.



- 12 Electrical drawing 5201-E07 notes 3, 4, 5 call for the removal an re-installation of several pieces of electrical equipment to allow for the addition of a double door. The scope of work has changed to leave this door as-is and move the new AHU into the penthouse by creating an opening in the roof. Remove and re-install existing light fixture and associated conduit, and heat detector and associated conduit as necessary to allow roof opening for new AHU.
- **13** In rooms 154, 156 and the adjacent corridor there is a 610mm space above the existing Tbar ceiling.
- 14 Refer to attached quote for controls work by Airtron. Carry this cost as a cash allowance and submit final invoice from Airtron to confirm amount at project completion. Only actual amount billed by Airtron is to be paid out of this cash allowance, any remaining balance is to be credited back to NRC. Carry all profit and overhead costs associated with all Airtron work in your bid, regardless of the final cost by Airtron.
- **15** All control wires are to be in colour coded EMT conduit per specifications. Coordinate conduit supply/install with airtron to ensure all work is included in bid.
- 16 Attached are the attendance sheets from the 2 job showings.







### NOTES:

- 1 ARRANGE PIPING & INSTALLATION OF VALVES SUCH THAT VALVES ARE GROUPED FOR EASY MAINTENANCE.
- (2) SUPPORT DUCTWORK ON EACH SIDE OF THE BOOSTER COIL.
- (3) PROVIDE ACCESS DOOR IN DUCT UPSTREAM OF COIL FOR CLEANING PURPOSES.



February 1, 2017

National Research Council Canada 1200 Montreal Road Ottawa, Ontario K1A 0R6

Attention:Derek FootTel.:613-991-4451Email:Derek.foot@nrc-cnrc.gc.ca

### Subject: NRC Building U-66 HVAC Equipment and Chiller Replacement – Section 25 EMCS

We are hereby submitting our quotation to provide the EMCS for the above-mentioned project. Our quotation is based on mechanical drawings dated January 27, 2017 – issued for tender, mechanical specifications and our understanding of the scope of work and services. For a detailed scope of work, please see the following;

### Scope of Work

- Demolition of existing EMCS controls.
- Supply and install (1) Andover BCX for integration of the following systems into the EMCS.
  - o (5) BACnet MS/TP Pump VFDs
  - (4) BACnet MS/TP Fan VFDs
  - (1) BACnet MS/TP Chiller (commissioning, setup and programming of Chiller OEM controls by system manufacturer or representative)
- Supply and install power and network for all new Andover controllers.
- Supply and install (1) Local Control Panel c/w Andover field controllers in <u>Basement Mechanical Room</u> for control/monitoring of the following systems as per points list;
  - o 66CCH01 Chiller
  - o 66CWP01, 02, 03 Pump VFDs
  - o 66CTP01, 02 Pump VFDs
  - o 66HX Heat Exchanger
  - o 66CTR Sump
  - Mechanical Room Ventilation System (66EF VFD, exhaust and outdoor motorized dampers)
  - o Refrigerant Leak Detection System
- Supply and install (1) Local Control Panel c/w Andover field controllers in <u>Penthouse Mechanical Room</u> for control/monitoring of the following systems as per points list;
  - 66AHU1 Air Handling Unit
  - o 66HUM1 Humidifier
  - o 66CTR Cooling Tower
- Supply and install (1) Local Control Panel c/w Andover field controllers in <u>Second Floor Room 257</u> for control/monitoring of the following systems as per points list;
  - 66FCU01 Fancoil Unit
- Supply and install (21) Andover VAV controllers (with integrated damper actuator and flow transducer) mounted in VAV box enclosures.
  - Interface VAV controllers to (19) perimeter heating control valves
- Supply and install (1) Refrigerant Leak Detection System c/w the following;
  - (1) Gas Detection Panel
  - o (1) R-134a leak detection sensor
  - (1) Audible and Visual Annunciator (mounted exterior to Mechanical Room)
  - o (1) Emergency Activation switch
  - Supply and install the following end-devices, including the required power supplies;
    - o (2) wet/wet differential pressure sensors
    - (9) immersion temperature thermistors
    - o (1) space temperature thermistors
    - (21) space Andover smart sensors
    - (1) freeze stat
    - (2) duct humidity sensors
    - o (4) duct temperature thermistors
    - o (1) averaging duct temperature thermistor
    - $\circ$  (1) duct CO2 sensor
    - o (6) duct pressure sensors
    - o (1) combination outdoor air temperature/humidity/CO2 sensor
    - o (4) motorized damper actuators (mechanical room ventilation system)
  - Supply the following motorized control valves. Installation by others;
    - (8) free cooling changeover control valves

Airtron Canada – Ottawa	Tel: (613) 247-7938
100-2935 Conroy Road	Fax: (613) 247-7990
Ottawa, ON K1G 6C6	www.airtroncanada.com

- o (1) heat exchanger control valve
- o (1) AHU heating control valve
- o (1) AHU cooling control valve
- (1) FCU cooling control valve
- (19) perimeter heating control valves
- Supply and install the following miscellaneous devices, associated low voltage wiring;
  - o Humidifier air-flow proving switch, humidistat
- Update existing Operator Workstation graphics to reflect the changes made.
- Testing and commissioning of new EMCS points.
- Coordination of final sequence of operations with NRC Staff before implementation.
- Engineering shop drawings, as-built updates.

### Items supplied by Airtron, installed by others

- (13) Immersion wells
- (31) Motorized control valves

### Items supplied and installed by others

- Motorized dampers
- 66AHU1, 66FCU motorized dampers and actuators (with required actuator feedback)
- Electrical, gas, water meters
- VFDs with BACnet MS/TP interface
- Chiller BACnet MS/TP interface
- Cooling tower sump float switch, basin heater

Our Scope of Work includes installation, start-up and commissioning, engineering, graphics and project management.

### Pricing;

We have established a total project cost of **\$165,000.00 HST Extra (one hundred sixty five thousand dollars)** as per the above scope of work.

Particular notes;

All exposed wiring will be installed in pre-painted orange conduit for EMCS. Gas Detection System wiring will be installed in pre-painted purple conduit.

Bonding/ Building Permit / Builder's Risk Insurance is not included in our price.

General Liability Coverage until substantial completion is included in our price.

All work to be performed during regular working hours.

Installation as per NRC/Airtron established standards.

All new Customer's to Airtron Canada will be subject to credit approval and agree to 45 day payment terms from date of invoice.

Price is valid for a period of 30 days.

Training is included.

Should you have any questions or comments, please contact me.

Regards, Airtron Canada


Aaron Dobson Filename: NRC U-66 HVAC Equipment and Chiller Replacement Airtron EMCS Quote FEB 2017.pdf

Airtron Canada – Ottawa 100-2935 Conroy Road Ottawa, ON K1G 6C6 Tel: (613) 247-7938 Fax: (613) 247-7990 www.airtroncanada.com NRC Chiller and HVAC replacement at U-66

Solicitation #12-22146

Addendum #2

Typical photos of existing perimeter heating & pneumatic control valves:











Typical photos of existing through the floor piping where new DDC hydronic control valves are to be installed.











					1 8	Hydroplumb/x-L-air	Serge Zimola Lowst.	Alliance	à	CLIMATS WORLDS	COMPANY	Maurice Richard	Denartmental Representative / représentant	Solicitation No./N° de solicitation		Project Description / Description de projet	Mandatory Site Visit Attendance	NAC-CNAC	
National Research Council Canada						plas	Serge Timole	Marc La liberte	Parach Dobsorp	STEW NOSTS	NAME	14/0	10-22140		U66 HVAC Equipment and Chiller Replacement		Attendance		
h Conseil national de recherches Canada						Muy 613	Luf C la	Kanger 61	And GI	M. Gr	ASIGNATURE	17	Signature Altern	Project No./No de projet					
					2005	-836-8261	3.745-7872 (43-	613 8056272	-217 0408-866-219	0-838-9989	PHONE	l, 2017	JZU I Alternate deadline Ouestio						
Canada						613-836-8369 "	(13.745.8957 S		8060-342-519		FAX		Ouestion Deadline 2nd	1st		Clos			
ada						11 2	Severa lindalanstical	Warco alliancencinperio	Patdobson C inflector.		EMAIL	February 16, 2017	Pedruary 14, ∠017	1st Showing	March 7, 2017	Closing Date			
						.ca	Lowice	anger ca	or, ca				9.00 AM	Showing Time	2:00 PM	Closing time			

-	
25	1
H	
$\mathbf{D}$	
2	
$\bigcirc$	1
2	6-

Council Canada	National Research
recherches Canada	Conseil national de

Mandalory one visit Anendance						
Project Description / Description de projet					Closing Date	Closing time
U66	U66 HVAC Equipment and Chiller Replacement				March 7, 2017	2:00 PM
Solicitation No./N° de solicitation		Project	Project No./No de projet		1st Showing	Showing Time
	16-22146		5201		February 14, 2017	
Departmental Representative / représentant	0	Signature			2nd Showing	9:00 AM
Maurice Richard	X	14/02/2017	February 24, 2017	February 28, 2017	February 16, 2017	
COMPANY	NAME	SIGNATURE	PHONE	FAX	EMAIL	÷
Blackund McZonald	Ben Buller	Brin Annel	613 8186159		BB ALLER Blackand Wedonald	ald, rom
Slautat Electric	CARL GAUNCAN	( our or -	Car 3-789-3535		Donaho & Electraic occ	22
3V MECHANICAL	ALLAN VARVE		613-526-4595	63-260-3540	Allan@ 3 V mechanical . ga	à
TPC/Ray FOND (TD)	SLET CROUFORD		613-822-2312	613-822-2317	Scotton strate tom	torel, CA >
Medern Niegara	Josenburgeen	A Cli	CC 20-808-ED	613-591.7512	Hourseau Omodernnie gara.	ara, com
0	C				(	
		(				
2.						
						75

## NAC-CNAC

# Mandatory Site Visit Attendance

Mandatory Site Visit Attendance	Attendance					
Project Description / Description de projet	U66 HVAC Equipment and Chiller Replacement	Replacement	v		Closing Date March 7, 2017	Closing time 2:00 PM
Solicitation No./N° de solicitation	16-22146	Project N	5201		1st Showing February 14, 2017	Showing Time
Departmental Representative / représentant Maurice Richard		Signature 16/02/2017	Alternate deadline February 24, 2017	Question Deadline 2 February 28, 2017	<sup>2nd Showing</sup> February 16, 2017	9:00 AM
COMPANY	NAME	SIGNATURE	PHONE	FAX	EMAIL	
TRAINOR MECHANICAL	DEAN KEONGH	(m/m	709-899-2404		dean.tranech(SSHAN.CA	CA
Thank way win	WARAN HEWENNES		403-614-4300		Murray traned e teles net	£.
Trainor Mechanical	Maurice West		250-551-9427	250-352-2557	Westmos@telus.Ne	ve t
SHABNAM Const. Lt.	Medi Shabram	A A	613-265-6632	277	Scl. Canada a) (choo.	o. Ca
NOCALIQUE ACI	Preble ASPAD		819-213-4963		INFOR MECANIQUE PCI.	L.COM
Asby uto	And Ver Cellist	and les	613-338-1080	4101-366-619	andrew @ asbetimet	
CAMM	A.CMARDA	a fre	6138800243		ANDREW (@ CAMM - MACHTY/ERY	ERY
Keminyon Dillion Le	Andren Bart	holints	613 812 1400		PCMINSton al a 4050 e ginai	1,000
Taplen	DougLee	3-Cee	6135212550		I lee priaplenconstruction con	777
				2		
-						

National Research Conseil national de Council Canada recherches Canada

Canada

NAC-CNAC						
Mandatory Site Visit Attendance	Attendance					
Project Description / Description de projet			8		Closing Date	Closing time
	U66 HVAC Equipment and Chiller Replacement	eplacement			March 7, 2017	2:00 PM
Solicitation No./N° de solicitation			Project No./No de projet	_	1st Showing	Showing Time
2	16-22146		5201		February 14, 2017	
Departmental Representative / représentant Maurice Richard	4	Signature 16/02/0017	Alternate deadline February 24, 2017	Question Deadline 2 February 28, 2017	<sup>2nd Showing</sup> February 16, 2017	9:00 AM
COMPANY	NAME ,	SIGNATURE	PHONE	FAX	EMAIL	Ξ
Applante Builders	Clarello hour hand	Whanhut	2138307790	6158302710	CAROLELAD LUTE CON. Albor .co	en ale
SIK, SHERT METRICIAL LID	(A) Kenzwen	Ster 1	613-7487277	6137487532	LEKENINGN @SKSHEET MET M	MCTAL OCA
55 electriz	Section & Boudrias	A Contraction	[43-551-0247	613-632-1975	Sbudriaso Sselectric.	CA
Alliance	Brook Pinky	XX	613-240-4029	And a second	breat @ alligace ensineer.	1.1.09
CLOWAIR	CHARLES LAVERODE	Charles Porsuna	89-955-7577	819-777-9369	TRAVE	TWTLATION.C
ProTAB	Poter Chabursky	Mit Link	2962244013		Profate @ Belline Fronce	
DONALCO	PD BREWLAN	NX X	63216-7678	6132167679	edbrennand denakonttawa.com	·com
				3		
		3				
						10
	5	5.				

National Research Conseil national de Council Canada recherches Canada

Canada