

The following Addendum 01 forms part of the Contract Documents for the Security System Retrofit, Warkworth Institution, Campbellford, Ontario K0L 1L0; and further identified as PWGSC Project Number R.078483.001. The following changes, additions or deletions shall be made to the following documents as indicated and all other Contract Documents shall remain the same.

This Addendum Number 01 contains one (1) written page(s).

## ARCHITECTURAL

### Specification:

#### Section 01 11 00 – Summary of Work

##### 1. 1.6 Work Sequence

Add the following:

.8 Renovations to Unit WW 05 shall be completed before Work on WW 06 commences. Contractor shall provide a schedule to the Departmental Representative which acknowledges procurement of materials, mobilization on site and completion of Work in WW 05 before WW 06 commences.

.9 Renovations on WW 08, 09, 10 & 11 shall be undertaken so that the Work is staged so that not more than two units are being renovated at the same time. Contractor may commence Work on a third Unit if the first Unit is completed. Contractor shall provide a schedule to the Departmental Representative which indicates start and completion of Work in each Unit and commencement in the next Unit.

### Drawing:

#### Drawing A-04A – ENLARGED DEMOLITION SECTION AND ELEVATION

1. Refer to Note 6: Contractor shall sawcut out and/or remove intact the existing precast concrete security grille from the exterior of the precast panel in Unit WW05. Contractor shall hand over and move the security grille to a location within the Institution as directed by the Departmental Representative.
2. Contractor shall remove the interior glazed security window unit and aluminum frame from the interior of the same precast panel location and turn over and move the unit to a location within the Institution as directed by the Departmental Representative.

End of ADDENDUM Number 01