
PART 1 - GENERAL

1.1 SECTION
INCLUDES

- .1 Barriers.
- .2 Traffic Controls.

1.2 INSTALLATION AND
REMOVAL

- .1 Provide temporary controls in order to execute work expeditiously.
- .2 Remove from site all such work after use.

1.3 HOARDING

- .1 Erect temporary site enclosure using new 1.2 m high snow fence wired to rolled steel "T" bar fence posts spaced at 2.4 m centres. Provide one lockable truck gate. Maintain fence in good repair.

1.4 GUARD RAILS AND
BARRICARDS

- .1 Provide secure, rigid guard rails and barricades around open excavations, steep cliffs, and as required to protect against falls.
- .2 Provide barricades along fishway structure until new work is completed.
- .3 Provide as required by governing authorities.

1.5 ACCESS TO SITE

- .1 Provide and maintain access to adjacent facilities.

1.6 PUBLIC TRAFFIC FLOW

- .1 Provide and maintain competent signal flag operators, traffic signals, barricades and flares, lights, or lanterns as required to perform work and protect the public.

1.7 FIRE ROUTES

- .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

DFO	Temporary Barriers	Section 01 56 00
Fishway Enhancement	& Enclosures	Page 2 of 2
Rocky River 2017		
Job No. F6879-171001		

- | | | |
|---|----|--|
| 1.8 PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY | .1 | Protect surrounding private and public property from damage during performance of work. |
| | .2 | Be responsible for damage incurred. |
| 1.9 MEASUREMENT FOR PAYMENT | .1 | No separate measurements for payment shall be made for items under this section. Include costs for Temporary Barriers & Enclosures in the Lump Sum portion of the work on the Bid and Acceptance Form. |

PART 2 - PRODUCTS

2.1 NOT USED

PART 3 - EXECUTION

3.1 NOT USED