
PART 1 - GENERAL

1.1 RELATED WORK

- .1 Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

1.2 DEFINITIONS

- .1 Hazardous Material: Product, substance, or organism that is used for its original purpose; and that is either dangerous goods or a material that may cause adverse impact to the environment or adversely affect health of persons, animals or plant life when released into the environment.

1.3 SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Prior to commencing construction activities or delivery of materials to site, submit Environmental Protection Plan for review and approval by Departmental Representative. Environmental Protection Plan is to present comprehensive overview of known or potential environmental issues which must be addressed during construction.
- .3 Address topics at level of detail commensurate with environmental issue and required construction tasks.
- .4 Environmental protection plan: include:
.1 Names of persons responsible for ensuring adherence to Environmental Protection Plan.
.2 Names and qualifications of persons responsible for manifesting hazardous waste to be removed from site.
.3 Names and qualifications of persons responsible for training site personnel.
.4 Descriptions of environmental protection personnel training program.
- .5 Erosion and sediment control plan which identifies type and location of erosion and sediment controls to be provided including monitoring and reporting requirements to assure that control measures are in compliance with erosion and sediment control plan, Federal, Provincial, and Municipal laws and regulations.
- .6 Drawings showing locations of proposed temporary excavations or embankments for haul roads, stream crossings, material storage areas, structures, sanitary facilities, and stockpiles of excess or spoil materials including methods to control runoff and to contain materials on site.

- .7 Spill Control Plan: including procedures, instructions, and reports to be used in event of unforeseen spill of regulated substance.
- .8 Non-Hazardous solid waste disposal plan identifying methods and locations for solid waste disposal including clearing debris.
- .9 Air pollution control plan detailing provisions to assure that dust, debris, materials, and trash, do not become air borne and travel off project site.
- .10 Contaminant prevention plan that: identifies potentially hazardous substances to be used on job site; identifies intended actions to prevent introduction of such materials into air, water, or ground; and details provisions for compliance with Federal, Provincial, and Municipal laws and regulations for storage and handling of these materials.
- .11 Wastewater management plan that identifies methods and procedures for management and/or discharge of waste waters which are directly derived from construction activities, such as concrete curing water, clean-up water, dewatering of ground water, disinfection water, hydrostatic test water, and water used in flushing of lines.

1.4 FIRES

- .1 Fires and burning of rubbish on site not permitted.

1.5 DISPOSAL OF WASTES
AND HAZARDOUS MATERIALS

- .1 Do not bury rubbish and waste materials on site. Dispose at approved landfill sites as specified in Section 01 74 21.
- .2 Do not dispose of hazardous waste or volatile materials such as mineral spirits, paint thinner, oil or fuel into waterways, storm or sanitary sewers or waste landfill sites.
- .3 Store, handle and dispose of hazardous materials and hazardous waste in accordance with applicable federal and provincial laws, regulations, codes and guidelines.
- .4 Dispose of construction waste materials and demolition debris, resulting from work, at approved landfill sites only. Carry out such disposal in strict accordance with provincial and municipal rules and regulations. Separate out and prevent improper disposal of items banned from landfills.
- .5 Establish methods and undertake construction practices

which will minimize waste and optimize use of construction materials. Separate at source all construction waste materials, demolition debris and product packaging and delivery containers into various recycling abilities of various materials and avoid disposal of debris at landfill site(s) in a "mixed state". Where recycling firms specializing in recycling of specific materials exist, transport such materials to the recycling facility and avoid disposal at landfill sites.

- .6 Communicate with landfill operator prior to commencement of work, to determine what specific construction, demolition and renovation waste materials have been banned from disposal at the landfill and at transfer stations.

1.6 DRAINAGE

- .1 Provide temporary drainage and pumping as necessary to keep excavations and site free from water.
- .2 Do not pump water containing suspended materials into waterways, sewer or drainage systems.
- .3 Control disposal or runoff of water containing suspended materials or other harmful substances in accordance with governing regulations and requirements.
- .4 Pumped water must meet applicable federal, provincial and municipal standards before it can be discharged to a surface water body. If regulatory guidelines exceedences are noted, the Departmental Representative has the right to issue stop pumping instructions to the Contractor. Contractor will not be compensated for any delays associated with retrofitting equipment to meet guidelines.
- .5 Provide control devices such as filter fabrics, sediment traps and settling ponds to control drainage and prevent erosion of adjacent lands. Maintain in good order for duration of work.

1.7 PERMITS

- .1 All guidelines and instructions stated on permits must be strictly adhered to.

1.8 WORK ADJACENT TO
WATERWAYS

- .1 Do not operate construction equipment in waterways, unless approved in writing by the Departmental Representative.
- .2 Do not use waterway beds for borrow material.
- .3 Do not dump excavated fill, waste material or debris in waterways.
- .4 At borrow sites, design and construct temporary crossings to minimize erosion to waterways in strict conformance with provincial and federal environmental regulations.
- .5 Do not skid logs or construction materials across waterways.
- .6 Avoid indicated spawning beds when constructing temporary crossings of waterways.
- .7 Do not blast within 100 m of spawning beds.
- .8 Equipment working in and adjacent to water way shall be equipped with biodegradable hydraulic oils specifically intended for environmentally sensitive areas. Contractor shall submit MSDS and Technical Data sheets on hydraulic oil to be used for approval by the Departmental Representative.

1.9 REFUELING

- .1 Refueling of equipment to be performed in locations as directed by Departmental Representative.
- .2 Do not refuel equipment within 100 metres of any watercourse or storm water catch basin unless protection against spills is in place and location is approved by Departmental Representative.
- .3 Use petroleum containers approved for products with no spill fill spouts for dispensing fuels. The sure pour nozzle to have self closing valve, prevent any flow of fuel until the nozzle is inserted into the receiving container. On removal from the receiving container the slide valve closes to eliminate any fuel spill. Nozzle to be equipped with its own automatic vent eliminating the need for the user to open or close air inlets on the pouring container.
- .4 Nozzle to support the weight of the pouring container. Nozzles to automatically stop the flow when the receiving container becomes full. The nozzle to be such that it reduces evaporative losses of volatile organic compounds during the fuel transfer.
- .5 All spills of hydrocarbon based products such as

gasoline, kerosene, naphtha, lubricating oils, engine oils, greases and de-icing fluids or antifreeze no matter how large or small to be reported to Departmental Representative.

- .6 Oil changes or equipment repairs in the field or on Correctional Services Canada land are not permitted.
- .7 Refueling to be performed on level surfaces, PCC Portland cement concrete or HMA surfaces when approved by the Departmental Representative unless otherwise directed.
- .8 Contractor to have drip pans sized for amounts of product to be recovered and customized to fit under pieces of equipment to perform routine maintenance to equipment while maintaining equipment on property. Drip Pans to be used whenever leaving equipment on site or parking overnight when not in use.
- .9 Parking of equipment on site to be on level ground in locations away from watercourses and as approved by Departmental Representative. Equipment with leaks or poor mechanical repair to be removed from site when so ordered by Departmental Representative.

1.10 SPILL CONTROL KIT

- .1 Contractor to have at the work site a spill control kit consisting of the following minimum types of equipment:
 - .1 a spaded shovel;
 - .2 a stable broom;
 - .3 a broad nosed shovel;
 - .4 a container(s) suitable, compatible to and of sufficient size to contain petroleum products being used with equipment;
 - .5 Absorbents;
 - .6 rags;
 - .7 metal container for soiled rags;
 - .8 Booms when working next to a watercourse that will traverse the width of the watercourse by two times; and
 - .9 Spill control kit to be inspected and approved by Wing Environment Office prior to Work commencing. Spill control kits to be available to Contractor employees at all areas where Work of the Contract is being performed and at all times during the course of the Contract.
 - .10 Contractor employees to be trained in the use of the spill control kit and the equipment they contain.

1.11 SPILLS

- .1 Disposal of spilled materials to be off the work site/property and at approved locations for materials to be disposed of.
- .2 When parking of equipment on site, the equipment is to be secured from entry, inspected for leaks and the ground protected from leaks.
- .3 Contractor to protect all wells, catch basins, drywells, drains and watercourses from contamination in event of a spill.
- .4 All equipment to be used for the Work of the Contract to be inspected by the Departmental Representative for leaks. Equipment not in good repair to be removed/repaired when directed by Departmental Representative.
- .5 Spills in excess of 74 litres to be reported immediately to Departmental Representative and the Newfoundland and Labrador Department of Environment and Conservation.
- .6 For spills occurring the Contractor to immediately remove as much or all of the contaminated soils created by the spill from Work of the Contractor as possible.
- .7 Contaminated soils/materials to be placed in containers compatible to the contaminants.
- .8 Any remaining clean-up to be performed at no extra cost to Canada. Clean-ups to be to the Departmental Representative's satisfaction.

1.12 POLLUTION CONTROL

- .1 Maintain temporary erosion and pollution control features installed under this contract.
- .2 Control emissions from equipment and plant to local authorities emission requirements.
- .3 Prevent sandblasting and other extraneous materials from contaminating air beyond application area, by providing temporary enclosures.
- .4 Cover or wet down dry materials and rubbish to prevent blowing dust and debris. Provide dust control for temporary roads and around entire construction site.
- .5 Maintain inventory of hazardous materials and hazardous waste stored on site. List items by product name, quantity and date when storage began.
- .6 Have emergency spill response equipment and rapid clean-up kit, appropriate to work, at site. Locate

adjacent to work and where hazardous materials are stored. Provide personal protective equipment as required for clean-up.

- .7 Report, to Federal and Provincial Department of the Environment, spills of petroleum and other hazardous materials as well as accidents having potential of polluting the environment. Also notify Departmental Representative and submit a written spill report to Departmental Representative within 24 hours of occurrence.
- .8 Provide a floating debris containment boom whenever any of the Contractors methods of work allow for the potential of floating debris.

1.13 WILDLIFE PROTECTION

- .1 Should nests of migratory birds in wetlands be encountered during work, immediately notify Departmental Representative for directives to be followed.
 - .1 Do not disturb nest site and neighbouring vegetation until nesting is completed.
 - .2 Minimize work immediately adjacent to such areas until nesting is completed.
 - .3 Protect these areas by following recommendations of Canadian Wildlife Service.

1.14 MEASUREMENT FOR PAYMENT

- .1 No separate measurements for payment shall be made for items under this section. Include costs for Environmental Procedures in the Lump Sum portion of the work on the Bid and Acceptance Form.

PART 2 - PRODUCTS

2.1 NOT USED

PART 3 - EXECUTION

3.1 NOT USED