



RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Bid Receiving Public Works and Government
Services Canada/Réception des soumissions Travaux
publics et Services gouvernementaux Canada
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British Columbia
V6Z 0B9
Bid Fax: (604) 775-9381

SOLICITATION AMENDMENT

MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada -
Pacific Region
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British C
V6Z 0B9

Title - Sujet Repaving Projects	
Solicitation No. - N° de l'invitation EZ899-172568/A	Amendment No. - N° modif. 002
Client Reference No. - N° de référence du client	Date 2017-03-14
GETS Reference No. - N° de référence de SEAG PW-\$PWY-019-7987	
File No. - N° de dossier PWY-6-39320 (019)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2017-03-17	Time Zone Fuseau horaire Pacific Daylight Saving Time PDT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Ngan, Ken (PWY)	Buyer Id - Id de l'acheteur pwy019
Telephone No. - N° de téléphone (604) 658-2755 ()	FAX No. - N° de FAX (604) 775-6633
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: CBSA - Pacific Highway Port of Entry/Abbotsford-Huntingdon Port of Entry - Surrey & Abbotsford, BC	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation No. - N° de l'invitation
EZ899-172568/A
Client Ref. No. - N° de réf. du client

Amd. No. - N° de la modif.
002
File No. - N° du dossier
pwy-6-39320

Buyer ID - Id de l'acheteur
pwy019
CCC No./N° CCC - FMS No/ N° VME

This Solicitation Amendment 002 is raised to incorporate Addendum 001.

Please find following Addendum 001.

Please note Addendum 001 Attachments can be viewed or downloaded on the buyandsell.gc.ca website.

All other terms and conditions remain unchanged.

Requisition No. EZ899-172568/A

The following changes in the tender documents are effective immediately. This addendum will form part of the Contract documents.

Answers (A) to Questions/Requests (Q) Received:

Q.1 At the site visit we discussed that there is a concrete slab under about a third of the parking lot at Pac Highway port of entry that doesn't show up on the drawings. How should we bid this item?

A.1 *The existing asphalt layer is to be stripped and removed, and a thicker layer of asphalt (min. 75mm) is to be placed over the existing concrete layer. See included Sketch 001 for area of parking lot with underlying concrete layer.*

Q.2 Regarding the cross sections for Pavement structure they are showing the base and sub-base to be repaired to depths "as required". How should we price this removal and grading work? Due to it being a lump sum contract we would have to assume that we are removing and replacing to bottom of sub-base and regrading at all locations. This will add quite a bit of money to the price if not clarified.

A.2 *For the Pacific Highway site (Sheet C002) - As indicated with different hatching and notes specifying the pavement structure details on Sheet 3, there are only two locations expected to require the asphalt pavement structures shown on Sheet 03 (C003):*

- *The widened areas where 176 Street meets Highway 15 – full pavement structure including asphalt, base, and subbase is required.*
- *Rounded corners on Secondary Inspection return lane – provide asphalt, and base and subbase gravel as required to repair soft areas and for levelling.*

For the Abbotsford-Huntingdon site (Sheet C001) - As indicated with different hatching and notes specifying the pavement structure details on Sheet 3, there are only two locations expected to require the asphalt pavement structures shown on Sheet 03 (C003):

- *The widened commercial lane areas at USA/Canada Border – full pavement structure including asphalt, base, and subbase is required.*
- *Intersection of Sumas Way and 1st Avenue - full pavement structure including asphalt, base, and subbase is required*

The remaining areas (majority of project area) are just to have existing asphalt removed, regrade base gravels to ensure drainage, and repave with thicknesses as noted.

- Q.3 The tender document doesn't clearly state what we are required to provide for bonding. Can you please confirm what type of bonding is required?
- A.3 *Refer to General Instructions - Construction Services - Bid Security Requirements, specifically G108 – Bid Security Requirements. This can be found at the following website link: <https://buyandsell.gc.ca/policy-and-guidelines/standard-acquisition-clauses-and-conditions-manual/5/R/R2710T/17>*
- Q.4 On the Concrete band structure detail it's showing us drilling a 600mm long bar 150mm deep into existing concrete/asphalt on both sides but there's only a 300mm slot to achieve this. From a constructability standpoint we feel like this can't be achieved?
- A.4 *May use 350mm long bar, 150mm deep into existing concrete with 50mm overlap.*
- Q.5 Is it possible to get an extension for a week? We are quite busy in our estimating department right now.
- A.5 *The tender has been extended by a week as requested. The revised closing date is now 14:00 PDT on March 17th, 2017, as per Amendment 001.*
- Q.6 Would you be able to provide the electrical as-built drawing for the Pacific Highway Port of Entry Site? As there are no electrical drawings available, we would like to get as-builts of the existing to price the electrical work required for relocating the lamp post and signage described on drawing A-03 and C002.
- A.6 *See included electrical as-built drawing E301 as requested.*
- Q.7 Could you please clarify the total # of traffic detector loops right on USA/Canada border at 28 176 Street, Surrey, BC (drawing is just showing reinstate existing traffic detector loops)?
- A.7 *There are three (3) traffic detector loops to be reinstated where noted on Drawing C002.*

Additional Clarifications:

Additional Clarification #1 – See included Sketch 002, labelling the sub-base/subgrade layer in the concrete pavement structure details on Sheet C004.

Additional Clarification #2 – See included colour copies of Sheets A-02 and A-04, to better show the suggested phasing (original drawings provided are in black and white).

END OF ADDENDUM