

Highway 430 – Climbing Lane in the Southeast Hills area
Gros Morne National Park, NL

APPENDIX 1 - COMBINED PRICE FORM

- 1) The prices per unit shall govern in establishing the Total Extended Amount. Any arithmetical errors in this Appendix will be corrected by Canada.
- 2) Canada may reject the bid if any of the prices submitted do not reasonably reflect the cost of performing the part of the work to which that price applies.

LUMP SUM

The Lump Sum Amount designates Work to which a Lump Sum Arrangement applies.

- (a) Work included in the Lump Sum Amount represents all work not included in the unit price table.

LUMP SUM AMOUNT (LSA) Excluding GST / HST

UNIT PRICE TABLE

- 1) The unit price table designates the Work to which a Unit Price Arrangement applies
 - (a) The Price per Unit and the Price must be entered for each Item Listed
 - (b) Work included in each item is as described in the referenced specification section

Item No.	Specification Reference	Class of Labour, Plant or Material	Unit of Measurement	Estimated Quantity	Price per Unit GST/HST Extra	Estimated Total Price GST/HST Extra
1	31 11 00	Clearing	ha	3.7		
2	31 23 10	Ditching	Hr	50.0		
3	31 23 10	Common Excavation	cu. m.	15,290		
4	31 23 16	Rock Excavation	cu. m.	43,970		
5	32 11 23	Granular "A" Base	tonne	6,530		
6	32 11 19	Granular "B" Sub-Base	tonne	18,180		
7	32 01 16	Asphalt Cold Milling	sq.m.	1,460		
8	32 01 16	Cutting of Asphalt Pavement	m	2,610		
9	32 12 13	Asphalt Tack Coat	sq.m.	1,460		
10	32 12 16	Hot Mix Asphalt Paving - Base Course	tonne	2,200		
11	32 12 16	Hot Mix Asphalt Paving - Surface Course	tonne	2,100		
12	32 12 16	Asphalt Cement	tonne	258		
13	32 12 16	Asphalt Gutter	m	900		
14	33 42 13	Culvert Replacement - Supply (900mm dia. CSP)	m	73		
15	33 42 13	Culvert Replacement - Install (900mm dia. CSP)	m	73		
16	33 42 13	New Culvert - Supply (900mm dia. CSP)	m	30		
17	33 42 13	New Culvert - Install (900mm dia. CSP)	m	30		
18	33 42 13	Culvert Extension - Supply (900mm dia CSP)	m	30		
19	33 42 13	Culvert Extension - Install (900mm dia CSP)	m	30		
20	33 42 13	Culvert Extension - Supply (1200mm dia CSP)	m	13		
21	33 42 13	Culvert Extension - Install (1200mm dia CSP)	m	13		

Highway 430 – Climbing Lane in the Southeast Hills area
Gros Morne National Park, NL

Item No.	Specification Reference	Class of Labour, Plant or Material	Unit of Measurement	Estimated Quantity	Price per Unit GST/HST Extra	Estimated Total Price GST/HST Extra
22	03 30 00	Cast-in-Place Reinforced Concrete Headwalls	cu. m.	18		
23	31 37 00	Rip-Rap (40 kg)	tonne	2,100		
24	33 46 19	Subdrain - Supply (200mm dia. CSP)	m	100		
25	33 46 19	Subdrain - Install (200mm dia. CSP)	m	100		
26	34 71 13	Guiderail Removal and Disposal	m	160		
27	34 71 13	Steel W-Beam Guide Rail - Supply (3.5 mm thick)	m	120		
28	34 71 13	Steel W-Beam Guide Rail - Install	m	120		
29	10 14 53	Sign Relocation (140x140mm posts)	each	2		
30	10 14 53	Sign Relocation (4 - 200x200mm posts)	each	1		
31	10 14 53	Supply of New Sign	each	2		
32	10 14 53	Installation of New Sign on 140x140mm Post	each	2		
33	32 17 23	Line Painting - Lane Lines	km	2.55		
34	32 92 21	Hydroseed	sq. m.	25,500		
TOTAL EXTENDED AMOUNT (TEA)						
Excluding GST / HST						

TOTAL BID AMOUNT

TOTAL BID AMOUNT (LSA + TEA) Excluding GST/HST
--

Please note: All fixed price items of the specification NOT designated in the unit price table above, are subject to a lump sum arrangement and should be included in the amount in subparagraph 1(a) of BA03