



RETURN BIDS TO:
 RETOURNER LES SOUMISSIONS À:

**Parks Canada Agency
 Mailroom
 30 Victoria Street
 Gatineau, Quebec, J8X 0B3**

Amendment #4

INVITATION TO TENDER
 APPEL D'OFFRES

Tender To: Parks Canada Agency
 We hereby offer to sell to Her Majesty the Queen in right of Canada, in accordance with the terms and conditions set out herein, referred to herein or attached hereto, the goods, services, and construction listed herein and on any attached sheets at the price(s) set out therefor.

Soumission aux: l'Agence Parcs Canada
 Nous offrons par la présente de vendre à Sa Majesté la Reine du Chef du Canada, aux conditions énoncées ou incluses par référence dans la présente aux annexes ci-jointes, les biens, services et construction énumérés ici et sur toute feuille ci-annexée, au(x) prix indiqué(s).

Vendor/Firm Name and Address
 Raison sociale et adresse du fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution

**Parks Canada Agency
 Mailroom
 30 Victoria Street
 Gatineau, Quebec, J8X 0B3**

Title-Sujet Highway 430 - Climbing lane in the Southeast Hills area - Gros Morne National Park, NL		Date 21 March, 2017
Solicitation No. - No. de l'invitation 5P300-17-5092	Client Ref. No. - No. de réf du client.	
GETS Reference No. - No de reference de SEAG		
Solicitation Closes L'invitation prend fin - at - à 02:00 PM on - le 2017-03-28	Time Zone Fuseau horaire - Eastern Daylight Time (EDT)	
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>		
Address Inquiries to: - Adresser toute demande de renseignements à : Patrick Sullivan at Patrick.Sullivan@pc.gc.ca		
Telephone No. - No de téléphone (819) 420-9557	Fax No. - No de FAX:	
Destination of Goods, Services, and Construction: Destinations des biens, services et construction: See Herein		
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur		
Name and title of person authorized to sign on behalf of the Vendor/Firm Nom et titre de la personne autorisée a signer au nom du fournisseur/ de l'entrepreneur		
Signature	Date	



AMENDMENT #4

THE PURPOSE OF THIS AMENDMENT IS TO POST QUESTIONS AND ANSWERS AND TO POST REVISED DOCUMENTS

QUESTIONS AND ANSWERS

1. **Q.** In Section 01 11 00, 1.1.4, on page 2 of 12, it refers to several other projects that will be ongoing at various locations during the time frame of this contract. Please provide details of these projects (i.e. Scope of Work, Location, Start Date and Completion Date)
A. Work shall be occurring at different areas throughout the Park as indicated. Work includes a mixture of Visitor Experience Projects as well as work on highways, which include:
 1. Baker's Brook Bridge Replacement (R430)
 - a. Start Date: Anytime
 - b. Completion Date: End of 2018
 2. Deer Arm Bridge Replacement (R430)
 - a. Currently out for tender
 - b. Completion Date: End of 2018
 3. Southeast Hill Climbing Lane Construction (R430)
 - a. Currently out for tender
 - b. Completion Date: June, 2018
 4. Southeast Brook Bridge Replacement (R430)
 - a. Work is temporary halted for winter
 - b. Completion Date: June, 2017.

The work mentioned herein is for reference purposes only. PCA shall not held responsible for any delays for this or future work not listed.

2. **Q.** Please clarify the requirements for maintaining traffic. Section 01 11 00 1.2.5 states "Ensure at least one lane of alternating two-way traffic at all times" and Section 01 11 00 1.19.6 states "Ensure two-way traffic is maintained at construction sites at all times".
A. To ensure limited disruptions to traffic, the contractor shall try and ensure two-way traffic is maintained at all times as the majority of work shall occur on the southbound shoulder of the existing highway. Therefore, Contractors shall plan work as a continuous operation limited to the new footprint of subgrade. Contractors shall not be permitted to perform continuous truck end-dumping at the edge of the existing shoulder as a means of climbing lane construction.



However, PCA understands that at times of construction there will need for one-lane closures (i.e.: culvert installations, blasting, periodical end-dumps, etc.) where traffic shall be controlled by flagpersons.

3. **Q.** Are there existing underground telephone cables along the road? Section 01 11 00, 1.10.1.4 Page 6 of 12, states “The contractor shall ensure that no damage will be done to any existing underground telephone cables.”
 - A. There are no buried telephone/fibre optic cables within this area.
4. **Q.** On Drawing C12, on the note at the left hand corner of the page, please clarify the station number shown as 7+80.
 - A. Within drawing notes on sheet C12, line seven (7) should read “STA. 7+960 – STA. 7+980” not, “STA. 7+960 – STA. 7+98”.
5. **Q.** Can excess excavated rock be used to crush granulars?
 - A. Yes. However the contractor will not be permitted to process granulars (‘A’ and ‘B’) on site. Excess rock shall be transported and processed at an alternate location selected by the contractor. Rock shall be weighed upon on arrival of processing site to confirm weight of material. In addition, the contractor shall be responsible for all testing of material to ensure the aggregate meets all parameters of the granular specifications.

Excess rock shall not be used for asphalt aggregate.

**ALL OTHER TERMS AND CONDITIONS OF THE ITT REMAIN
UNCHANGED**