

Part 1 General

1.1 RELATED REQUIREMENTS

- .1 Section 32 91 19.13 Topsoil Placement, Grading, and Capping
- .2 Section 01 33 00 - Submittal Procedures.
- .3 Section 01 35 29.06 - Health and Safety Requirements.
- .4 Section 31 05 16 - Aggregate Materials
- .5 Section 31 32 19.01 - Geotextile soil stabilization
- .6 Section 02 41 13 - Selective Site Demolition

1.2 MEASUREMENT PROCEDURES

- .1 Excavated materials and Backfilling with approved material will be measured in cubic metres in their original location.
 - .1 Excavation quantities measured will be actual volume removed within the following limits:
 - .1 Width for excavation as indicated in the statement of work (SOW).
 - .2 Depth from ground surface immediately prior to excavation, to depths identified in SOW as indicated by Departmental Representative.
 - .3 Includes placing, spreading/grading and compaction of all materials backfilled or placed.
- .2 Shoring, bracing, cofferdams, underpinning and de-watering of excavation will not be measured separately for payment.
- .3 Included under this section will be all tools, equipment required for either excavation or backfilling.
- .4 Mobilization and Demobilization of tool, equipment and supply and delivery of material will be paid under section 02 41 16. Includes loading and unloading.
- .5 Labour will be paid under bid items.
- .6 Transportation of excavated materials Hazardous or Non-Hazardous, to a Registered Waste Disposal Facilities, will be paid under section section 02 41 16. (Includes loading and unloading.)
- .7 Placing and spreading of topsoil will be measured for payment under section 32 91 19.13

1.3 REFERENCE STANDARDS

- .1 U.S. Environmental Protection Agency (EPA)/Office of Water
 - .1 EPA 832R92005, Storm Water Management for Construction Activities: Developing Pollution Prevention Plans and Best Management Practices.
- .2 Statement of Work to be provided on a site specific basis.

1.4 DEFINITIONS

- .1 Unclassified excavation: excavation of deposits of whatever character encountered in Work.
- .2 Topsoil:
 - .1 Material capable of supporting good vegetative growth and suitable for use in top dressing, landscaping and seeding.
 - .1 Material reasonably free from subsoil, clay lumps, brush, objectionable weeds, and other litter, and free from cobbles, stumps, roots, and other objectionable material larger than 25 millimeters in any dimension.
- .3 Waste material: excavated material unsuitable for use in Work or surplus to requirements.
- .4 Borrow material: material obtained from locations outside area to be graded, and required for construction of fill areas or for other portions of Work.
- .5 Recycled fill material: material, considered inert, obtained from alternate sources and engineered to meet requirements of fill areas.
- .6 Unsuitable materials:
 - .1 Weak, chemically unstable, and compressible materials.
 - .2 Frost susceptible materials:
 - .1 Fine grained soils with plasticity index less than 10 when tested to ASTM D4318, and gradation within limits specified when tested to ASTM D422 or ASTM C136: Sieve sizes to CAN/CGSB-8.1 or CAN/CGSB-8.2.
 - .2 Table:

Sieve Designation	% Passing
2.00 mm	100
0.10 mm	45 - 100
0.02 mm	10 - 80
0.005 mm	0 - 45

- .3 Coarse grained soils containing more than 20 % by mass passing 0.075 mm sieve.
- .7 Unshrinkable fill: very weak mixture of cement, concrete aggregates and water that resists settlement when placed in utility trenches, and capable of being readily excavated.

1.5 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Make submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Preconstruction Submittals:
 - .1 Submit construction equipment list for major equipment to be used in this section prior to start of Work.

- .2 Submit records of underground utility locates, indicating:
location plan of existing utilities as found in field, and
location plan of relocated and abandoned services, as required.
- .3 Samples:
 - .1 Submit samples in accordance with Section 01 33 00 - Submittal Procedures.
 - .2 Inform Departmental Representative at least 4 weeks prior to beginning Work, of proposed source of fill and/or topsoil materials and provide access for sampling.

1.6 QUALITY ASSURANCE

- .1 Qualification Statement: submit proof of insurance coverage for professional liability.
- .2 Submit design and supporting data at least 2 weeks prior to beginning Work.
- .3 Design and supporting data submitted to bear stamp and signature of qualified professional engineer registered or licensed in Territory or Province where Work is to be conducted, Canada.
- .4 Keep design and supporting data on site.
- .5 Engage services of qualified professional Engineer who is registered or licensed in the Province or Territory, which Work is to be carried out to design and inspect cofferdams, shoring, bracing and underpinning required for Work.
- .6 Do not use soil material until written report of soil test results are approved by Departmental Representative.
- .7 Health and Safety Requirements:
 - .1 Do construction occupational health and safety in accordance with Section 01 35 29.06 - Health and Safety Requirements.

1.7 WASTE MANAGEMENT AND DISPOSAL

- .1 Excavated soil is to be disposed of at a provincially approved disposal facility.
- .2 Obtain official approval for the disposal from the facility prior to removing soil from the site. They may request soil chemistry results and volumes prior to approving receipt and/or issuing any required Special Waste Permits. These are provided in the SOW.

1.8 EXISTING CONDITIONS

- .1 Site Access:
 - .1 Please note the site location is indicated in the SOW. Should access to the site be required via another land owner, permission will be required for site access.
 - .2 Minimize damage to any third party properties during work.
 - .3 Repair damage and reinstate areas impacted on third party properties to the satisfaction of the Departmental Representative immediately following damage and at the completion of site work related to this contract.

.2 Buried services:

- .1 Before commencing work establish location of buried services on and adjacent to site.
- .2 Arrange with appropriate authority for relocation of buried services that interfere with execution of work: pay costs of relocating services.
- .3 Remove obsolete buried services within 2 m of foundations: cap cut-offs.
- .4 Size, depth and location of existing utilities and structures as indicated are for guidance only. Completeness and accuracy are not guaranteed.
- .5 Prior to beginning excavation Work, notify applicable Departmental Representative. Have authorities having jurisdiction establish location and state of use of buried utilities and structures. Contractors are to clearly mark such locations to prevent disturbance during Work.
- .6 Confirm locations of buried utilities by careful test excavations/soil hydrovac methods.
- .7 Maintain and protect from damage, all water, sewer, gas, electric, telephone and other utilities and structures encountered.
- .8 Where utility lines or structures exist in area of excavation, obtain direction of Departmental Representative before removing or re-routing.
- .9 Record location of maintained, re-routed and abandoned underground lines.
- .10 Confirm locations of recent excavations adjacent to area of excavation.

.3 Existing buildings and surface features:

- .1 Conduct, with Departmental Representative, condition survey of existing buildings, trees and other plants, lawns, fencing, service poles, wires, rail tracks, pavement, survey bench marks and monuments which may be affected by Work.
- .2 Protect existing buildings and surface features from damage while Work is in progress. In event of damage, immediately make repair as directed by Departmental Representative.
- .3 Where required for excavation, cut roots or branches as directed by Departmental Representative.

Part 2 Products

2.1 MATERIALS

- .1 Type 1 and Type 2 fill: properties to Section 31 05 16 - Aggregate Materials and the following requirements:

- .1 Crushed, pit run or screened stone, gravel or sand.
- .2 Gradations to be within limits specified when tested to ASTM C136 or ASTM C117. Sieve sizes to CAN/CGSB-8.2 or CAN/CGSB-8.1.
- .3 Table:

Sieve Designation	% Passing	
Type 1	Type 2	
75 mm	-	100
50 mm	-	-
37.5 mm	-	-
25 mm	100	-
19 mm	75-100	-
12.5 mm	-	-
9.5 mm	50-100	-
4.75 mm	30-70	22-85
2.00 mm	20-45	-
0.425 mm	10-25	5-30
0.180 mm	-	-
0.075 mm	3-8	0-10

- .2 Type 3 fill: selected material from excavation or other sources, approved by Departmental Representative for use intended, unfrozen and free from rocks larger than 75 mm, cinders, ashes, sods, refuse or other deleterious materials.
- .3 Unshrinkable fill: proportioned and mixed to provide:
 - .1 Maximum compressive strength of 0.4 MPa at 28 days.
 - .2 Maximum cement content of 25 kg/m³ with by volume 40 fly ash replacement: to CSA-A3001, Type GU.
 - .3 Minimum strength of 0.07 MPa at 24 h.
 - .4 Concrete aggregates: to CSA-A23.1/A23.2.
 - .5 Cement: Type GU.
 - .6 Slump: 160 to 200 mm.
- .4 Shearmat: honeycomb type bio-degradable cardboard 100 mm thick, treated to provide sufficient structural support for poured concrete until concrete cured.
- .5 Geotextile soil stabilization: to Section 31 32 19.01 - Geotextile soil stabilization.

Part 3 Execution

3.1 TEMPORARY EROSION AND SEDIMENTATION CONTROL

- .1 Provide temporary erosion and sedimentation control measures to prevent soil erosion and discharge of soil-bearing water runoff or airborne dust to adjacent properties and walkways, according to authorities having jurisdiction.
- .2 Inspect, repair, and maintain erosion and sedimentation control measures during construction until permanent vegetation has been established.
- .3 Remove erosion and sedimentation controls and restore and stabilize areas disturbed during removal.

3.2 SITE PREPARATION

- .1 Remove obstructions, ice and snow, from surfaces to be excavated within limits indicated in SOW.
- .2 Cut pavement or sidewalk neatly along limits of proposed excavation in order that surface may break evenly and cleanly in accordance with Section 02 41 13 - Selective Site Demolition.
- .3 Remove other obstructions identified in the SOW (i.e., fencing, outside stairs, etc.) prior to excavation. These obstructions are to be returned to their original place and condition once work is completed. Note: if identified, outside stairs (with railing as required by code) to be replaced following remediation to fit new grades.
- .4 Minimum area to be excavated with backfill consisting of 0.3 m of compacted topsoil, and/or as indicated in the SOW.
- .5 Remove trees, bushes from surfaces to be excavated within limits as indicated by Departmental Representative.

3.3 PREPARATION/PROTECTION

- .1 Protect existing features in accordance with applicable local regulations.
- .2 Keep excavations clean, free of standing water, and loose soil.
- .3 Where soil is subject to significant volume change due to change in moisture content, cover and protect to Departmental Representative satisfaction.
- .4 Protect natural and man-made features required to remain undisturbed. Unless otherwise indicated or located in an area to be occupied by new construction, protect existing trees from damage.
- .5 Protect buried services that are required to remain undisturbed.

3.4 STRIPPING OF TOPSOIL

- .1 Remove sod/weeds and topsoil to depth indicated in SOW as directed by the Departmental Representative.
- .2 Place sod/weeds and topsoil directly in truck for offsite disposal at a provincially approved disposal facility.
- .3 Do not place excavated sod/weeds or topsoil on ground surface.

3.5 STOCKPILING

- .1 Stockpile fill materials in areas designated by Departmental Representative.
 - .1 Stockpile granular materials in manner to prevent segregation.
- .2 Protect fill materials from contamination.
- .3 Implement sufficient erosion and sediment control measures to prevent sediment release off construction boundaries and into water bodies.

3.6 COFFERDAMS, SHORING, BRACING AND UNDERPINNING

- .1 Maintain sides and slopes of excavations in safe condition by appropriate methods and in accordance with Section 01 35 29.06 - Health and Safety Requirements.
- .2 Obtain permit from authority having jurisdiction for temporary diversion of water course.
- .3 Construct temporary Works to depths, heights and locations as approved by DCC Representative.
- .4 During backfill operation:
 - .1 Unless otherwise indicated or directed by Departmental Representative, remove sheeting and shoring from excavations.
 - .2 Do not remove bracing until backfilling has reached respective levels of such bracing.
 - .3 Pull sheeting in increments that will ensure compacted backfill is maintained at elevation at least 500 mm above toe of sheeting.
- .5 When sheeting is required to remain in place, cut off tops at elevations as indicated.
- .6 Upon completion of substructure construction:
 - .1 Remove cofferdams, shoring and bracing.
 - .2 Remove excess materials from site and restore watercourses as directed by Departmental Representative.

3.7 DEWATERING AND HEAVE PREVENTION

- .1 Keep excavations free of water while Work is in progress.
- .2 Provide details of proposed dewatering or heave prevention methods, including dikes, well points, and sheet pile cut-offs to Departmental Representative for review.
- .3 Avoid excavation below groundwater table if quick condition or heave is likely to occur.
 - .1 Prevent piping or bottom heave of excavations by groundwater lowering, sheet pile cut-offs, or other means.
- .4 Protect open excavations against flooding and damage due to surface run-off.
- .5 Dispose of water in a manner not detrimental to public and private property, or portion of Work completed or under construction.
 - .1 Provide and maintain temporary drainage ditches and other diversions outside of excavation limits.
- .6 Provide flocculation tanks, settling basins, or other treatment facilities to remove suspended solids or other materials before discharging to storm sewers, watercourses or drainage areas.

3.8 EXCAVATION

- .1 Advise Departmental Representative at least 7 days in advance of excavation operations for initial cross sections to be taken.

- .2 Excavate to lines, grades, elevations and dimensions as directed by Departmental Representative.
- .3 Remove walks, demolished foundations and rubble, paving, masonry, concrete, and other obstructions encountered during excavation in accordance with Section 02 41 13 - Selective Site Demolition.
- .4 Excavation must not interfere with bearing capacity of adjacent foundations.
- .5 Do not disturb soil within branch spread of trees or shrubs that are to remain.
 - .1 If excavating through roots, excavate by hand and cut roots with sharp axe or saw.
- .6 For trench excavation, unless otherwise authorized by Departmental Representative in writing, do not excavate more than 30 m of trench in advance of installation operations and do not leave open more than 15 m at end of day's operation.
- .7 Keep excavated and stockpiled materials safe distance away from edge of trench as directed by Departmental Representative.
- .8 Restrict vehicle operations directly adjacent to open trenches.
- .9 Dispose of surplus and unsuitable excavated material off site at an approved facility.
- .10 Do not obstruct flow of surface drainage or natural watercourses.
- .11 Earth bottoms of excavations to be undisturbed soil, level, free from loose, soft or organic matter.
- .12 Notify Departmental Representative when bottom of excavation is reached.
- .13 Obtain Departmental Representative approval of completed excavation.
- .14 Remove unsuitable material from trench bottom including those that extend below required elevations to extent and depth as directed by Departmental Representative.
- .15 Correct unauthorized over-excavation as follows:
 - .1 Fill with clean topsoil or approved backfill material.
- .16 Hand trim, make firm and remove loose material and debris from excavations.
 - .1 Where material at bottom of excavation is disturbed, compact foundation soil to density at least equal to undisturbed soil.

3.9 FILL TYPES AND COMPACTION

- .1 Use types of fill as indicated or specified below. Compaction densities are percentages of maximum densities obtained from ASTM D698 or ASTM D1557 in accordance with Section 31 05 10 - Corrected Maximum Dry Density for Fill.
 - .1 Exterior side of perimeter walls: use Type 3 fill to subgrade level. Compact to 95% of corrected maximum dry density.

- .2 Within building area: use Type 2 to underside of base course for floor slabs. Compact to 100 % of corrected maximum dry density.
- .3 Under concrete slabs: provide 150 mm compacted thickness base course of Type 1 fill topped with shearmat filler as indicated to underside of slab. Compact base course to 100 %.
- .4 Retaining walls: use Type 2 fill to subgrade level on high side for minimum 500 mm from wall and compact to 95 %. For remaining portion, use Type 3 fill compacted to 95 %.
- .5 Place unshrinkable fill in areas as indicated.

3.10 BEDDING AND SURROUND OF UNDERGROUND SERVICES

- .1 Place and compact granular material for bedding and surround of underground services Section 33 41 00 - Storm Utility Drainage Piping as indicated or as specified in Section 33 31 13 - Public Sanitary Utility Sewerage Piping, Section 23 11 26 - Facility Liquid Petroleum Gas Piping, Section 33 11 16 - Site Water Utility Distribution Piping, and/or Section 33 34 00 - Sanitary Utility Sewerage Force Mains.
- .2 Place bedding and surround material in unfrozen condition.

3.11 BACKFILLING

- .1 Do not proceed with backfilling operations until completion of following:
 - .1 Departmental Representative has inspected and approved installations.
 - .2 Departmental Representative has inspected and approved of construction below finish grade.
 - .3 Inspection, testing, approval, and recording location of underground utilities.
 - .4 Removal of concrete formwork.
 - .5 Removal of shoring and bracing; backfilling of voids with satisfactory soil material.
- .2 Areas to be backfilled to be free from debris, snow, ice, water and frozen ground.
- .3 Do not use backfill material which is frozen or contains ice, snow or debris.
- .4 Place backfill material in uniform layers not exceeding 150 mm compacted thickness up to grades indicated. Compact each layer before placing succeeding layer.
- .5 Backfilling around installations:
 - .1 Place bedding and surround material as specified elsewhere.
 - .2 Do not backfill around or over cast-in-place concrete within 24 hours after placing of concrete.
 - .3 Place layers simultaneously on both sides of installed Work to equalize loading.
 - .4 Where temporary unbalanced earth pressures are liable to develop on walls or other structures:
 - .1 Permit concrete to cure for minimum 14 days or until it has sufficient strength to withstand earth and compaction

pressure and approval obtained from Departmental Representative.

- .2 If approved by Departmental Representative, erect bracing or shoring to counteract unbalance, and leave in place until removal is approved by Departmental Representative.
- .6 Place fill in areas as indicated.
- .7 Consolidate and level unshrinkable fill with internal vibrators.
- .8 Install drainage or filter system in backfill as indicated by Departmental Representative.
- .9 Backfill with topsoil as described in Section 32 91 19 13 Topsoil Placement, Grading and Capping.

3.12 RESTORATION

- .1 Upon completion of Work, remove waste materials and debris, trim slopes, and correct defects as directed by Departmental Representative.
- .2 Replace topsoil as directed by Departmental Representative.
- .3 Reinstate lawns to elevation which existed before excavation.
- .4 Reinstate pavements and sidewalks disturbed by excavation to thickness, structure and elevation which existed before excavation.
- .5 Clean and reinstate areas affected by Work as directed by Departmental Representative.
- .6 Use temporary plating to support traffic loads over unshrinkable fill for initial 24 hours.
- .7 Protect newly graded areas from traffic and erosion and maintain free of trash or debris.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Section 31 23 33.01 - Excavation, Trenching and Backfilling.
- .2 Section 01 33 00 - Submittal Procedures

1.02 REFERENCES

- .1 ASTM International
 - .1 ASTM A 123/A 123M-09, Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products.
 - .2 ASTM D 4491-99a(2009), Standard Test Methods for Water Permeability of Geotextiles by Permittivity.
 - .3 ASTM D 4595-09, Standard Test Method for Tensile Properties of Geotextiles by the Wide-Width Strip Method.
 - .4 ASTM D 4716-08, Standard Test Method for Determining the (In-Plane) Flow Rate Per Unit Width and Hydraulic Transmissivity of a Geosynthetic Using a Constant Head.
 - .5 ASTM D 4751-04, Standard Test Method for Determining Apparent Opening Size of a Geotextile.
- .2 Canada Green Building Council (CaGBC)
 - .1 LEED Canada-NC Version 1.0-2004, LEED (Leadership in Energy and Environmental Design): Green Building Rating System Reference Package For New Construction and Major Renovations (including Addendum 2007).
 - .2 LEED Canada-CI Version 1.0-2007, LEED (Leadership in Energy and Environmental Design): Green Building Rating System Reference Guide For Commercial Interiors.
- .3 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-4.2 No. 11.2-2004, Textile Test Methods - Bursting Strength - Ball Burst Test (Extension of September 1989).
 - .2 CAN/CGSB-148.1, Methods of Testing Geotextiles and Complete Geomembranes.
 - .1 No.2-M85, Methods of Testing Geosynthetics - Mass per Unit Area.
 - .2 No.3-M85, Methods of Testing Geosynthetics - Thickness of Geotextiles.
 - .3 No.6.1-93, Methods of Testing Geotextiles and Geomembranes - Bursting Strength of Geotextiles Under No Compressive Load.
 - .4 No.7.3-92, Methods of Testing Geotextiles and Geomembranes - Grab Tensile Test for Geotextiles.
 - .5 No. 10-94, Methods of Testing Geosynthetics - Geotextiles - Filtration Opening Size.
- .4 CSA International
 - .1 CSA G40.20/G40.21-04(R2009), General Requirements for Rolled or Welded Structural Quality Steel/Structural Quality Steel.
- .5 Ontario Provincial Standard Specifications (OPSS)
 - .1 OPSS 1860-November 2010, Material Specification for Geotextiles.

1.02 MEASUREMENT FOR PAYMENT

- .1 Measure supply and installation of geotextiles in square meters of surface covered by material. No allowance will be made for secure pins and overlaps.

1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for geotextiles and include product characteristics, performance criteria, physical size, finish and limitations.

1.04 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Storage and Handling Requirements:
 - .1 Store materials off ground in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect geotextiles from direct sunlight and UV rays.
 - .3 Replace defective or damaged materials with new.
- .3 Packaging Waste Management: as specified in Construction Waste Management Plan.

2 PRODUCTS

2.01 MATERIAL

- .1 Geotextile: woven synthetic fibre fabric, supplied in rolls.
 - .1 Width: 2 m minimum.
 - .2 Seam: Minimum of 1m seam with at least 300mm of geotextile on both sides of seam.
 - .3 Composed of: minimum 85% by mass of polypropylene, polyester with inhibitors added to base plastic to resist deterioration by ultra-violet and heat exposure for 60 days.
- .2 Physical properties:
 - .1 Thickness: to CAN/CGSB-148.1, No.3.
 - .2 Mass per unit area: to CAN/CGSB-148.1, No.2.
 - .3 Tensile strength and elongation in any principal direction: to ASTM D 4595.
 - .1 Tensile strength: minimum 400 N, wet condition.
 - .2 Elongation at break: maximum 25%.
 - .3 Seam strength: equal to or greater than tensile strength of fabric.
 - .4 Grab tensile strength and elongation: to [CAN/CGSB-148.1, No.7.3].
 - .1 Breaking force: minimum 200 N, wet condition.
 - .2 Elongation at future: maximum 50%.
- .3 Hydraulic properties:

- .1 Apparent opening size (AOS): to ASTM D 4751.
- .2 Filtration opening size (FOS): to CAN/CGSB-148.1 No.10.
- .3 Transmissivity: to ASTM D 4716.
- .4 Permittivity: to ASTM D 4491 pers.

- .4 Securing pins and washers: to CSA G40.21, Grade 300W, hot-dipped galvanized with minimum zinc coating of 600 g/m² to ASTM A 123/A 123M.

- .5 Factory seams: sewn in accordance with manufacturer's recommendations.

- .6 Thread for sewn seams: equal or better resistance to chemical and biological degradation than geotextile.

3 EXECUTION

3.01 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for geotextile material installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied.

3.02 INSTALLATION

- .1 Place geotextile material by unrolling onto graded surface in orientation, manner and locations indicated and retain in position with secure pins or an approved alternative.

- .2 Place geotextile material smooth and free of tension stress, folds, wrinkles and creases.

- .3 Place geotextile material on sloping surfaces in one continuous length from toe of slope to upper extent of geotextile.

- .4 Overlap each successive strip of geotextile 600 mm over previously laid strip.

- .6 Pin successive strips of geotextile with securing pins.

- .7 Protect installed geotextile material from displacement, damage or deterioration before, during and after placement of material layers.

- .8 After installation, cover with overlying layer within 4 hours of placement.

- .9 Replace damaged or deteriorated geotextile to approval of Departmental Representative.

- .10 Place and compact soil layers in accordance with Section 31 23 33.01 - Excavating, Trenching and Backfilling.

3.03 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.

3.04 PROTECTION

- .1 Vehicular traffic not permitted directly on geotextile.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Section 31 23 33.01 - Excavation, Trenching and Backfilling.
- .2 Section 01 33 00 - Submittal Procedures

1.01 DESCRIPTION

- .1 The section consists of the supply, installation, maintenance and removal of sediment control fence.

1.02 MEASUREMENT FOR PAYMENT

- .1 Measure Supply, Installation of Sediment Control fence in linear meters installed, as specified under this section.
 - .1 Maintenance of Sediment Control Fence will be incidental to this section.

1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for geotextiles and include product characteristics, performance criteria, physical size, finish and limitations.

1.04 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Storage and Handling Requirements:
 - .1 Store materials off ground in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect geotextiles from direct sunlight and UV rays.
 - .3 Replace defective or damaged materials with new.
- .3 Packaging Waste Management: as specified in Construction Waste Management Plan.

2 PRODUCTS

2.01 MATERIAL

- .1 All materials shall be supplied by the Contractor.
- .2 The fence may be prefabricated or constructed on site from the specified

components.

- .3 The fabric shall conform to the requirements of 601.2, Type W1, geotextile.
- .4 Wooden, Metal or Synthetic Post or Stake, minimum 1200mm long.

3 EXECUTION

3.01 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for geotextile material installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied.

3.02 INSTALLATION

- .1 The Contractor shall carry out the Work as indicated in the Contract Documents and/or as specifically directed by the Departmental Representative.
- .2 The sediment control fence shall be installed as per manufacturer's instructions or as specified by the Departmental Representative.
 - .1 In areas of potential sheet flow runoff, where construction activity cause the drainage run-off to transport sediment(s), the Contractor shall ensure that sediment control fences are properly located for effective runoff control.
 - .2 The Contractor will install sediment control fences, after consultation and agreement with the Departmental Representative.
- .3 The Contractor shall maintain the sediment control fence in a functional condition continuously from the time of installation until the completion of the Contract or removal.
- .4 The Contractor shall inspect all sediment control fences after each rainfall and at least daily during periods of prolonged rainfall.
- .5 The Contractor shall immediately repair any damage to sediment control fences or parts thereof.
- .6 The Contractor shall remove retained sediment prior to it having accumulated to a level approximately but not exceeding one-half the height of the fence, and this sediment shall be disposed of at a location at least 30m away from any watercourse, and in such a manner that the sediment will not be returned to the Work Area or the watercourse; or
 - .1 Subject to the Departmental Representative, the Contractor may install a second, back-up sediment control fence.

- .7 The Contractor shall remove all sediment control fence and the time of such removal shall be subject to the Departmental Representative's approval, but in cases shall occur prior to the completion of the Contract.
 - .1 Sediment Control Fence removed shall become the property of the Contractor and shall be disposed of outside of Work site, at a Registered Disposal Site.
 - .2 If the Departmental Representative notifies the Contractor in writing, prior to the completion of the Contract, that all or any part of the sediment control fence is to remain in place, the Contractor shall be deemed to have completed his obligations for that portion of the sediment control fence, under this item and the sediment control fence shall become the property of the Owner.
- .8 At the time of removal, the Contractor shall excavate any remaining sediment and dispose of it at a location at least 30m from any watercourse, and in such a manner that the sediment will not be returned to the Work Area or the watercourse and shall dress and seed the area of the removed fence and sedimentation, to the satisfaction of the Departmental Representative.

3.03 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.

END OF SECTION