



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

**Bid Receiving Public Works and Government
Services Canada/Réception des soumissions Travaux
publics et Services gouvernementaux Canada**
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British Columbia
V6Z 0B9
Bid Fax: (604) 775-9381

**SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Questions sur la soumission :
Carolyn Arthur
Agente des contrats
Courriel : Carolyn.Arthur@pwgsc.gc.ca
Tél. : 604-364-2752

Vendor/Firm Name and Address

**Raison sociale et adresse du
fournisseur/de l'entrepreneur**

Issuing Office - Bureau de distribution

Public Works and Government Services Canada -
Pacific Region
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British C
V6Z 0B9

Title - Sujet Réaménagement du Port de Bedwell	
Solicitation No. - N° de l'invitation EZ899-173002/A	Amendment No. - N° modif. 001
Client Reference No. - N° de référence du client	Date 2017-04-18
GETS Reference No. - N° de référence de SEAG PW-\$PWY-022-8038	
File No. - N° de dossier PWY-6-39387 (022)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2017-05-10	
Time Zone Fuseau horaire Pacific Daylight Saving Time PDT	
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Arthur (PWY), Carolyn	Buyer Id - Id de l'acheteur pwy022
Telephone No. - N° de téléphone (604) 364-2752 ()	FAX No. - N° de FAX (604) 775-6633
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: CBSA - Bedwell Harbour - South Pender Island, BC	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation No. - N° de l'invitation

EZ899-173002

Amd. No. - N° de la modif.

001

Buyer ID - Id de l'acheteur

pw022

Client Ref. No. - N° de réf. du client

File No. - N° du dossier

CCC No./N° CCC - FMS No./N° VME

PWY-6-3987

Les documents français seront disponibles sur demande.

Amendment 001 has been raised to incorporate Addendum # 01

1) Please see the attached Addendum #01.

All other terms and conditions remain unchanged.

The following changes /clarifications in the tender documents are effective immediately.
This addendum will form part of the contract documents.

1. Specifications:
 - 1.1 01 11 05 – Marine General Instructions
 - 1.1.1 Remove: Clause 1.4.1 "...excluding the Canadian Border Service Agency (CBSA) office."
 - 1.1.2 Add: Clause 1.14.2 "provide office space for use by the Departmental Representatives."
 - 1.1.3 Renumber existing Clauses 1.14.1.1, 1.14.1.2, and 1.14.1.3 with their subclauses to Clauses 1.14.2.1, 1.14.2.2, and 1.14.2.3
 - 1.1.4 Add: Clause 1.14.3.1 "Portable washroom facilities are to be provided for the use of CBSA employees and limited use by the public for the duration of the work to be conducted on the Approach (removal and replacement). The portable washroom facilities are to be placed at the CBSA office."
 - 1.1.5 Add Clause 1.14.3.2 "Portable washroom facilities are to be serviced at even intervals at least 4 times per week. Servicing is to include cleaning and providing a supply of toilet paper and hand sanitizer adequate for at least 3 days use without restocking."
 - 1.1.6 Remove: Clause 1.15.1 "Complete work within 12 weeks of contract award."
 - 1.1.7 Add: Clause 1.15
 - "1.15.1 Complete approach work (removal and replacement) by June 30, 2017. Work is to start from offshore and work towards inshore.
 - 1.15.1.1 All approach and office platform work, with the exception of the electrical, bearing pile, and removal / replacement of the gangway, is to be completed by June 30, 2017.
 - 1.15.1.2 The contractor is to remove all equipment, materials, debris, and any temporary facilities including the portable washroom facilities by June 30, 2017.
 - 1.15.1.3 The contractor will have no access to the site from July 1 to September 6, 2017.
 - 1.15.2 Commence all other work including installation of the floats and piles starting September 7, 2017. Complete work by November 3, 2017."
 - 1.1.8 Remove: Clause 1.17.1.1. "...One (1) construction sign to be:"
 - 1.1.9 Remove: Clause 1.17.1.1.1
 - 1.1.10 Remove: Clause 1.17.1.1.2
 - 1.1.11 Remove: Clause 1.17.1.1.3
 - 1.1.12 Add: Clause 1.17.1.1.1 "One (1) notice of closure. Size to be determined by Contractor."
 - 1.1.13 Add: Clause 1.17.1.1.2 "One (1) construction sign"
 - 1.1.14 Add: Clause 1.17.1.1.2.1 "Plywood and framing for sign to be 1.2m x 2.4m."
 - 1.1.15 Add: Clause 1.17.1.1.2.2 "Mounting to be on the outside of the guardrail near the office building, refer to drawings. The location to be confirmed by

- the Departmental Representative.”
- 1.1.16 Add: Clause 1.17.1.1.2.3 “One vinyl sign with an adhesive back will be provided to the Contractor to be applied to the plywood.”
- 1.1.17 Adjust subsequent sub-clauses
- 1.1.18 Add to Clause 1.17.4 “Contractor to maintain an 11 m clear space on the sea side of Float C for tie-up of a CBSA vessel. Install 4 temporary cleats for tie-up of this vessel. These cleats will become the contractor’s at the end of the work. Maintain a clear path for CBSA staff to access Float B from their vessel.”
- 1.1.19 Add: Clause 1.17.5.1 “The Departmental Representative will invite the CBSA site superintendent to attend the contractor’s first site orientation at the start of the approach work. Contractor to confirm the time of this meeting 2 business days in advance. At this meeting, the CBSA site superintendent will provide a short briefing of CBSA operational procedures on site, including identification of some of the potentially hazardous interactions the CBSA Officers may be dealing with at the site.”
- 1.1.20 Add: Clause 1.17.5.2 “Due to the potential sensitive and personal nature of the interactions between the CBSA staff and the travelling public, construction personnel should make every reasonable effort not to interfere with the border process (including overhearing of conversations).”
- 1.1.21 Add: Clause 1.17.5.3 “As construction personnel are within the CBSA areas, their actions and language content of conversation will be a direct reflection on the CBSA. Be mindful that the travelling public will be aware of your presence and act professionally at all times.”
- 1.1.22 Add: Clause 1.17.5.4 “Construction personnel shall not have any interactions with the travelling public.”
- 1.1.23 Add: Clause 1.17.5.5 “Construction personnel are to obey uniformed CBSA officers at all times for matters of safety and security. The uniformed CBSA officers do not have authority to change the requirements and conditions of the construction contract. If the contractor considers they have received an instruction from a uniformed officer which changes the conditions of the construction contract, this is to be reported to the PSPC Departmental Representative as soon as possible and not later than 1 business day after the instruction.”
- 1.2 01 35 43 Environmental Procedures
- 1.2.1 Add: Clause 1.1.5 “Contractor to provide the Departmental Representative all information required for the Departmental Representative to submit the web-based DFO Notice of Project.”
- 1.2.2 Remove and replace: Clause 1.4.1.1 with: “Provide documentation with respect to recycling/landfill site and disposal in accordance with Section 35 05 51.”
- 1.2.3 Remove and Replace Clause 1.6.2 with “If the Work is to occur outside the work windows above, a Qualified Environmental Professional / Environmental Monitor must supervise the Work.”
- 1.2.4 Adjust subsequent sub-clauses
-

- 1.3 01 33 00 – Shop Drawings, Product Data and Samples
 - 1.3.1 Remove: Clause 1.4.9
 - 1.3.2 Remove and replace: Clause 1.4.11.1 with: “Provide documentation with respect to recycling/landfill site and disposal in accordance with Section 35 05 51.”
 - 1.3.3 Adjust subsequent sub-clauses
- 1.4 01 52 00 – Construction Facilities
 - 1.4.1 Remove: Clause 1.7
 - 1.4.2 Remove and Replace: Clause 1.10 “Protection and Maintenance of Traffic (Vehicle and Pedestrian)” with “Protection and Maintenance of Traffic (Vehicle, Pedestrian, Marine and Air)”.
 - 1.4.3 Adjust subsequent sub-clauses
- 1.5 26 05 01 – Common Work Results for Electrical
 - 1.5.1 Remove and Replace: Clause 1.4.1 “...the Owner’s...” with “...the Department’s...”
 - 1.5.2 Remove and Replace: Clause 1.6.7 “...the Owner...” with “...Canada...”
 - 1.5.3 Remove and Replace: Clause 1.15.1.9 “...the Owner...” with “...Canada...”
 - 1.5.4 Remove and Replace: Clause 1.15.1.11 “...the Owner...” with “...Canada...”
 - 1.5.5 Remove and Replace: Clause 1.17.2.8.4 “...the Owner...” with “...Canada...”
 - 1.5.6 Remove and Replace: Clause 2.8.3 “...the Owner...” with “...Canada...”
- 1.6 31 62 16.19 – Steel Pipe Piles
 - 1.6.1 Remove and Replace: Clause 1.1.6 “...in Appendix C.” with “...in Appendix B.”
 - 1.6.2 Remove and Replace: Clause 2.1.3.2 “32 MPa” with “50 MPa”.
 - 1.6.3 Remove and Replace: Clause 3.4.2.5.3 “...specified strength.” With “...50% of the specified strength, 25 MPa.”
- 1.7 35 05 51 – Marine General Sitework
 - 1.7.1 Remove: Clause 2.4.5.1 “...and approach stringers, fishplates”
 - 1.7.2 Add: Clause 2.4.6.1 “...approach stringers, and fishplates.”
 - 1.7.3 Remove: Clause 2.5, in its entirety
 - 1.7.4 Add: Clause 2.15 “Neoprene Washer
 - .1 Material: Neoprene with Reinforcing Cloth
 - .2 Shape: round, unless specified to be square
 - .3 Size: as from the table below, unless specified otherwise:

Neoprene Washer Dimensions		
Bolt Size	Thickness	Outside Diameter
19.1mm	6mm	75mm
25.4mm	6mm	87mm

- .4 Bore holds to provide driving fit"

- 1.7.5 Remove: Clause 3.2: "not including fumigant"
- 1.7.6 Remove: Clause 3.3, in its entirety
- 1.7.7 Add: Clause 3.6.1 "...arriving on site for the float installation. Floats to be installed after Sept 7, 2017."
- 1.7.8 Remove and revise: Clause 3.6.2.4 from "...pile D7..." to "...pile D6..."
- 1.7.9 Add: Clause 3.7.2.1 "Each incremental load to be held for sufficient time to allow for an accurate (+/- 3mm) measurement of the deflection."
- 1.7.10 Add: Clause 3.7.7 "Load shall be held for 1 minute."
- 1.7.11 Add: Clause 3.7.8 "Provide Departmental Representative a report summarizing the test results within 2 days of conducting the tests."
- 1.7.12 Remove: Clause 3.8.6
- 1.7.13 Add: Clause 3.20 "Float to Float Connection"
 - 1.7.13.1 U-bolt connection through bolt to be tighten, but not over torqued.
- 1.7.14 Adjust subsequent sub-clauses
- 1.8 Preliminary Hazard Assessment Form
 - 1.8.1 Chemical Hazards, Other: Remove 'fumigants'

2 Drawings

- 2.1 Structural S03 of S12
 - 2.1.1 Refer to revised drawing, attached.
- 2.2 Structural S04 of S12
 - 2.2.1 Refer to revised drawing, attached.
- 2.3 Structural S05 of S12
 - 2.3.1 Refer to revised drawing, attached.
- 2.4 Structural S06 of S12
 - 2.4.1 Refer to revised drawing, attached.
- 2.5 Structural S07 of S12
 - 2.5.1 Refer to revised drawing, attached.
- 2.6 Structural S09 of S12
 - 2.6.1 Refer to revised drawing, attached.
- 2.7 Structural S10 of S12
 - 2.7.1 Refer to revised drawing, attached.
- 2.8 Structural S11 of S12
 - 2.8.1 Refer to revised drawing, attached.
- 2.9 Structural E03 of E06
 - 2.9.1 Add: Note 5 to luminaire on west end of Float B.
 - 2.9.2 Remove: #14 conductors on the inside and outside of the Office building and revise: to #12 conductors (consistent with 26 05 01 – Common Work Results for Electrical, Clause 2.10.)
- 2.10 Structural E05 of E06
 - 2.10.1 Section A: Luminaire base plate shown in wrong location. Is as shown in Drawings E04 of E06, side view

- END OF ADDENDUM -