

STEEL SCHEDULE AND CONCRETE QUANTITIES



ALTERNATIVE "C"	DECK & CURB	COMPOSITE DECK & CURBS	PIERS	ABUTMENTS-CURBS & PYLONS	LOCATION	STEEL SCHEDULE AND CONCRETE QUANTITIES	
						CU YDS CONC.	LES. REIN.
337	71,640	34,300	515	196	12024	STANDARD BARS	
						NO. SIZE	LENGTH
						64	6 10.9
						8	6 10.5
						8	6 9.6
						12	6 9.5
						8	6 8.7
						8	6 7.8
						8	6 6.9
						64	6 6.3
						62	6 6.0
						8	6 5.0
						8	6 4.1
						168	6 4.0 A
						20	5 25.9
						80	5 24.9
						8	5 14.0
						4	5 12.6
						4	5 12.2
						4	5 10.2
						4	5 7.0
						32	5 5.9
						4	5 5.6
						12	4 12.9
12	4 4.0						
16	11 28.0						
40	11 14.0						
64	9 42.6						
44	9 11.6						
64	9 7.0						
12	6 36.0						
4	6 31.6						
48	6 19.6						
48	6 14.6						
16	6 12.0						
10	6 11.0						
96	6 6.9						
8	6 25.0						
16	5 35.6						
48	5 31.6						
4	4 3.6						
756	1/4" 9' of 1/4" Dia						
60	8 8.8						
496	5 9.0						
972	5 25.0						
286	5 21.0						
468	4 41.0						
12	4 15.7						
84	4 12.0						
12	4 10.9						
12	4 8.2						
24	7 42.0						
968	7 3.0						
48	5 25.0						
240	4 28.0						
240	4 31.0						
534	4 40.5						
12	4 15.7						
84	4 12.0						
12	4 10.9						
12	4 8.2						
240	4 17.9						
240	4 20.0						
400	4 17.5						
340	4 22.0						
516	5 5.6						
360	5 6.1						
402							
403							
404							
302							

BENDING DIMENSIONS
ALL DIMENSIONS ARE OUT TO OUT

NOTE - Steel schedule for Alternative "C" does not include precast stringer reinforcement. See contractors dwgs 267-1 & 267-2

Revised to conform with dwg. No. 5.C	Jan 28/58
△ Bent bars marked △ omitted	Jan 28/58
△ Total lbs. Reinf. revised on schedule	Oct. 28/56
△ Bars added on schedule	Oct. 18 - 56
REVISIONS	DATE

<u>DEPARTMENT OF PUBLIC WORKS</u> CANADA DEVELOPMENT ENGINEERING BRANCH STRUCTURES DIVISION	
<u>OTTERTAIL RIVER BRIDGE</u> YOHO NATIONAL PARK B.C. M.12.9	
<u>ABUTMENTS</u> <u>REINFORCING</u>	

JOB SUPERVISOR J. C. BEAUCHAMP	DESIGN G. L. GLOIS
APPROVED DATE 27/8/58	DRAWN W. L.
 CHIEF STRUCTURES DIVISION	CHECKED J. C. B.
	PROJECT NO. NP 10 - 21 - 34
APPROVED DATE 27-1-16	SHEET 3 OF 6
 CHIEF ENGINEER	