



ADDENDUM No. 3

Project: 5P201-17-5006 - Butler's Barracks

Project #: 15-075-02 (ERA)

Prepared By: Shelley Ludman

Date Issued:

May 12, 2017.

THIS ADDENDUM FORMS PART OF CONTRACT DOCUMENTS AND IS TO BE READ, INTERPRETED, AND COORDINATED WITH ALL OTHER PARTS. THE COST OF ALL CONTAINED HEREIN IS TO BE INCLUDED IN THE CONTRACT SUM. THE FOLLOWING REVISIONS SUPPLEMENT AND/OR SUPERSEDE THE INFORMATION CONTAINED IN THE ORIGINAL DRAWINGS AND SPECIFICATIONS ISSUED FOR THE ABOVE NAMED PROJECT TO THE EXTENT REFERENCED, AND SHALL BECOME PART THEREOF. ACKNOWLEDGE RECEIPT OF THIS ADDENDUM BY INSERTING ITS NUMBER AND DATE ON THE TENDER FORM. FAILURE TO DO SO MAY SUBJECT THE BIDDER TO DISQUALIFICATION.

1.1. DRAWINGS

1.1.1. A001 - Add general note:

- "Unless absolutely necessary, mechanical and electrical system routing is to avoid permanent damage to heritage fabric, i.e. avoid drilling into historic timbers, boards, etc. If uncertain, bring to the attention of the Project Manager or Designate before proceeding with the work."

1.1.2. A201 - Additional removals scope:

- Remove and salvage both existing gates found on the interior side of the ground floor doors; hand over to owner.
- Remove wood mantle and hand over to owner. Fill fastener holes in brick and refinish.

1.2. SPECIFICATIONS

1.2.1. Remove specification section 04 03 06.01 *Interior Heritage Masonry Cleaning*

END OF ADDENDUM #1