

1 REFERENCES

- .1 Canadian Standards Association (CSA)
 - .1 CAN/CSA Z321-96 (R2006), Signs and Symbols for the Workplace.
- .2 National Research Council Canada
 - .1 NRCC NBCC-2015, National Building Code of Canada.
 - .2 NRC Canadian Fire Code, National Fire Code of Canada 2015.

2 MINIMUM STANDARDS

- .1 Materials shall be new and work shall conform to the minimum applicable standards of the Canadian General Standards Board, the Canadian Standards Association, the NRCC NBCC-2015 and all applicable Provincial and Municipal codes. In the case of conflict or discrepancy the most stringent requirement shall apply.

3 TAXES

- .1 Pay all taxes properly levied by law (including Federal, Provincial and Municipal).

4 FEES, PERMITS, AND CERTIFICATES

- .1 Pay all fees and obtain all permits. Provide authorities with plans and information for acceptance certificates. Provide inspection certificates as evidence that work conforms to requirements of Authority having jurisdiction.

5 FIRE SAFETY REQUIREMENTS

- .1 Comply with both the NRCC NBCC-2015 (NBC) and the NRC Canadian Fire Code (NFC) for safety of persons in buildings in the event of a fire and the protection of buildings from the effects of fire, as follows:
 - .1 The NBC: for fire safety and fire protection features that are required to be incorporated in a building during construction.
 - .2 The NFC:
 - .1 The on-going maintenance and use of the fire safety and fire protection features incorporated in buildings.
 - .2 The conduct of activities that might cause fire hazards in and around buildings.
 - .3 The establishment of fire safety plans.
 - .4 Fire safety at construction and demolition sites.
- .2 Welding and cutting:
 - .1 Before welding, soldering, grinding and/or cutting work, obtain a permit as directed by the Departmental Representative. Store flammable liquids in approved CSA containers.
 - .2 At least one week prior to commencing cutting, welding or soldering procedure, provide to Departmental Representative:
 - .1 Notice of intent, indicating devices affected, time and duration of isolation or bypass.
 - .2 Completed welding permit as defined in NFC.
 - .3 Return welding permit to Departmental Representative immediately upon completion of procedures for which permit was issued.
- .3 "Fire Watchers" as described in NFC shall be assigned when welding or cutting operations are carried out in areas where combustible materials within 15 m may be ignited by conduction or radiation.

5 FIRE SAFETY
REQUIREMENTS
(Cont'd)

- .4 Where work requires interruption or cause activation of fire alarms or fire suppression, extinguishing or protection systems:
- .1 Provide "Watchman Service" as described in NFC; In general, watchman service is defined as an individual conversant with "Fire Emergency Procedures", performing fire picket duty within an unprotected and unoccupied (no workers) area once per hour.
 - .2 Retain services of manufacturer for fire protection systems on daily basis or as approved by Departmental Representative, to isolate and protect all devices relating to:
 - .1 Modification of fire alarms, fire suppression, extinguishing or protection systems; and/or
 - .2 Cutting, welding, soldering or other construction activities that might activate fire protection systems.
 - .3 Immediately upon completion of work, restore fire protection systems to normal operation and verify that all devices are fully operational.
 - .4 Inform fire alarm system monitoring agency and local Fire Department immediately prior to isolation and immediately upon restoration of normal operation.

6 FIELD QUALITY
CONTROL

- .1 Carry out Work using qualified licenced workers or apprentices in accordance with Provincial Act respecting manpower vocational training and qualification.
- .2 Permit employees registered in Provincial apprenticeship program to perform specific tasks only if under direct supervision of qualified licenced workers.
- .3 Determine permitted activities and tasks by apprentices, based on level of training attended and demonstration of ability to perform specific duties.

7 HAZARDOUS
MATERIALS

- .1 Comply with the requirements of the Workplace Hazardous Materials Information System (WHMIS) regarding use, handling, storage, and disposal of hazardous materials; and regarding labelling and the provision of Material Safety Data Sheets (MSDS).
- .2 For work in occupied buildings give the Departmental Representative 1 week notice for work involving designated substances (Ontario Bill 208) and before painting.

8 REMOVED
MATERIALS

- .1 Unless otherwise specified, materials for removal become the Contractor's property and shall be taken from site.

9 PROTECTION

- .1 Protect finished work against damage until take-over.
- .2 Protect adjacent work against the spread of dust and dirt beyond the work areas.
- .3 Protect operatives and other users of site from all hazards.

10 USE OF SITE AND FACILITIES

- .1 Execute work with least possible interference or disturbance to the normal use of premises. Make arrangements with Departmental Representative to facilitate work as stated.
- .2 Maintain existing services to building and provide for personnel and vehicle access.
- .3 Sanitary facilities will be assigned for Contractor's personnel. Others shall not be used. Keep facilities clean.

11 SITE STORAGE

- .1 Do not unreasonably encumber site with materials or equipment.
- .2 Move stored products or equipment which interfere with operations of occupants.

12 CUT, PATCH AND MAKE GOOD

- .1 Cut existing surfaces as required to accommodate new work.
- .2 Remove all items so shown or specified.
- .3 Patch and make good surfaces cut, damaged or disturbed, to Departmental Representative's approval. Match existing material, colour, finish and texture.

13 EXAMINATION

- .1 Examine site and conditions likely to affect work and be familiar and conversant with existing conditions.
- .2 Provide photographs of surrounding properties, objects and structures liable to be damaged or be the subject of subsequent claims.

14 SIGNS

- .1 Provide common-use signs related to traffic control, information, instruction, use of equipment, public safety devices, etcetera, in both official languages or by the use of commonly-understood graphic symbols to the Departmental Representative's approval.
- .2 Signs must comply with CAN/CSA Z321. Symbols size to be 200 mm for a viewing distance of 24 to 30 metres.
- .3 No advertising will be permitted on this project.

15 ACCESS AND EGRESS

- .1 Design, construct and maintain temporary "access to" and "egress from" work areas, independent of finished surfaces and in accordance with relevant municipal, provincial and other regulations.

<u>15 ACCESS AND EGRESS (Cont'd)</u>	.2	The contractor shall agree to install proper site separation and identification in order to maintain "Time and Space" at all times throughout the life of the project. When building operations staff, building staff or private sector maintenance personnel require access to operational equipment located in the construction area in order to operate the building, access shall be granted and proper coordination and communication must exist between all parties involved.
<u>16 SCAFFOLDS AND WORK PLATFORMS</u>	.1	Design, install, and inspect scaffolds and work platforms required for work in accordance with relevant municipal, provincial and other regulations.
	.2	Provide design drawings, signed and sealed by qualified Professional Engineer licensed in the province of Ontario.
	.3	Additions or modifications to scaffolding must be approved by Professional Engineer in writing.
<u>17 WASTE MANAGEMENT</u>	.1	Comply with the Environmental Protection Act, Ontario Regulations O.Reg. 102/94 and O. Reg. 103/94 for waste management program on construction and demolition projects.
<u>18 RECORDS</u>	.1	As work progresses, maintain accurate records to show deviations from contract drawings. Just prior to Departmental Representative's inspection for issuance of final certificate of completion, supply to the Departmental Representative one (1) set of white prints with all deviations neatly inked in. The Departmental Representative will provide two sets of clean white prints for this purpose.
<u>19 GUARANTEES AND WARRANTIES</u>	.1	Before completion of work collect all manufacturer's guarantees and warranties and deposit with Departmental Representative.
<u>20 CLEAN UP</u>	.1	Clean up work area as work progresses. At the end of each work period, and more often if ordered by the Departmental Representative, remove debris from site, neatly stack material for use, and clean up generally.
	.2	Upon completion remove scaffolding, temporary protection and surplus materials. Make good defects noted at this stage.
	.3	Clean areas under contract to a condition at least equal to that previously existing and to approval of Departmental Representative.
<u>21 SECURITY CHECK</u>	.1	Personnel will be checked daily at start of work shift and given a pass which must be worn at all times. Pass must be returned at end of work shift and personnel checked out.

-
- | | | |
|--|----|---|
| <u>22 BUILDING SMOKING</u>
<u>ENVIRONMENT</u> | .1 | Smoking is not permitted in the Building. Obey smoking restrictions on building property. |
|
 | | |
| <u>23 DUST CONTROL</u> | .1 | Provide dust tight screens or partitions to localize dust generating activities, and for protection of workers, finished areas of work and public. |
| | .2 | Maintain and relocate protection until such work is complete. |
|
 | | |
| <u>24 SCHEDULING</u> | .1 | On award of contract submit bar chart construction schedule for work, indicating anticipated progress stages within time of completion. When schedule has been reviewed by the Departmental Representative, take necessary measures to complete work within scheduled time. Do not change schedule without notifying Departmental Representative. |
| | .2 | Carry out work during "regular hour" Monday to Friday from 07:00 to 18:00 hours and on Saturdays, Sundays and statutory holidays. |
| | .3 | Give the Departmental Representative 48 hours notice for work to be carried out during "off hours". |
|
 | | |
| <u>25 COST BREAKDOWN</u> | .1 | Before submitting first progress claim submit breakdown of Contract Amount in detail as directed by Departmental Representative and aggregating the Contract Amount. After approval by Departmental Representative cost breakdown will be used as the basis of progress payments |
|
 | | |
| <u>26 PRECEDENCE</u> | .1 | For Federal Government projects, Division 01 Sections take precedence over technical specification sections in other Divisions of this Project Manual. |

END OF SECTION

1. GENERAL

1.1 REFERENCES

1. Federal Legislation

1. *Canada Labour Code, Part II, section 124 and 125. Canada Occupational Health and Safety Regulations*
2. *Transportation of Dangerous Goods Act, 1992 (TDGA)*
3. *Canada Consumer Product Safety Act*
 1. *Surface Coating Materials Regulations SOR/2005-109.*
4. *Canadian Environmental Protection Act, 1999 (CEPA)*
 1. *PCB Regulations (SOR/2008-273)*
 2. *Federal Halocarbon Regulations, 2003 (SOR/2003-289)*

2. Provincial Legislation

1. *Ontario Occupational Health and Safety Act, R.S.O. 1990, 2010 edition.*
 1. *Ontario Regulation 490/09 – Designated Substances (O.Reg. 490/09).*
 2. *Ontario Regulation 278/05 – Designated Substance - Asbestos on Construction Projects and in Buildings and Repair Operations, (O.Reg. 278/05).*
 3. *Ontario Regulation 213/91 for Construction Projects (O.Reg. 213/91)*
2. *Ontario Environmental Protection Act, R.R.O. 1990,*
 1. *Ontario Regulation 347/09, General – Waste Management (O.Reg. 347/09).*
 2. *Ontario Regulation 463/10, Ozone Depleting Substances and Other Halocarbons (O.Reg. 463/10).*
3. *Canadian General Standards Board (CGSB).*
4. *Canadian Standards Association (CSA International). CAN/CSA-Z94.4-11 - Respiratory Protection*
5. *Underwriters' Laboratories of Canada (ULC).*

1.2 DEFINITIONS

Asbestos-Containing Materials (ACMs): means material that contains 0.5 per cent or more asbestos by dry weight as per Ontario Regulation 278/05.

Friable Material: material that when dry can be crumbled, pulverized or powdered by hand pressure and includes such material that is crumbled, pulverized or powdered.

Time-weighted average exposure limit (TWAEEL): the time-weighted average airborne concentration of a biological or chemical agent to which a worker may be exposed in a work day or work week as prescribed by Ontario Regulation 490/09 Designated Substances, as amended.

1.3 DESIGNATED SUBSTANCES

Confirm with the Departmental Representative that no additional designated substances have been brought to the project area prior to beginning work.

Additional designated substances and hazardous materials may exist outside the accessible survey areas but are beyond the scope of this project.

Should any additional material, suspected to be a designated substance, be encountered within the project area, any disturbance of such material must be stopped, precautionary measures taken, and the Departmental Representative must be notified immediately. Do not proceed until written instructions have been received.

1. ACRYLONITRILE: Not Identified

2. ARSENIC: Not Identified

3. ASBESTOS: **Identified**

Based on visual observations, the following material is assumed to contain regulated amounts of asbestos:

- Non-friable, corrugated, asbestos cement, Transite panels, that comprise the entire ceiling deck of the T-58 main hanger, are assumed to contain asbestos. These panels were not observed in the Helicopter hanger.

Bulk sampling and laboratory analysis has determined that the following materials do not contain regulated amounts of asbestos:

- Sprayed fireproofing, T-58 Main Hanger, ceiling deck and structural steel beams.

4. BENZENE: Not Identified

5. COKE OVEN EMISSIONS: Not identified

6. ETHYLENE OXIDE: Not Identified

7. ISOCYANATES: Not Identified

8. LEAD: **Assumed**

No lead paint samples were collected for lead content analysis, as paints and surface coatings encountered in the project areas were in good condition and sampling without matrix interference (i.e. removing the paint without the substrate material) would have proved difficult. All paints and surface coatings, including structural steel coatings, throughout the project area, shall be assumed to contain detectable concentrations of lead, unless specific bulk sampling and laboratory analysis confirms otherwise.

9. MERCURY: **Identified**

Mercury is suspected to be present in the following:

- High Intensity Discharge (HID) light fixtures that contain light tubes were observed throughout the project area. Light tubes contain mercury in a vapour form and in the phosphor coating in the lamps

10. SILICA: **Identified**

Free crystalline silica is expected to be present in the following materials:

- Fireproofing;
- Asbestos cement Transite ceiling panels; and
- Concrete.

11. VINYL CHLORIDE MONOMER: Not Identified

12. POLYCHLORINATED BIPHENYLS (PCBs): **Assumed**

HID light fixtures in the project areas were not disassembled as they were electrical energized at the time of the survey. Based on limited visual observations, HID light fixture ballasts (if present) are assumed to contain PCBs, until proven otherwise.

13. MOULD: Not Identified

14. HALOCARBONS: Not Identified

15. OTHER HAZARDOUS MATERIALS: Not Identified

1.4 RECOMMENDATIONS

.1 ASBESTOS

All work must be done in accordance with O.Reg. 278/05 (as amended).

1. The disturbance of ACMs on construction and demolition projects in the province of Ontario is governed by *O.Reg. 278/05*, as amended. This regulation classifies all asbestos disturbances as Low Risk (Type 1), Moderate Risk (Type 2), or High Risk (Type 3), each of which has defined precautionary measures. All asbestos materials are subject to specific handling and disposal precautions, and must be removed prior to demolition. The Ontario Ministry of Labour (MoL) must be notified of any project involving removal of more than a minor amount (e.g. typically 1 square metre) of friable asbestos material.

2. Type 1 work procedures can be used for the removal of non-friable ACMs (transite) provided that the material can be wetted and removed using only non-powered hand tools. If these conditions cannot be met, then more stringent (e.g., Type 2 or Type 3) procedures are necessary.
3. Disposal of asbestos waste must be done in accordance with "General – Waste Management" O.Reg. 347/90 (as amended) under the Ontario Environmental Protection Act and the federal Transportation of Dangerous Goods Act. The waste must be disposed at a licensed waste disposal site. Proper notification must be issued to the Departmental Representative prior to transportation of waste.

2. LEAD

1. Follow recommendations provided in the Ontario Ministry of Labour (MoL) Guideline entitled "Guideline: Lead on Construction Projects". This guideline classifies all lead disturbances as Type 1, Type 2a, Type 2b, Type 3a or Type 3b work, and assigns different levels of respiratory protection and work procedures for each classification.
2. Work procedures and personal protective equipment must be used to ensure that workers are not exposed to airborne lead levels that exceed the TWAEEL of 0.05 milligram per cubic metre (mg/m³) prescribed by O.Reg. 490/09.
3. Even at low concentrations, there may be a potential for exposure to high concentrations of lead depending on the activities performed that disturb the lead-containing materials. At low lead concentrations, conducting a risk assessment to assess the potential for exposure is required to determine the need to follow precautionary measures.
4. Disposal of construction waste containing lead must be done in accordance with O.Reg. 347/90 – General Waste Management, as amended, under the Ontario Environmental Protection Act and the federal Transportation of Dangerous Goods Act. The classification of the waste is dependent upon the result(s) of leachate test(s). The waste can be classified as "hazardous," "non-hazardous" or "registerable solid waste" depending on the results of the leachate test.

3. MERCURY

1. All work involving disturbance of mercury-containing equipment must be done in accordance with O.Reg 490/09.
2. Follow recommendations provided in the MoL Guideline entitled "The Safe Handling of Mercury: A Guide for the Construction Industry". This document provides advice on how to reduce the risk of mercury exposure, and outlines clean-up methods for spills.
3. When removal of fluorescent light tubes is required, the tubes should be removed intact from the fixtures. Other sources of liquid mercury should be removed intact to prevent worker exposure.
4. Disposal of waste containing mercury must be done in accordance with "General – Waste Management" O.Reg 347/90 (as amended) under the Ontario Environmental Protection Act and the federal Transportation of Dangerous Goods Act.

4. SILICA

1. Comply with Ontario Regulations O.Reg. 490/09 when performing works that may disturb silica-containing materials. The regulation provides requirements for allowable exposure levels.
2. Silica dust can be generated through such processes as blasting, grinding, crushing, and sandblasting silica-containing material. Since silica is present in select materials within the project area, appropriate respiratory protection and ventilation must be donned during the demolition and modifications of these structures.
3. Follow recommendations provided in the MoL Guideline entitled "Guideline: Silica on Construction Projects". This document classifies all silica disturbances as Type 1, Type 2 or Type 3 work, and assigns different levels of respiratory protection and work procedures for each classification. These work procedures should be followed when performing work involving the disturbance of silica-containing materials.

5. PCBs

1. Prior to removal or disposal, the PCB content of equipment and/or liquids should be confirmed to determine proper procedures to be followed, unless conservatively assumed to contain PCBs. When the HID light fixtures are taken out of service, these ballasts, as well as other ballasts, should be examined to determine whether they contain PCBs. This can be done by comparing the manufacturer date

codes stamped on the ballasts to information contained in the document titled Identification of Lamp Ballasts Containing PCBs, published by Environment Canada. Ballasts that contain PCBs must be packaged, transported and disposed of in accordance with all appropriate provincial and federal regulations

2. If PCB-containing equipment and/or materials are identified and must be removed, they should be disposed of in accordance with the Canadian Environment Protection Act's PCB Regulations, O. Reg. 362/90 – Waste Management, PCBs and O. Reg. 347, General – Waste Management, as amended, are regulated under the Environmental Protection Act to regulate the handling, storage and transportation of hazardous substances and waste dangerous goods. The transport of PCB waste to the disposal site is controlled by the federal Transportation of Dangerous Goods Act.

2. PRODUCTS

Not used

2. EXECUTION

Not used

END OF SECTION

PART 1 - GENERAL**1.1 ADMINISTRATIVE**

- .1 Submit to Departmental Representative submittals listed for review. Submit promptly and in orderly sequence to not cause delay in Work. Failure to submit in ample time is not considered sufficient reason for extension of Contract Time and no claim for extension by reason of such default will be allowed.
- .2 Do not proceed with Work affected by submittal until review is complete.
- .3 Present shop drawings, product data, samples and mock-ups in SI Metric units.
- .4 Where items or information is not produced in SI Metric units converted values are acceptable.
- .5 Review submittals prior to submission to Departmental Representative. This review represents that necessary requirements have been determined and verified, or will be, and that each submittal has been checked and co-ordinated with requirements of Work and Contract Documents. Submittals not stamped, signed, dated and identified as to specific project will be returned without being examined and considered rejected.
- .6 Notify Departmental Representative, in writing at time of submission, identifying deviations from requirements of Contract Documents stating reasons for deviations.
- .7 Verify field measurements and affected adjacent Work are co-ordinated.
- .8 Contractor's responsibility for errors and omissions in submission is not relieved by Departmental Representative's review of submittals.
- .9 Contractor's responsibility for deviations in submission from requirements of Contract Documents is not relieved by Departmental Representative review.
- .10 Keep one reviewed copy of each submission on site.

**1.2 SHOP DRAWINGS
AND PRODUCT DATA**

- .1 The term "shop drawings" means drawings, diagrams, illustrations, schedules, performance charts, brochures and other data which are to be provided by Contractor to illustrate details of a portion of Work.
- .2 Submit drawings stamped and signed by professional engineer registered or licensed in Province of Ontario, Canada.
- .3 Indicate materials, methods of construction and attachment or anchorage, erection diagrams, connections, explanatory notes and other information necessary for completion of Work. Where articles or equipment attach or connect to other articles or equipment, indicate that such items have been co-ordinated, regardless of Section under which adjacent items will be supplied and installed. Indicate cross references to design drawings and specifications.
- .4 Allow 10 days for Departmental Representative's review of each submission.

1.2 SHOP DRAWINGS
AND PRODUCT DATA
(Cont'd)

- .5 Adjustments made on shop drawings by Departmental Representative are not intended to change Contract Price. If adjustments affect value of Work, state such in writing to Departmental Representative prior to proceeding with Work.
- .6 Make changes in shop drawings as Departmental Representative may require, consistent with Contract Documents. When resubmitting, notify Departmental Representative in writing of revisions other than those requested.
- .7 Accompany submissions with transmittal letter, containing:
 - .1 Date.
 - .2 Project title and number.
 - .3 Contractor's name and address.
 - .4 Identification and quantity of each shop drawing, product data and sample.
 - .5 Other pertinent data.
- .8 Submissions include:
 - .1 Date and revision dates.
 - .2 Project title and number.
 - .3 Name and address of:
 - .1 Subcontractor.
 - .2 Supplier.
 - .3 Manufacturer.
 - .4 Contractor's stamp, signed by Contractor's authorized representative certifying approval of submissions, verification of field measurements and compliance with Contract Documents.
 - .5 Details of appropriate portions of Work as applicable:
 - .1 Fabrication.
 - .2 Layout, showing dimensions, including identified field dimensions, and clearances.
 - .3 Setting or erection details.
 - .4 Capacities.
 - .5 Performance characteristics.
 - .6 Standards.
 - .7 Operating weight.
 - .8 Wiring diagrams.
 - .9 Single line and schematic diagrams.
 - .10 Relationship to adjacent work.
- .9 After Departmental Representative's review, distribute copies.
- .10 Submit electronic copy of shop drawings for each requirement requested in specification Sections and as Departmental Representative may reasonably request.
- .11 Submit electronic copy of product data sheets or brochures for requirements requested in specification Sections and as requested by Departmental Representative where shop drawings will not be prepared due to standardized manufacture of product.
- .12 Submit electronic copy of test reports for requirements requested in specification Sections and as requested by Departmental Representative.
 - .1 Report signed by authorized official of testing laboratory that material, product or system identical to material, product or system to be provided has been tested in accord with specified requirements.
 - .2 Testing must have been within 3 years of date of contract award for project.

**1.2 SHOP DRAWINGS
AND PRODUCT DATA**
(Cont'd)

- .13 Submit electronic copy of certificates for requirements requested in specification Sections and as requested by Departmental Representative.
 - .1 Statements printed on manufacturer's letterhead and signed by responsible officials of manufacturer of product, system or material attesting that product, system or material meets specification requirements.
 - .2 Certificates must be dated after award of project contract complete with project name.
- .14 Submit electronic copy of manufacturers instructions for requirements requested in specification Sections and as requested by Departmental Representative.
 - .1 Pre-printed material describing installation of product, system or material, including special notices and Material Safety Data Sheets concerning impedances, hazards and safety precautions.
- .15 Submit electronic copy of Manufacturer's Field Reports for requirements requested in specification Sections and as requested by Departmental Representative.
- .16 Documentation of the testing and verification actions taken by manufacturer's representative to confirm compliance with manufacturer's standards or instructions.
- .17 Submit electronic copies of Operation and Maintenance Data for requirements requested in specification Sections and as requested by Departmental Representative.
- .18 Delete information not applicable to project.
- .19 Supplement standard information to provide details applicable to project.
- .20 If upon review by Departmental Representative, no errors or omissions are discovered or if only minor corrections are made, copy will be returned and fabrication and installation of Work may proceed. If shop drawings are rejected, noted copy will be returned and resubmission of corrected shop drawings, through same procedure indicated above, must be performed before fabrication and installation of Work may proceed.
- .21 The review of shop drawings by Departmental Representative is for sole purpose of ascertaining conformance with general concept.
 - .1 This review shall not mean that PSPC approves detail design inherent in shop drawings, responsibility for which shall remain with Contractor submitting same, and such review shall not relieve Contractor of responsibility for errors or omissions in shop drawings or of responsibility for meeting requirements of construction and Contract Documents.
 - .2 Without restricting generality of foregoing, Contractor is responsible for dimensions to be confirmed and correlated at job site, for information that pertains solely to fabrication processes or to techniques of construction and installation and for co-ordination of Work of sub-trades.

PART 2 - PRODUCTS**2.1 NOT USED**

- .1 Not Used.

PART 3 - EXECUTION

3.1 NOT USED .1 Not Used.

END OF SECTION

PART 1 - GENERAL**1.1 REFERENCE
STANDARDS**

- .1 Province of Ontario
 - .1 Occupational Health and Safety Act and Regulations for Construction Projects, R.S.O. 1990, c.0.1, as amended and O. Reg. 213/91 as amended - Current edition.
- .2 Canadian Standards Association (CSA)
 - .1 CAN/CSA Z460-13, Control of Hazardous Energy - Lockout and Other Methods.
 - .2 CSA Z462-15, Workplace Electrical Safety.

**1.2 ACTION AND
INFORMATIONAL
SUBMITTALS**

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit site-specific Health and Safety Plan: Within 7 days after date of Notice to Proceed and prior to commencement of Work. Health and Safety Plan must include:
 - .1 Results of site specific safety hazard assessment.
 - .2 Results of safety and health risk or hazard analysis for site tasks and operation found in work plan.
- .3 Submit three (3) copies of Contractor's authorized representative's work site health and safety inspection reports to Departmental Representative.
- .4 Submit copies of reports or directions issued by Federal and Provincial health and safety inspectors.
- .5 Submit copies of incident and accident reports.
- .6 Departmental Representative will review Contractor's site-specific Health and Safety Plan and provide comments to Contractor within 14 days after receipt of plan. Revise plan as appropriate and resubmit plan to Departmental Representative within 5 days after receipt of comments from Departmental Representative.
- .7 Departmental Representative's review of Contractor's final Health and Safety plan should not be construed as approval and does not reduce the Contractor's overall responsibility for construction Health and Safety.
- .8 On-site Contingency and Emergency Response Plan: address standard operating procedures to be implemented during emergency situations.
- .9 The constructor shall advise the Departmental Representative of any accident, injury, near-miss incident, fire, explosion or Chemical spill occurring at the Work site and any visit to the site by a governmental enforcement official. The constructor shall provide a written report within 24 hours of any accident, injury, near-miss incident, fire, explosion or chemical spill.

<u>1.2 ACTION AND INFORMATIONAL SUBMITTALS (Cont'd)</u>	.10	Submit to the Departmental Representative for review, one complete Hazard Assessment Site Specific Health and Safety Plan (HASSSP) in an indexed format, and in a three ring binder. Once the Departmental Representative has reviewed and accepts the HASSSP binder the Departmental Representative will return to contractor for site use.
<u>1.3 FILING OF NOTICE</u>	.1	File Notice of Project with Provincial authorities prior to beginning of Work.
	.2	Contractor shall be responsible for each work zone location and not the entire complex. Contractor shall provide a written acknowledgement of this responsibility with 3 weeks of contract award.
	.3	Contractor shall agree to install proper site separation and identification in order to maintain time and space at all times throughout life of project.
<u>1.4 SAFETY ASSESSMENT</u>	.1	Perform site specific safety hazard assessment related to project.
<u>1.5 MEETINGS</u>	.1	Schedule and administer Health and Safety meeting with Departmental Representative prior to commencement of Work.
<u>1.6 GENERAL REQUIREMENTS</u>	.1	Develop written site-specific Health and Safety Plan based on hazard assessment prior to beginning site Work and continue to implement, maintain, and enforce plan until final demobilization from site. Health and Safety Plan must address project specifications.
	.2	Departmental Representative may respond in writing, where deficiencies or concerns are noted and may request re-submission with correction of deficiencies or concerns.
<u>1.7 RESPONSIBILITY</u>	.1	Be responsible for health and safety of persons on site, safety of property on site and for protection of persons adjacent to site and environment to extent that they may be affected by conduct of Work.
	.2	Contractor will be responsible and assume the role Constructor as described in the Ontario Occupational Health and Safety Act and Regulations for Construction Projects.
	.3	Contractor shall be the Principal Contractor as described in the Quebec Act Respecting Health and Safety code for the Construction for only their scope and areas of work as defined and described this project specification.
	.4	Comply with and enforce compliance by employees with safety requirements of Contract Documents, applicable federal, provincial, territorial and local statutes, regulations, and ordinances, and with site-specific Health and Safety Plan.

<u>1.7 RESPONSIBILITY (Cont'd)</u>	.5	Ensure the site supervisor is an employee of the constructor and that this person is present and available at all-times throughout the life of the project.
<u>1.8 COMPLIANCE REQUIREMENTS</u>	.1	Comply with Ontario Occupational Health and Safety Act, R.S.O. 1990, c. 0.1 and Ontario Regulations for Construction Projects, O. Reg. 213/91.
	.2	Comply with the Health and Safety requirements of CSA Z462.
	.3	Comply with the Health and Safety requirements of CAN/CSA Z460.
<u>1.9 UNFORESEEN HAZARDS</u>	.1	When unforeseen or peculiar safety-related factor, hazard, or condition occur during performance of Work, follow procedures in place for Employee's Right to Refuse Work in accordance with Acts and Regulations of Province having jurisdiction and advise Departmental Representative verbally and in writing.
	.2	When unforeseen or peculiar safety-related factor, hazard, or condition occur during performance of Work, advise Health and Safety co-ordinator and follow procedures in accordance with Acts and Regulations of Province having jurisdiction and advise Departmental Representative verbally and in writing.
<u>1.10 HEALTH AND SAFETY CO-ORDINATOR</u>	.1	Employ and assign to Work, competent and authorized representative as Health and Safety Co-ordinator. Health and Safety Co-ordinator must: .1 Be responsible for completing Contractor's Health and Safety Training Sessions and ensuring that personnel not successfully completing required training are not permitted to enter site to perform Work. .2 Be responsible for implementing, enforcing daily and monitoring site-specific Contractor's Health and Safety Plan. .3 Be on site during execution of Work and report directly to and be under direction of site supervisor.
<u>1.11 POSTING OF DOCUMENTS</u>	.1	Ensure applicable items, articles, notices and orders are posted in conspicuous location on site in accordance with Acts and Regulations of Province having jurisdiction, and in consultation with Departmental Representative.
<u>1.12 CORRECTION OF NON-COMPLIANCE</u>	.1	Immediately address health and safety non-compliance issues identified by authority having jurisdiction or by Departmental Representative.
	.2	Provide Departmental Representative with written report of action taken to correct non-compliance of health and safety issues identified.
	.3	Departmental Representative may stop Work if non-compliance of health and safety regulations is not corrected.

<u>1.13 WORK STOPPAGE</u>	.1	Give precedence to safety and health of public and site personnel and protection of environment over cost and schedule considerations for Work.
---------------------------	----	---

<u>1.14 DIESEL POWERED EQUIPMENT</u>	.1	Contractor may not use any diesel fired powered equipment such as scissor lifts on the site.
--------------------------------------	----	--

<u>1.15 POWER ACTUATED DEVICES</u>	.1	Use powder actuated devices only after receipt of written permission from <u>Departmental Representative</u> .
------------------------------------	----	--

PART 2 - PRODUCTS

<u>2.1 NOT USED</u>	.1	Not used.
---------------------	----	-----------

PART 3 - EXECUTION

<u>3.1 NOT USED</u>	.1	Not used.
---------------------	----	-----------

END OF SECTION

PART 1 - GENERAL

<u>1.1 REFERENCE STANDARDS</u>	.1	Canadian Standards Association (CSA International)
	.1	CSA-O121-08 (R2013), Douglas Fir Plywood, Includes Update No. 1 (2013).
<u>1.2 INSTALLATION AND REMOVAL</u>	.1	Provide temporary controls in order to execute Work expeditiously.
	.2	Remove from site all such work after use.
<u>1.3 HOARDING</u>	.1	Erect temporary site enclosures using 38 x 89 mm construction grade lumber framing at 600 mm centres and 1200 x 2400 x 13 mm exterior grade fir plywood to CSA O121.
	.2	Apply plywood panels vertically flush and butt jointed.
	.3	Provide two lockable truck entrance gate gates and at least one pedestrian door conforming to applicable traffic restrictions. Equip gates with locks and keys.
<u>1.4 ACCESS TO SITE</u>	.1	Provide and maintain access as required for access to Work.
<u>1.5 PROTECTION OF BUILDING FINISHES</u>	.1	Provide protection for finished building finishes and equipment during performance of Work.
	.2	Provide necessary screens, covers, and hoardings.
	.3	Confirm with Departmental Representative locations and installation 1 week prior to installation.
	.4	Be responsible for damage incurred due to lack of or improper protection.

PART 2 - PRODUCTS

<u>2.1 NOT USED</u>	.1	Not Used.
----------------------------	----	-----------

PART 3 - EXECUTION

<u>3.1 NOT USED</u>	.1	Not Used.
----------------------------	----	-----------

END OF SECTION

PART 1 - GENERAL

<u>1.1 REFERENCE STANDARDS</u>	<div>.1 Canadian Environmental Protection Act (CEPA)</div> <div>.1 SOR/2008-197, Storage Tank Systems for Petroleum Products and Allied Petroleum Products Regulations.</div>
<u>1.2 ADMINISTRATIVE REQUIREMENTS</u>	<div>.1 Pre-warranty Meeting:</div> <div>.1 Convene meeting one week prior to contract completion with contractor's representative and Departmental Representative to:</div> <div>.1.1 Verify Project requirements.</div> <div>.1.2 Review manufacturer's installation instructions and warranty</div> <div>.2 Departmental Representative to establish communication procedures for:</div> <div>.1.1 Notifying construction warranty defects.</div> <div>.1.2 Determine priorities for type of defects.</div> <div>.1.3 Determine reasonable response time.</div> <div>.3 Contact information for bonded and licensed company for warranty work action: provide name, telephone number and address of company authorized for construction warranty work action.</div> <div>.4 Ensure contact is located within local service area of warranted construction, is continuously available, and is responsive to inquiries for warranty work action.</div>
<u>1.3 ACTION AND INFORMATIONAL SUBMITTALS</u>	<div>.1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.</div> <div>.2 Provide spare parts, maintenance materials and special tools of same quality and manufacture as products provided in Work.</div> <div>.3 Provide evidence, if requested, for type, source and quality of products supplied.</div>
<u>1.4 FORMAT</u>	<div>.1 Organize data as instructional manual.</div> <div>.2 Binders: vinyl, hard covered, 3 'D' ring, loose leaf 219 x 279 mm with spine and face pockets.</div> <div>.3 When multiple binders are used correlate data into related consistent groupings.</div> <div>.3.1 Identify contents of each binder on spine.</div> <div>.4 Cover: identify each binder with type or printed title 'Project Record Documents'; list title of project and identify subject matter of contents.</div> <div>.5 Arrange content by systems, under Section numbers and sequence of Table of Contents.</div> <div>.6 Provide tabbed fly leaf for each separate product and system, with typed description of product and major component parts of equipment.</div> <div>.7 Text: manufacturer's printed data, or typewritten data.</div>

1.4 FORMAT (Cont'd)	.8	Drawings: provide with reinforced punched binder tab.
	.1	Bind in with text; fold larger drawings to size of text pages.
1.5 CONTENTS - PROJECT RECORD DOCUMENTS	.1	Table of Contents for Each Volume: provide title of project;
	.1	Date of submission; names.
	.2	Addresses, and telephone numbers of Consultant and Contractor with name of responsible parties.
	.3	Schedule of products and systems, indexed to content of volume.
	.2	For each product or system:
	.1	List names, addresses and telephone numbers of subcontractors and suppliers, including local source of supplies and replacement parts.
	.3	Product Data: mark each sheet to identify specific products and component parts, and data applicable to installation; delete inapplicable information.
	.4	Drawings: supplement product data to illustrate relations of component parts of equipment and systems, to show control and flow diagrams.
1.6 AS -BUILT DOCUMENTS AND SAMPLES	.1	Maintain, in addition to requirements in General Conditions, at site for Departmental Representative one record copy of:
	.1	Contract Drawings.
	.2	Specifications.
	.3	Addenda.
	.4	Change Orders and other modifications to Contract.
	.5	Reviewed shop drawings, product data, and samples.
	.6	Field test records.
	.7	Inspection certificates.
	.8	Manufacturer's certificates.
	.2	Store record documents and samples in field office apart from documents used for construction.
	.1	Provide files, racks, and secure storage.
	.3	Label record documents and file in accordance with Section number listings in List of Contents of this Project Manual.
	.1	Label each document "PROJECT RECORD" in neat, large, printed letters.
	.4	Maintain record documents in clean, dry and legible condition.
	.1	Do not use record documents for construction purposes.
	.5	Keep record documents available for inspection by Departmental Representative.
1.7 RECORDING INFORMATION ON PROJECT RECORD DOCUMENTS	.1	Record information on set of black line opaque drawings, and in copy of Project Manual, provided by Departmental Representative.
	.2	Use felt tip marking pens, maintaining separate colours for each major system, for recording information.

**1.7 RECORDING
INFORMATION ON
PROJECT RECORD
DOCUMENTS**
(Cont'd)

- .3 Record information concurrently with construction progress.
 - .1 Do not conceal Work until required information is recorded.
- .4 Contract Drawings and shop drawings: mark each item to record actual construction, including:
 - .1 Measured depths of elements of foundation in relation to finish first floor datum.
 - .2 Measured horizontal and vertical locations of underground utilities and appurtenances, referenced to permanent surface improvements.
 - .3 Measured locations of internal utilities and appurtenances, referenced to visible and accessible features of construction.
 - .4 Field changes of dimension and detail.
 - .5 Changes made by change orders.
 - .6 Details not on original Contract Drawings.
 - .7 Referenced Standards to related shop drawings and modifications.
- .5 Specifications: mark each item to record actual construction, including:
 - .1 Manufacturer, trade name, and catalogue number of each product actually installed, particularly optional items and substitute items.
 - .2 Changes made by Addenda and change orders.
- .6 Other Documents: maintain manufacturer's certifications, inspection certifications, required by individual specifications sections.
- .7 Provide digital photos, if requested, for site records.

**1.8 EQUIPMENT AND
SYSTEMS**

- .1 For each item of equipment and each system include description of unit or system, and component parts.
 - .1 Give function, normal operation characteristics and limiting conditions.
 - .2 Include performance curves, with engineering data and tests, and complete nomenclature and commercial number of replaceable parts.
- .2 Panel board circuit directories: provide electrical service characteristics, controls, and communications.
- .3 Include installed colour coded wiring diagrams.
- .4 Operating Procedures: include start-up, break-in, and routine normal operating instructions and sequences.
 - .1 Include regulation, control, stopping, shut-down, and emergency instructions.
 - .2 Include summer, winter, and any special operating instructions.
- .5 Maintenance Requirements: include routine procedures and guide for trouble-shooting; disassembly, repair, and reassembly instructions; and alignment, adjusting, balancing, and checking instructions.
- .6 Provide servicing and lubrication schedule, and list of lubricants required.
- .7 Include manufacturer's printed operation and maintenance instructions.
- .8 Include sequence of operation by controls manufacturer.

**1.8 EQUIPMENT AND
SYSTEMS**
(Cont'd)

- .9 Provide original manufacturer's parts list, illustrations, assembly drawings, and diagrams required for maintenance.
- .10 Provide installed control diagrams by controls manufacturer.
- .11 Provide Contractor's co-ordination drawings, with installed colour coded piping diagrams.
- .12 Provide charts of valve tag numbers, with location and function of each valve, keyed to flow and control diagrams.
- .13 Provide list of original manufacturer's spare parts, current prices, and recommended quantities to be maintained in storage.

**1.9 MAINTENANCE
MATERIALS**

- .1 Spare Parts:
 - .1 Provide spare parts, in quantities specified in individual specification sections.
 - .2 Provide items of same manufacture and quality as items in Work.
 - .3 Deliver to location as directed; place and store.
 - .4 Receive and catalogue items.
 - .1 Submit inventory listing to Departmental Representative.
 - .2 Include approved listings in Maintenance Manual.
 - .5 Obtain receipt for delivered products and submit prior to final payment.
- .2 Special Tools:
 - .1 Provide special tools, in quantities specified in individual specification section.
 - .2 Provide items with tags identifying their associated function and equipment.
 - .3 Deliver to location as directed; place and store.
 - .4 Receive and catalogue items.
 - .1 Submit inventory listing to Departmental Representative.
 - .2 Include approved listings in Maintenance Manual.

**1.10 DELIVERY,
STORAGE AND
HANDLING**

- .1 Store spare parts, maintenance materials, and special tools in manner to prevent damage or deterioration.
- .2 Store in original and undamaged condition with manufacturer's seal and labels intact.
- .3 Store components subject to damage from weather in weatherproof enclosures.
- .4 Store paints and freezable materials in a heated and ventilated room.
- .5 Remove and replace damaged products at own expense and for review by Departmental Representative.

**1.11 WARRANTIES AND
BONDS**

- .1 Develop warranty management plan to contain information relevant to Warranties.
- .2 Warranty management plan to include required actions and documents to assure that Departmental Representative receives warranties to which it is entitled.

1.11 WARRANTIES AND BONDS
(Cont'd)

- .3 Provide plan in narrative form and contain sufficient detail to make it suitable for use by future maintenance and repair personnel.
- .4 Assemble approved information in binder, submit upon acceptance of work and organize binder as follows:
 - .1 Separate each warranty or bond with index tab sheets keyed to Table of Contents listing.
 - .2 List subcontractor, supplier, and manufacturer, with name, address, and telephone number of responsible principal.
 - .3 Obtain warranties and bonds, executed in duplicate by subcontractors, suppliers, and manufacturers, within ten days after completion of applicable item of work.
 - .4 Verify that documents are in proper form, contain full information, and are notarized.
 - .5 Co-execute submittals when required.
 - .6 Retain warranties and bonds until time specified for submittal.
- .5 Except for items put into use with Owner's permission, leave date of beginning of time of warranty until Date of Substantial Performance is determined.
- .6 Include information contained in warranty management plan as follows:
 - .1 Roles and responsibilities of personnel associated with warranty process, including points of contact and telephone numbers within the organizations of Contractors, subcontractors, manufacturers or suppliers involved.
 - .2 Provide list for each warranted equipment, item, feature of construction or system indicating:
 - .1 Name of item.
 - .2 Model and serial numbers.
 - .3 Location where installed.
 - .4 Name and phone numbers of manufacturers or suppliers.
 - .5 Names, addresses and telephone numbers of sources of spare parts.
 - .6 Warranties and terms of warranty: include one-year overall warranty of construction. Indicate items that have extended warranties and show separate warranty expiration dates.
 - .7 Cross-reference to warranty certificates as applicable.
 - .8 Starting point and duration of warranty period.
 - .9 Summary of maintenance procedures required to continue warranty in force.
 - .10 Cross-Reference to specific pertinent Operation and Maintenance manuals.
 - .11 Organization, names and phone numbers of persons to call for warranty service.
 - .12 Typical response time and repair time expected for various warranted equipment.
 - .3 Procedure and status of tagging of equipment covered by extended warranties.
 - .4 Post copies of instructions near selected pieces of equipment where operation is critical for warranty and/or safety reasons.
- .7 Respond in timely manner to oral or written notification of required construction warranty repair work.
- .8 Written verification to follow oral instructions.
 - .1 Failure to respond will be cause for the Departmental Representative to proceed with action against Contractor.

PART 2 - PRODUCTS

2.1 NOT USED .1 Not Used.

PART 3 - EXECUTION

3.1 NOT USED .1 Not Used.

END OF SECTION

PART 1 - GENERAL**1.1 SUMMARY**

- .1 Section Includes:
 - .1 General requirements relating to commissioning of project's components and systems, specifying general requirements to PV of components, equipment, sub-systems, systems, and integrated systems.
- .2 Acronyms:
 - .1 BMM - Building Management Manual.
 - .2 Cx - Commissioning.
 - .3 O&M - Operation and Maintenance.
 - .4 PI - Product Information.
 - .5 PV - Performance Verification.

1.2 GENERAL

- .1 Cx is a planned program of tests, procedures and checks carried out systematically on systems and integrated systems of the finished Project. Cx is performed after systems and integrated systems are completely installed, functional and Contractor's Performance Verification responsibilities have been completed and approved.
Objectives:
 - .1 Verify installed equipment, systems and integrated systems operate in accordance with Contract Documents and design criteria and intent.
 - .2 Ensure appropriate documentation is compiled into the BMM.
 - .3 Effectively train O&M staff.
- .2 Contractor assists in Cx process, operating equipment and systems, troubleshooting and making adjustments as required.
 - .1 Systems to be operated at full capacity under various modes to determine if they function correctly and consistently at peak efficiency. Systems to be interactively with each other as intended in accordance with Contract Documents and design criteria.
 - .2 During these checks, adjustments to be made to enhance performance to meet environmental or user requirements.
- .3 Design Criteria: as per client's requirements or determined by designer. To meet Project functional and operational requirements.

1.3 COMMISSIONING OVERVIEW

- .1 Section 01 91 31 - Commissioning (Cx) Plan.
- .2 For Cx responsibilities refer to Section 01 91 31 - Commissioning (Cx) Plan.
- .3 Cx to be a line item of Contractor's cost breakdown.
- .4 Cx activities supplement field quality and testing procedures described in relevant technical sections.

1.3 COMMISSIONING
OVERVIEW
(Cont'd)

- .5 Cx is conducted in concert with activities performed during stage of project delivery. Cx identifies issues in Planning and Design stages which are addressed during Construction and Cx stages to ensure the built is constructed and proven to operate satisfactorily under weather, environmental and occupancy conditions to meet functional and operational requirements. Cx activities includes transfer of critical knowledge to facility operational personnel.
- .6 Departmental Representative will issue Interim Acceptance Certificate when:
 - .1 Completed Cx documentation has been received, reviewed for suitability and approved by Departmental Representative.
 - .2 Equipment, components and systems have been commissioned.
 - .3 O&M training has been completed.

1.4 NON-
CONFORMANCE TO
PERFORMANCE
VERIFICATION
REQUIREMENTS

- .1 Should equipment, system components, and associated controls be incorrectly installed or malfunction during Cx, correct deficiencies, re-verify equipment and components within the unfunctional system, including related systems as deemed required by Departmental Representative, to ensure effective performance.
- .2 Costs for corrective work, additional tests, inspections, to determine acceptability and proper performance of such items to be borne by Contractor. Above costs to be in form of progress payment reductions or hold-back assessments.

1.5 PRE-CX REVIEW

- .1 Before Construction:
 - .1 Review Contract Documents, confirm by writing to Departmental Representative.
 - .1 Adequacy of provisions for Cx.
 - .2 Aspects of design and installation pertinent to success of Cx.
- .2 During Construction:
 - .1 Co-ordinate provision, location and installation of provisions for Cx.
- .3 Before start of Cx:
 - .1 Have completed Cx Plan up-to-date.
 - .2 Ensure installation of related components, equipment, sub-systems, systems is complete.
 - .3 Fully understand Cx requirements and procedures.
 - .4 Have Cx documentation shelf-ready.
 - .5 Understand completely design criteria and intent and special features.
 - .6 Submit complete start-up documentation to Departmental Representative.
 - .7 Have Cx schedules up-to-date.
 - .8 Ensure systems have been cleaned thoroughly.
 - .9 Ensure "As-Built" system schematics are available.
- .4 Inform Departmental Representative in writing of discrepancies and deficiencies on finished works.

1.6 CONFLICTS

- .1 Report conflicts between requirements of this section and other sections to Departmental Representative before start-up and obtain clarification.

<u>1.6 CONFLICTS (Cont'd)</u>	.2	Failure to report conflict and obtain clarification will result in application of most stringent requirement.
<u>1.7 ACTION AND INFORMATIONAL SUBMITTALS</u>	.1	Submittals: in accordance with Section 01 33 00 - Submittal Procedures. <ul style="list-style-type: none">.1 Submit no later than 4 weeks after award of Contract:<ul style="list-style-type: none">.1 Name of Contractor's Cx agent..2 Draft Cx documentation..3 Preliminary Cx schedule..2 Request in writing to Departmental Representative for changes to submittals and obtain written approval at least 8 weeks prior to start of Cx..3 Submit proposed Cx procedures to Departmental Representative where not specified and obtain written approval at least 8 weeks prior to start of Cx..4 Provide additional documentation relating to Cx process required by Departmental Representative.
<u>1.8 COMMISSIONING DOCUMENTATION</u>	.1	Refer to Section 01 91 33 - Commissioning (Cx) Forms: Installation Check Lists and Product Information (PI) / Performance Verification (PV) Forms for requirements and instructions for use.
	.2	Departmental Representative to review and approve Cx documentation.
	.3	Provide completed and approved Cx documentation to Departmental Representative.
<u>1.9 COMMISSIONING SCHEDULE</u>	.1	Provide detailed Cx schedule as part of construction schedule.
	.2	Provide adequate time for Cx activities prescribed in technical sections and commissioning sections including: <ul style="list-style-type: none">.1 Approval of Cx reports..2 Verification of reported results..3 Repairs, retesting, re-commissioning, re-verification..4 Training.
<u>1.10 COMMISSIONING MEETINGS</u>	.1	Convene Cx meetings following project meetings.
	.2	Purpose: to resolve issues, monitor progress, identify deficiencies, relating to Cx.
	.3	Continue Cx meetings on regular basis until commissioning deliverables have been addressed.
	.4	Thereafter Cx meetings to be held until project completion and as required during equipment start-up and functional testing period.
	.5	Meeting will be chaired by Cx Agent, who will record and distribute minutes.
	.6	Ensure subcontractors and relevant manufacturer representatives are present at 60% and subsequent Cx meetings and as required.

<u>1.11 STARTING AND TESTING</u>	.1	Contractor assumes liabilities and costs for inspections. Including disassembly and re-assembly after approval, starting, testing and adjusting, including supply of testing equipment.
<u>1.12 WITNESSING OF STARTING AND TESTING</u>	.1	Provide 14 days notice prior to commencement.
	.2	Departmental Representative to witness of start-up and testing.
	.3	.3 Contractor's Cx Agent to be present at tests performed and documented by sub-trades, suppliers and equipment manufacturers.
<u>1.13 MANUFACTURER'S INVOLVEMENT</u>	.1	Factory testing: manufacturer to: <ul style="list-style-type: none">.1 Coordinate time and location of testing..2 Provide testing documentation for approval by Departmental Representative.3 Arrange for Departmental Representative to witness tests..4 Obtain written approval of test results and documentation from Departmental Representative before delivery to site.
	.2	Obtain manufacturers installation, start-up and operations instructions prior to start-up of components, equipment and systems and review with Departmental Representative. <ul style="list-style-type: none">.1 Compare completed installation with manufacturer's published data, record discrepancies, and review with manufacturer..2 Modify procedures detrimental to equipment performance and review same with manufacturer before start-up.
	.3	Integrity of warranties: <ul style="list-style-type: none">.1 Use manufacturer's trained start-up personnel where specified elsewhere in other divisions or required to maintain integrity of warranty..2 Verify with manufacturer that testing as specified will not void warranties.
	.4	Qualifications of manufacturer's personnel: <ul style="list-style-type: none">.1 Experienced in design, installation and operation of equipment and systems..2 Ability to interpret test results accurately..3 To report results in clear, concise, logical manner.
<u>1.14 PROCEDURES</u>	.1	Verify that equipment and systems are complete, clean, and operating in normal and safe manner prior to conducting start-up, testing and Cx.
	.2	Conduct start-up and testing in following distinct phases: <ul style="list-style-type: none">.1 Included in delivery and installation:<ul style="list-style-type: none">.1 Verification of conformity to specification, approved shop drawings and completion of PI report forms..2 Visual inspection of quality of installation..2 Start-up: follow accepted start-up procedures..3 Operational testing: document equipment performance..4 System PV: include repetition of tests after correcting deficiencies..5 Post-substantial performance verification: to include fine-tuning.

<u>1.14 PROCEDURES (Cont'd)</u>	<ul style="list-style-type: none">.3 Correct deficiencies and obtain approval from Departmental Representative after distinct phases have been completed and before commencing next phase..4 Document require tests on approved PV forms..5 Failure to follow accepted start-up procedures will result in re-evaluation of equipment by an independent testing agency selected by Departmental Representative. If results reveal that equipment start-up was not in accordance with requirements, and resulted in damage to equipment, implement following:<ul style="list-style-type: none">.1 Minor equipment/systems: implement corrective measures approved by Departmental Representative..2 Major equipment/systems: if evaluation report concludes that damage is minor, implement corrective measures approved by Departmental Representative..3 If evaluation report concludes that major damage has occurred, Departmental Representative shall reject equipment.<ul style="list-style-type: none">.1 Rejected equipment to be remove from site and replace with new..2 Subject new equipment/systems to specified start-up procedures.
<u>1.15 START-UP DOCUMENTATION</u>	<ul style="list-style-type: none">.1 Assemble start-up documentation and submit to Departmental Representative for approval before commencement of commissioning..2 Start-up documentation to include:<ul style="list-style-type: none">.1 Factory and on-site test certificates for specified equipment..2 Pre-start-up inspection reports..3 Signed installation/start-up check lists..4 Start-up reports,.5 Step-by-step description of complete start-up procedures, to permit Departmental Representative to repeat start-up at any time.
<u>1.16 OPERATION AND MAINTENANCE OF EQUIPMENT AND SYSTEMS</u>	<ul style="list-style-type: none">.1 After start-up, operate and maintain equipment and systems as directed by equipment/system manufacturer..2 With assistance of manufacturer develop written maintenance program and submit Departmental Representative for approval before implementation..3 Operate and maintain systems for length of time required for commissioning to be completed..4 After completion of commissioning, operate and maintain systems until issuance of certificate of interim acceptance.
<u>1.17 TEST RESULTS</u>	<ul style="list-style-type: none">.1 If start-up, testing and/or PV produce unacceptable results, repair, replace or repeat specified starting and/or PV procedures until acceptable results are achieved..2 Provide manpower and materials, assume costs for re-commissioning.

<u>1.18 START OF COMMISSIONING</u>	.1	Notify Departmental Representative at least 21 days prior to start of Cx.
	.2	Start Cx after elements of building affecting start-up and performance verification of systems have been completed.
<u>1.19 INSTRUMENTS / EQUIPMENT</u>	.1	Submit to Departmental Representative for review and approval:
	.1	Complete list of instruments proposed to be used.
	.2	Listed data including, serial number, current calibration certificate, calibration date, calibration expiry date and calibration accuracy.
	.2	Provide the following equipment as required:
	.1	2-way radios.
<u>1.20 COMMISSIONING PERFORMANCE VERIFICATION</u>	.2	Ladders or lifts.
	.3	Equipment as required to complete work.
	.1	Carry out Cx:
	.1	Under actual or accepted simulated operating conditions, over entire operating range, in all modes.
	.2	On independent systems and interacting systems.
	.2	Cx procedures to be repeatable and reported results are to be verifiable.
	.3	Follow equipment manufacturer's operating instructions.
<u>1.21 WITNESSING COMMISSIONING</u>	.1	Departmental Representative to witness activities and verify results.
<u>1.22 AUTHORITIES HAVING JURISDICTION</u>	.1	Where specified start-up, testing or commissioning procedures duplicate verification requirements of authority having jurisdiction, arrange for authority to witness procedures so as to avoid duplication of tests and to facilitate expedient acceptance of facility.
	.2	Obtain certificates of approval, acceptance and compliance with rules and regulation of authority having jurisdiction.
	.3	Provide copies to Departmental Representative within 5 days of test and with Cx report.
<u>1.23 SUNDRY CHECKS AND ADJUSTMENTS</u>	.1	Make adjustments and changes which become apparent as Cx proceeds.
	.2	Perform static and operational checks as applicable and as required.

<u>1.24 DEFICIENCIES, FAULTS, DEFECTS</u>	.1	Correct deficiencies found during start-up and Cx to satisfaction of Departmental Representative.
	.2	Report problems, faults or defects affecting Cx to Departmental Representative in writing. Stop Cx until problems are rectified. Proceed with written approval from Departmental Representative.
<u>1.25 COMPLETION OF COMMISSIONING</u>	.1	Upon completion of Cx leave systems in normal operating mode.
	.2	Except for warranty and seasonal verification activities specified in Cx specifications, complete Cx prior to issuance of Interim Certificate of Completion.
	.3	Cx to be considered complete when contract Cx deliverables have been submitted and accepted by Departmental Representative.
<u>1.26 ACTIVITIES UPON COMPLETION OF COMMISSIONING</u>	.1	When changes are made to baseline components or system settings established during Cx process, provide updated Cx form for affected item.
<u>1.27 TRAINING</u>	.1	In accordance with Section 01 91 41 - Commissioning (Cx) - Training.
<u>1.28 MAINTENANCE MATERIALS, SPARE PARTS, SPECIAL TOOLS</u>	.1	Supply, deliver, and document maintenance materials, spare parts, and special tools as specified in contract.
<u>1.29 OWNER'S PERFORMANCE TESTING</u>	.1	Performance testing of equipment or system by Departmental Representative will not relieve Contractor from compliance with specified start-up and testing procedures.

PART 2 - PRODUCTS

<u>2.1 NOT USED</u>	.1	Not Used.
---------------------	----	-----------

PART 3 - EXECUTION

<u>3.1 NOT USED</u>	.1	Not Used.
---------------------	----	-----------

END OF SECTION

PART 1 - GENERAL**1.1 SUMMARY**

- .1 Section Includes:
- .1 Commissioning forms to be completed for equipment, system and integrated system.

**1.2 INSTALLATION/
START-UP CHECK
LISTS**

- .1 Include the following data:
- .1 Special procedures as specified in relevant technical sections.
- .1 Product manufacturer's installation instructions and recommended checks:
- .2 Items considered good installation and engineering industry practices deemed appropriate for proper and efficient operation.
- .2 Equipment manufacturer's installation/start-up check lists are acceptable for use. As deemed necessary by Departmental Representative supplemental additional data lists will be required for specific project conditions.
- .3 Use check lists for equipment installation. Document check list verifying checks have been made, indicate deficiencies and corrective action taken.
- .4 Installer to sign check lists upon completion, certifying stated checks and inspections have been performed. Return completed check lists to Departmental Representative. Check lists will be required during Commissioning and will be included in Building Maintenance Manual (BMM) at completion of project.
- .5 Use of check lists will not be considered part of commissioning process but will be stringently used for equipment pre-start and start-up procedures.

**1.3 PRODUCT
INFORMATION (PI)
REPORT FORMS**

- .1 Product Information (PI) forms compiles gathered data on items of equipment produced by equipment manufacturer, includes nameplate information, parts list, operating instructions, maintenance guidelines and pertinent technical data and recommended checks that is necessary to prepare for start-up and functional testing and used during operation and maintenance of equipment. This documentation is included in the BMM at completion of work.
- .2 Prior to Performance Verification (PV) of systems complete items on PI forms related to systems and obtain Departmental Representative's approval.

**1.4 PERFORMANCE
VERIFICATION (PV)
FORMS**

- .1 PV forms to be used for checks, running dynamic tests and adjustments carried out on equipment and systems to ensure correct operation, efficiently and function independently and interactively with other systems as intended with project requirements.
- .2 PV report forms include those developed by Contractor records measured data and readings taken during functional testing and Performance Verification procedures.

1.4 PERFORMANCE VERIFICATION (PV) FORMS (Cont'd)	.3	Prior to PV of integrated system, complete PV forms of related systems and obtain Departmental Representative's approval.
1.5 SAMPLES OF COMMISSIONING FORMS	.1	Departmental Representative will develop and provide to Contractor required project-specific Commissioning forms in electronic format complete with specification data.
	.2	Revise items on Commissioning forms to suit project requirements.
	.3	Samples of Commissioning forms and a complete index of produced to date will be attached to this section.
1.6 CHANGES AND DEVELOPMENT OF NEW REPORT FORMS	.1	When additional forms are required, but are not available from Departmental Representative develop appropriate verification forms and submit to Departmental Representative for approval prior to use.
	.1	Additional commissioning forms to be in same format as provided by Departmental Representative.
1.7 COMMISSIONING FORMS	.1	Use Commissioning forms to verify installation and record performance when starting equipment and systems.
	.2	Strategy for Use:
	.1	Departmental Representative provides Contractor project-specific Commissioning forms with Specification data included.
	.2	Contractor will provide required shop drawings information and verify correct installation and operation of items indicated on these forms.
	.3	Confirm operation as per design criteria and intent.
	.4	Identify variances between design and operation and reasons for variances.
	.5	Verify operation in specified normal and emergency modes and under specified load conditions.
	.6	Record analytical and substantiating data.
	.7	Verify reported results.
	.8	Form to bear signatures of recording technician and reviewed and signed off by Departmental Representative.
	.9	Submit immediately after tests are performed.
	.10	Reported results in true measured SI unit values.
	.11	Provide Departmental Representative with originals of completed forms.
	.12	Maintain copy on site during start-up, testing and commissioning period.
	.13	Forms to be both hard copy and electronic format with typed written results in Building Management Manual.
1.8 LANGUAGE	.1	To suit the language profile of the awarded contract.

PART 2 - PRODUCTS

2.1 NOT USED .1 Not Used.

PART 3 - EXECUTION

3.1 NOT USED .1 Not Used.

END OF SECTION

PART 1 - GENERAL

- 1.1 SUMMARY** .1 Section Includes:
.1 This Section specifies roles and responsibilities of Commissioning Training.
- 1.2 TRAINEES** .1 Trainees: personnel selected for operating and maintaining this facility. Includes Facility Manager, building operators, maintenance staff, security staff, and technical specialists as required.
.2 Trainees will be available for training during later stages of construction for purposes of familiarization with systems.
- 1.3 INSTRUCTORS** .1 Departmental Representative will provide:
.1 Descriptions of systems.
.2 Instruction on design philosophy, design criteria, and design intent.
.2 Contractor and certified factory-trained manufacturers' personnel: to provide instruction on the following:
.1 Start-Up, operation, shut-down of equipment, components and systems.
.2 Control features, reasons for, results of, implications on associated systems of, adjustment of set points of control and safety devices.
.3 Instructions on servicing, maintenance and adjustment of systems, equipment and components.
.3 Contractor and equipment manufacturer to provide instruction on:
.1 Start-up, operation, maintenance and shut-down of equipment they have certified installation, started up and carried out PV tests.
- 1.4 TRAINING OBJECTIVES** .1 Training to be detailed and duration to ensure:
.1 Safe, reliable, cost-effective, energy-efficient operation of systems in normal and emergency modes under all conditions.
.2 Effective on-going inspection, measurements of system performance.
.3 Proper preventive maintenance, diagnosis and trouble-shooting.
.4 Ability to update documentation.
.5 Ability to operate equipment and systems under emergency conditions until appropriate qualified assistance arrives.
- 1.5 TRAINING MATERIALS** .1 Instructors to be responsible for content and quality.
.2 Training materials to include:
.1 "As-Built" Contract Documents.
.2 Operating Manual.
.3 Maintenance Manual.

1.5 TRAINING
MATERIALS
(Cont'd)

- .3 Project Manager, Commissioning Manager and Property Manager will review training manuals.
- .4 Training materials to be in a format that permits future training procedures to same degree of detail.
- .5 Supplement training materials:
 - .1 Transparencies for overhead projectors.
 - .2 Multimedia presentations.
 - .3 Manufacturer's training videos.
 - .4 Equipment models.

1.6 SCHEDULING

- .1 Include in Commissioning Schedule time for training.
- .2 Deliver training during regular working hours, training sessions to be 3 hours in length.
- .3 Training to be completed prior to acceptance of facility.

1.7 RESPONSIBILITIES

- .1 Be responsible for:
 - .1 Implementation of training activities,
 - .2 Coordination among instructors,
 - .3 Quality of training, training materials,
- .2 Departmental Representative will evaluate training and materials.
- .3 Upon completion of training, provide written report, signed by Instructors, witnessed by Departmental Representative.

1.8 TRAINING
CONTENT

- .1 Training to include demonstrations by Instructors using the installed equipment and systems.
- .2 Content includes:
 - .1 Review of facility and occupancy profile.
 - .2 Functional requirements.
 - .3 System philosophy, limitations of systems and emergency procedures.
 - .4 Review of system layout, equipment, components and controls.
 - .5 Equipment and system start-up, operation, monitoring, servicing, maintenance and shut-down procedures.
 - .6 System operating sequences, including step-by-step directions for starting up, shut-down, operation of valves, dampers, switches, adjustment of control settings and emergency procedures.
 - .7 Maintenance and servicing.
 - .8 Trouble-shooting diagnosis.
 - .9 Inter-Action among systems during integrated operation.
 - .10 Review of O&M documentation.
- .3 Provide specialized training as specified in relevant Technical Sections of the construction specifications.

1.9 VIDEO-BASED
TRAINING

- .1 Manufacturer's videotapes to be used as training tool with Departmental Representative's review and written approval 1 month prior to commencement of scheduled training.
- .2 On-Site training videos:
 - .1 Videotape training sessions for use during future training.
 - .2 To be performed after systems are fully commissioned.
 - .3 Organize into several short modules to permit incorporation of changes.
- .3 Production methods to be high quality.

PART 2 - PRODUCTS2.1 NOT USED

- .1 Not Used.

PART 3 - EXECUTION3.1 NOT USED

- .1 Not Used.

END OF SECTION