

Answers to Questions

Q1. On the Unit Price Table items 3.1 – 3.4 are clear that we supply and deliver to site and do not place.

A1. Correct

Q2. For the other items (3.5 – 3.8 and 3.17 – 3.20) is this granular material in addition to the quantities in 3.1 – 3.4?

A2. No - in respect to items 3.6 to 3.8 and 3.17 to 3.20. However, there was a typographical error in the UPT - item 3.5. The unit of measurement is square meters m². It is the contractor's responsibility to prepare two (2) Temporary Work Areas each 900 m² (total area = 1,800 m²) using materials the contractor considers to be appropriate, and placed and compacted to a thickness the contractor considers to be appropriate for the contractor's own needs. Hence, the volume and type of material required is at the discretion of the contractor. This material shall be removed upon cleanup of the site. Any suitable material may be placed in the landfill embankment as directed by the Departmental Representative.

Q3. Or are we using the material in 3.1 – 3.4?

A3. Yes, except for Item 3.5, additional materials over and above what is provided under Items 3.1 to 3.4 will be required. See answer A2 above.

Q4. For the items 3.9 – 3.16 is this material used on site or disposed off-site?

A4. On site - as directed by the Departmental Representative. Inorganic materials shall be placed at the base of the existing landfill, within or adjacent to Zone 1 indicated on the drawings. Any organic material shall be segregated and stockpiled separately for later use in restoration of any disturbed ground surfaces.