



1 TRAINING ROOM (207) & FIT-UP AREA RCP DEMOLITION PLAN
E2.4 SCALE: 1 : 100

GENERAL NOTES

- A. COORDINATE ALL WORK REQUIRING SHUT-DOWN OF EXISTING SYSTEMS THAT COULD AFFECT EXISTING TENANTS WITH THE BUILDING OWNER AT A TIME AND MANNER SUITABLE TO THEM.
- B. CONTRACTOR SHALL DEMOLISH ALL EXISTING LIGHT FIXTURES COMPLETE WITH WIRING BACK TO SOURCE. REUSE EXISTING CIRCUITS FOR NEW LIGHTING FIXTURES WITHIN THE SPACE. PROVIDE TYPEWRITTEN PANEL DIRECTORIES INDICATING UPDATED CIRCUITING. TURN ALL LIGHTING COMPONENTS OVER TO BUILDING OWNER.
- C. CONTRACTOR SHALL REMOVE ALL EXISTING ABANDONED WIRING IN CEILING SPACE BACK TO SOURCE. SECURE ALL EXISTING UN-SUPPORTED WIRING, CONDUIT AND JUNCTION BOXES TO MEET MINIMUM CODE REQUIREMENTS.
- D. DEMOLISH EXISTING LOW VOLTAGE RELAY LIGHTING CONTROL SYSTEM FROM THIS SPACE. TURN ALL COMPONENTS OVER TO BUILDING OWNER.
- E. DEMOLISH ALL EXISTING SWITCHES COMPLETE WITH WIRING AND CONDUIT BACK TO SOURCE UNLESS OTHERWISE INDICATED.
- F. ALL DEVICES INDICATED WITH 'R' SHALL BE RELOCATED. INCLUDE THE COMPLETE RELOCATION OF THE EXISTING ITEM IDENTIFIED IN ITS CURRENT LOCATION ON THE DEMOLITION DRAWINGS, TO THE NEW LOCATION AS INDICATED ON THE RENOVATION DRAWINGS. INCLUDE ALL LABOUR AND MATERIALS TO REROUTE/EXTEND/REFEED THE EXISTING CIRCUITRY AS REQUIRED TO ACCOMMODATE THE RELOCATION.

KEY NOTES

- 1 DEMOLISH EXISTING LIGHT FIXTURES COMPLETE WITH WIRING, CONDUITS AND LIGHT CONTROLS.



0	ISSUED FOR CONSTRUCTION	2017-04-24
Revision	Description	Date

Client client

**PUBLIC WORK AND
GOVERNMENT SERVICES
CANADA**

CRA WINNIPEG TAX-CENTRE FIT-UP

WINNIPEG, MANITOBA

Designed by Conçu par
SV

Drawn by Dessiné par
SV

Approved by Approuvé par
MP

PWSSC Project Manager Administrateur de Projets TPSSGC
Jason Frezza

Drawing Title Titre du dessin

**SECOND FLOOR - FIT UP AREA
AND TRAINING RM #5 - LIGHTING
PLAN - DEMO**