



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Bid Receiving Public Works and Government
Services Canada/Réception des soumissions Travaux
publics et Services gouvernementaux Canada
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British Columbia
V6Z 0B9
Bid Fax: (604) 775-9381

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise
indicated, all other terms and conditions of the Solicitation
remain the same.

Ce document est par la présente révisé; sauf indication contraire,
les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Solicitation Amendment 001 is issued to release the
specifications and drawings that were not issued
with the original solicitation documents.

Vendor/Firm Name and Address

Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution

Public Works and Government Services Canada -
Pacific Region
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British C
V6Z 0B9

Title - Sujet Infrastructure Improvements Phase 2	
Solicitation No. - N° de l'invitation EZ899-173322/A	Amendment No. - N° modif. 007
Client Reference No. - N° de référence du client	Date 2017-06-02
GETS Reference No. - N° de référence de SEAG PW-\$PWY-028-8054	
File No. - N° de dossier PWY-7-40004 (028)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2017-06-07	Time Zone Fuseau horaire Pacific Daylight Saving Time PDT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Lam (PWY), Tian	Buyer Id - Id de l'acheteur pwy028
Telephone No. - N° de téléphone (604) 363-7968 ()	FAX No. - N° de FAX (604) 775-6633
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: PWGSC - Infrastructure Improvements Phase 2 - Glacier National Park - Rogers Pass, BC Maintenance Compound	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation No. - N° de l'invitation
EZ899-173322/A

Amd. No. - N° de la modif.
007

Buyer ID - Id de l'acheteur
pwy028

Client Ref. No. - N° de réf. du client

File No. - N° du dossier CCC No./N°

CCC - FMS No./N° VME

Les documents français seront disponibles sur demande.

The Solicitation Amendment 007 is raised to issue Addendum #4 and Addendum #5.

1) Please find Addendum #4 herein.

2) Please find Addendum #5 herein.

All other terms and conditions remain unchanged.

GENERAL

The following changes / clarifications in the tender documents are effective immediately. This Addendum will form part of the Contract Documents.

SPECIFICATIONS

n/a

DRAWINGS

n/a

CLARIFICATIONS

Questions Received by PWGSC to May 31, 2017

1. *Are sleeves/casing or sonotubes allowable for the precast concrete fence posts? If so, can the casing be left in the ground during the concrete encasement?*

Yes, sleeves, cases or sonotubes are allowable and may be left in the ground during the concrete encasement. The sleeves, cases or sonotubes must be in direct contact to the surrounding soil. If there are any voids between the casing, sleeve or sonotube and the surrounding soil then the voids should be infilled with concrete to maintain direct contact of the casing, sleeve or sonotube with the surrounding soil.

Additional Questions Received to May 31, 2017

1. *There appear to be trash racks missing from some storm pipe inlet headwalls. Are trash racks required to be supplied with all inlet headwalls?*

Yes. Trash racks are required to be supplied with all inlet headwalls.

2. *Critter grates were required on storm pipe inlets and outlets last year. Are they required for this years' work?*

Yes. Critter grates are required on all storm pipe inlets and outlets. Maximum grate opening should be 75mm x 125mm.

END OF ADDENDUM #4

GENERAL

The following changes / clarifications in the tender documents are effective immediately. This Addendum will form part of the Contract Documents.

SPECIFICATIONS

n/a

DRAWINGS

n/a

CLARIFICATIONS

Questions Received by PWGSC to June 01, 2017

1. *We would like to bid on this job using a Hydro International product in place of the Stormceptor product. The product is very similar and equivalent to the Stormceptor product. Would an alternative to the Stormceptor product be considered?*

Yes. Alternatives to the minimum acceptable standard as identified in Section 33 05 13.01, Part 2.1.4 will be considered, providing they provide equivalent INTERNAL bypass capabilities.

Additional Questions Received to June 01, 2017

1. *Can you please confirm the load requirement for the 3-sided box culvert and the expected cover (ie. greater than or less than 2ft)?*

Load requirement is HS-20. It can be assumed cover will be LESS than 2ft.

2. *Are perforations required on the bottom of the large detention chambers?*

No. Refer to *Typical Detention Vault Detail* on DWG Sheet C11 for perforation requirements.

3. *Is there any other planned work within Rogers Pass that would affect this project that we should be aware of?*

Yes. Planned work includes:

- a. **Approximately 400m of sanitary sewer replacement in the compound East of the TCH between June 5th and July 7th, 2017.**
- b. **Construction of a new TCH vehicle ponding area in the compound West of the TCH. This will be located at the Northern most point – within and beyond the bus turnaround loop.**

This work will be ongoing throughout the Summer/Fall of 2017.

The successful proponent will be required to work with the other Contractors onsite, and the Departmental Representative, to schedule work activities in a manner that will minimize potential scheduling conflicts.