



ADDENDUM # 1

Date: May 30, 2017

Project: 'Turnkey' Project St-Augustin Greenhouses

Bidders must make sure that their bids are based on the latest version of the tender documents published and take into consideration the following amendments and information, including any information provided on amendments or Q&A previously published for this project.

Bidders that do not comply with this requirement will be discarded.

APPENDIX E : Technical Specifications & Plans

1. Section 1.6 Project Location

ADD :

Construction project will meet HQ safety advice, according to info from HQ web site. Such as, the dimension 5875 mm between the cold greenhouse and the existing shop will be reduce to meet HQ safety advice.

<http://www.hydroquebec.com/electricity-and-you/work-lines-security/distribution-lines/approach-distances.html>

2. Section 1.7 Exterior Works

ADD :

The existing fence located at the west of the projected greenhouse will remain.

3. Section 1.10 Plumbing

CHANGE :

-Only the 25 mm existing conduit will be use by the projected greenhouse project. The existing 32mm conduit is not available for the project.

-The room for plumbing connection is # 1304, not # 1200.

ADD :

The cold water frost free outlets will be to the number of 2 for the hot greenhouse and to the number of 1 for the cold greenhouse. They are located on sketch #2.

4. Section 1.11 Electrical and control components and systems

CHANGE:

The existing room for electrical connection is # 1302, not # 1150.

ADD:

-The empty existing conduits (1 of 63 mm DIA and 2 of 50 mm DIA) between existing shop and the exterior for the electrical wires to feed the projected greenhouses are in room # 1300.



-Greenhouse control temperature alarms will be connected by the construction project to existing Honeywell panel, located in room #1302

All other terms and conditions remain the same