



SCALE: 1:125

SCALE : 1:125



GENERAL NOTES

- A. FIRE ALARM WORK IN SPECIFIC CONSTRUCTION ZONE SHOULD NOT IMPACT REMAINING PORTION OF THE FIRE ALARM SYSTEM IN THE FACILITY. PROVIDE TEMPORARY BY-PASSES AS REQUIRED.
- B. FIRE ALARM SYSTEM MUST BE FULLY OPERATIONAL AT THE END OF THE END OF EACH WORKING DAY.
- C. EXISTING ZONE SCHEDULE TO REMAIN.

NEW ZONES TO ADD:

- 1. 1ST FLOOR SPRINKLER FLOW
- 2. 2ND FLOOR SPRINKLER FLOW
- 3. 1ST FLOOR WINDOW SPRINKLER FLOW
- 4. 2ND FLOOR WINDOW SPRINKLER FLOW
- 5. AHU-1 RETURN
- 6. AHU-1 SUPPLY
- 7. AHU-2 RETURN
- 8. AHU-2 SUPPLY
- 9. AHU-5 RETURN
- 10. AHU-5 SUPPLY