



RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:
Public Works Government Services Canada- Bid
Receiving / Réception des soumissions
189 Prince William Street
Room 405
Saint John
New Brunswick
E2L 2B9
Bid Fax: (506) 636-4376

SOLICITATION AMENDMENT

MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works Government Services Canada- Bid
Receiving / Réception des soumissions
189 Prince William Street
Room 405
Saint John
New Bruns
E2L 2B9

Title - Sujet Entrance Upgrade-Fundy Natl Park,NB	
Solicitation No. - N° de l'invitation EC373-180243/A	Amendment No. - N° modif. 003
Client Reference No. - N° de référence du client R075853.001	Date 2017-06-12
GETS Reference No. - N° de référence de SEAG PW-\$PWB-013-4130	
File No. - N° de dossier PWB-7-40016 (013)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2017-06-15	
Time Zone Fuseau horaire Atlantic Daylight Saving Time ADT	
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Johnston, Edward PWB	Buyer Id - Id de l'acheteur pwb013
Telephone No. - N° de téléphone (506) 636-4416 ()	FAX No. - N° de FAX (506) 636-4376
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Cette modification à l'invitation numéro trois (3) est soumise pour inclure l'addenda numéro 3 suivant.

La modification qui suie apportée aux documents de soumission entre en vigueur dès maintenant. L'addenda fera partie des documents de contrat.

Toutes autre conditions ne changent pas.

Modification numéro 3

Questions and Answers

Q6. Dwg C-8 shows clearly an excavation of total area under septic fields of 1m deep and replacement with imported *material type not described* ?? underneath the infiltrators while the Specs say Section 33.36.33 Pg 3 describes a "trench type" septic field saying only 150 mm of washed stone under the infiltrators.

Then says Backfill trenches with material as indicated. *Material is not indicated anywhere* ??

Says to install Distribution boxes...*not shown on dwgs*

A6. Imported soils for the septic system shall be per Table 3 "Material specifications for Imported Sand" of the latest edition of the New Brunswick Technical Guidelines for On-site Sewage Disposal Systems. There shall be 1000mm of this Class A fill below the infiltrators and 300mm (Minimum) to 600mm (Maximum) over the infiltrators.

Q7. QUESTION: None of the dwgs that I see show the distance of the waterlinewhere the waterline is coming from or to..... Or the sizing.

A7. The waterline is shown on C3. It is 50mm and is approximately 6m +/- . It is to connect to the existing and be marked and capped 1m from building by civil contractor. Existing water main will have to be exposed to get exact length.

Q8. Nowhere on symbol legend or specs are cabling requirements indicated, can you please confirm category rating of cable requested as well as flamespread (FT4 or FT6) rating of cabling?

A8. FT4 used.

Q9. As no formal communications spec has been provided there is no indication that patch/line cords are required for data outlets, can you please confirm if these are required and if so can you please provide details on required lengths and quantities?

A9. Supply one (1) patch cord per drop plus 10%

- Two meters long, with factor installed male plug at one end to mate with "RJ-45" jack terminal strip with factory-installed male plug at other end to mate with "RJ-45" jack terminal strip Category 6, 4 pairs. TIA/EIA-568-B.2
- Color: blue for telephone
- Color: green for data

Q10. Riser diagram for communications cabling has not been provided and symbol legend does not indicate where communications cabling will go however there is a communications backboard identified within elec room 103. Can you please confirm that this is demark point for all cabling and that voice will terminate on BIX and data on wall mounted 24P patch panel?

A10.

- TV symbol: RG6 Coax to communications termination point

Solicitation No. - N° de l'invitation

EC373-180243/A

Client Ref. No. - N° de réf. du client

R.075853.001

Amd. No. - N° de la modif.

003

File No. - N° du dossier

PWB-7-40016

Buyer ID - Id de l'acheteur

PWB013

CCC No./N° CCC - FMS No./N° VME

-
- *Data symbol: CAT6 to data termination point*
 - *1.5" raceway to be installed within wall between each TV and the millwork below for connection to TV devices. Supply 2x HDMI cable for interconnection.*

Q11. In regards to "TV" symbol there is no indication on drawings as to what is to be installed for this, are we to assume TV is meant to indicate (1) RG6 Coax cable to room 103 unless key note adds additional items above this requirement?

A11. TV symbol – RG6 Coax to communications termination point.

DRAWINGS

1 M1.1 – Ventilation Plans

.1 Ruskin dampers to be added as an approved alternate.