



- GANGWAY CONSTRUCTION NOTES:**
- UNFACTORED DESIGN LIVE LOAD: UNIFORMLY DISTRIBUTED LOAD OF 4.8kN/m². CONCENTRATED LOAD OF 2.2kN.
 - GANGWAY AND GANGWAY HINGE PLATES FABRICATED USING ALUMINUM TO FOLLOWING: CSA HA.4. 6061-T6, CSA HA.5. 6061-T6, CSA HA.7. 6061-T6.



NOTES:

- THE DRAWINGS ARE TO BE READ IN CONJUNCTION WITH ALL OTHER PROJECT DRAWINGS AND SPECIFICATIONS.

Public Works and Government Services Canada
Travaux Publics et Services gouvernementaux Canada

0	ISSUED FOR TENDER	JUN 5 2017
revisions		date
project	WHARF CONSTRUCTION PORT BICKERTON EAST GUYSBOROUGH COUNTY NOVA SCOTIA	
drawing	GANGWAY PLAN AND DETAILS	
designed	V.L.	conçu
date	APR. 2017	
drawn	M.M.	dessiné
date	MAY 25, 2017	
approved		approuvé
date	06/06/17	
tender		
PWSC Project Manager	Administrateur de projet TPSGC	
project number	R.082082.001	
drawing no.	S15	