


| FLOATING DOCK MODULE MATERIAL LIST PER DOCK 18.0m | |
|---|---------------------------------------|
| QTY | METRIC DESIGNATION |
| 4 | 200x200x6100 LONGITUDINALS |
| 8 | 200x200x5950 LONGITUDINALS |
| 8 | 200x200x4880 LONGITUDINALS |
| 8 | 200x200x4120 LONGITUDINALS |
| 4 | 200x200x2760 LONGITUDINALS |
| 2 | 200x200x2760 (BLOCKING) LONGITUDINALS |
| 32 | 200x200x3650 CROSS-TIES |
| 2 | 200x200x3650 BLOCKING CROSS-TIES |
| 10 | 200x200x1220 SPLICE BLOCKS |
| 4 | 150x200x1220 SPLICE BLOCKS |
| 8 | 200x200x1600 BINDER POSTS |
| 8 | 200x200x1800 BINDER POSTS |
| 5 | 100x200x5226 STRINGERS |
| 5 | 100x200x2610 STRINGERS |
| 10 | 100x200x5532 STRINGERS |
| 117 * | 50x150x3650 TIMBER DECKING |
| 14 | 50x150x3650 STRAPPING |
| 7 | 50x150x1550 STRAPPING |
| 7 | 100x200x2560 UPPER BLOCKING |
| 7 | 100x200x5176 UPPER BLOCKING |
| 14 | 100x200x5432 UPPER BLOCKING |
| 2 | 100x200x7385 GUARD (CHAMFERED) |
| 2 | 100x200x8080 GUARD |
| 1 | 100x200x3450 GUARD |
| 29 | 100x200x400 GUARD CHOCKS |

*EXACT NUMBER OF DECKING MAY VARY DUE TO VARIATIONS IN WIDTH AND SPACING OF PLANKS. DECKING TO BE MILLED ONE SIDE TO ENSURE EVEN THICKNESS AND INSTALLED ROUGH SIDE UP.



0 ISSUED FOR TENDER JUN 5 2017
 revisions
 project WHARF CONSTRUCTION PORT BICKERTON EAST GUYSBOROUGH COUNTY NOVA SCOTIA

drawing
 design
 FLOATING WHARVES

designed V.L. conquis
 date APR. 2017
 drawn M.M. dessiné
 date MAY 25, 2017
 approved M. Walu 06/06/17 approuvé
 date
 Tender
 PWSC Project Manager
 project number R.082082.001
 drawing no. S17

NOTES:
 1. THE DRAWINGS ARE TO BE READ IN CONJUNCTION WITH ALL OTHER PROJECT DRAWINGS AND SPECIFICATIONS