

TENDER ADDENDUM

**Fire Protection Systems Preventative Maintenance
NCC tender file # LW065
June 19, 2017**

ADDENDUM NO : 2

ADDENDA À LA SOUMISSION

**Programme d'entretien complet des systèmes de
protection contre les incendies
Dossier de soumission de la CCN no. LW065
le 19 juin 2017**

ADDENDA NO: 2

The following shall be read in conjunction with and shall form an integral part of the Tender / Proposal and Contract Documents :

Ce qui suit doit être interprété comme faisant partie intégrante de la proposition/appeal d'offres et des documents relatifs au contrat:

1. REQUEST FOR INFORMATION

1. DEMANDE D'INFORMATION

Q1. In Section 50 01 02, Part 1.2 Affected Building Systems, there are 14 buildings with fire alarm system. However, in the RFP documents it seems there are only reports for only nine of them.

Q1. Dans la section 50 01 02, partie 1.2 Systèmes de bâtiments affectés, il y a 14 bâtiments avec système d'alarme incendie. Cependant, dans les documents de la DP, il semble qu'il n'y ait que des rapports pour seulement neuf d'entre eux.

A1. Please find attached reports for: 2-HL, 3-TF, 4-10S, and 6-7RG. 8-CsGR is currently under construction.

R1. Veuillez trouver les rapports ci-joints pour: 2-HL, 3-TF, 4-10S et 6-7RG. Le 8-CsGR est actuellement en construction.

Q2. In Section 50 01 02, one of the test reports has a building number of "NCC", what building does this report belong to?

Q2. Dans la section 50 01 02, un des rapports de test a un numéro de bâtiment de "NCC", à quel bâtiment ce rapport appartient-il?

A2. This report is for building 1-FGH.

R2. Ce rapport est pour le bâtiments 1-FGH.

Q3. Is weekly Fire Pump Testing part of this bid, as it is part of NFPA-25? Also, is the Fire Alarm Inspection on a frequency of Monthly x 11 and Annual x 1?

Q3. L'essai hebdomadaire de pompage d'incendie fait-il partie de cette offre, car elle fait partie de la NFPA-25? De plus, l'inspection de la système d'alarme d'incendie ce fait-elle sur une fréquence de: mensuelle x 11 et annuelle x 1?

A3. Fire pump testing shall occur on a monthly basis. Fire alarm testing shall occur on a monthly basis.

R3. Le test de la pompe à incendie doit se faire sur une base mensuelle. Les tests d'alarme incendie doivent être effectués sur une base mensuelle.



Lana Wilson
Senior Contract Officer
Procurement Services



Lana Wilson
Agent principal des contrats
Services d'approvisionnement



Individual Device Record

Generated by: BuildingReports.ca

Type of Inspection: Fire Alarm System Annual Inspection and Test (ULC S536)

Project Name: [Redacted]

Inspection Date and Time: 8/5/16 8:07:06 AM

Inspector:

Note: Reading Column: Detector sensitivity in percentage and Waterflow Switch time delay in seconds.

Building: 2-HL

The Individual Device Record lists each device type, it's exact location within the building, the corresponding zone or address of the device, and confirmation checkboxes indicating satisfactory test results for each ULC test requirement. Devices that are in need of service and repair are clearly indicated.

<input type="checkbox"/> Location	Device Type	Zone/Address	Reading	Correctly Installed	Requires Service or Repairs	Alarm Operation / Activation Confirmed	Annunciation Indication Confirmed	Supervision	Ground Circuit Confirmed
Basement By Electrical Room	Bell	1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Basement By Electrical Room	Heat Detector	1-1-1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Basement By Exit Stair	Pull Station	1-1-1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Basement By Exit Stairs	Heat Detector	1-1-1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Basement By Furnace Room	Heat Detector	1-1-1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Basement Center	Heat Detector	1-1-1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Basement Electrical Room	Battery	2		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Basement Electrical Room	Control Panel	1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Basement Electrical Room	Heat Detector	1-1-1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Basement Electrical Room (2nd Floor)	End Of Line	1-1-3		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Basement Electrical Room (Attic)	End Of Line	1-1-5		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Basement Electrical Room (Basement)	End Of Line	1-1-1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Basement Electrical Room (Bell CCT)	End Of Line	1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Basement Electrical Room (East Stair Case)	End Of Line	1-1-4		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Basement Electrical Room (Ground Floor)	End Of Line	1-1-2		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Basement In Furnace Room	Heat Detector	1-1-1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Basement Top of Exit Stairs	Heat Detector	1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
1st By Main Stair	Bell	1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1st By Main Stair	Pull Station	1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
1st In bedroom #1	Smoke Detector	1-1-2		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
1st In office	Smoke Detector	1-1-2		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
1st In storage by office	Heat Detector	1-1-2		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2nd By Bathroom #1	Smoke Detector	1-1-3		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2nd By Bathroom #2	Smoke Detector	1-1-3		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2nd By bedroom #2	Smoke Detector	1-1-3		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2nd By Office	Bell	1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>



2nd By Office	Pull Station	1-1-3	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2nd By Office	Smoke Detector	1-1-3	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2nd Garage Addic	Bell	1	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2nd In bedroom #1	Smoke Detector	1-1-3	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2nd In bedroom #2	Smoke Detector	1-1-3	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2nd Top of Center stair	Smoke Detector	1-1-4	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2nd Top of Main Stair	Smoke Detector	1-1-3	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Gaurde House Gaurde Office	Annunciator	1	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Gaurde House Gaurde Office	Horn/Strobe	1	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>



Battery & Power Supply Testing

Generated by: BuildingReports.ca

Building: 2-HL		Control Panel: 1 - EST Quick Start					
<p><i>The Control & Power Testing section details the readings and measurements of batteries and power supplies used to provide power to the fire alarm and life safety systems. Items are grouped by Passed or Failed/Other.</i></p>							
Type	Location	Rated Ah	Rated Volts	Pre Test	Post Test	Min Ah	Tested Ah
<i>Passed</i>							
Control Panel							
Basement Electrical Room							



Building: 2-HL		Control Panel: 2					
<p><i>The Control & Power Testing section details the readings and measurements of batteries and power supplies used to provide power to the fire alarm and life safety systems. Items are grouped by Passed or Failed/Other.</i></p>							
Type	Location	Rated Ah	Rated Volts	Pre Test	Post Test	Min Ah	Tested Ah
<i>Passed</i>							
Battery							
Basement Electrical Room							



Inventory & Warranty Report

Generated by: BuildingReports.ca

Building: 2-HL		Control Panel: 1 - EST Quick Start		
<p><i>The Inventory & Warranty Report lists each of the devices and items that are included in your Inspection Report. A complete inventory count by device type and category is provided. Items installed within the last 90 days, within the last year, and devices installed for two years or more are grouped together for easy reference.</i></p>				
Device or Item	Category	% of Inventory		Quantity
Heat Detector	Initiating	22.86%		8
Bell	Indicating	11.43%		4
End Of Line	Supervisory	17.14%		6
Battery	Control	2.86%		1
Pull Station	Initiating	8.57%		3
Control Panel	Control	2.86%		1
Smoke Detector	Initiating	28.57%		10
Annunciator	Control	2.86%		1
Horn/Strobe	Indicating	2.86%		1
Type	Qty	Model #	Description	Install Date
<i>In Service - 2 Years to 3 Years</i>				
Edwards				
Annunciator	1	MB6-24		10/22/2014
Bell	1	MB10-24		10/22/2014
Bell	3	MB6-24		10/22/2014
Heat Detector	8	281	Rate-of-Rise	10/22/2014
Horn/Strobe	1	MULTI-CD-STR		10/22/2014
		OBE		
Pull Station	3	SPO-270		10/22/2014
Smoke Detector	8	C2M-PDC	Photoelectric	10/22/2014
Smoke Detector	2	C2M-PDV	Photoelectric	10/22/2014
EST				
Control Panel	1	Quick Start		10/22/2014
End Of Line	6			10/22/2014



Building: 2-HL Control Panel: 2

The Inventory & Warranty Report lists each of the devices and items that are included in your Inspection Report. A complete inventory count by device type and category is provided. Items installed within the last 90 days, within the last year, and devices installed for two years or more are grouped together for easy reference.

Type	Qty	Model #	Description	Install Date
<i>In Service - 2 Years to 3 Years</i>				
EST				
Battery	1	2 x 12v12ah		10/22/2014



Individual Device Record

Generated by: BuildingReports.ca

Type of Inspection: Fire Alarm System Annual Inspection and Test (ULC S536)

Project Name:

Inspection Date and Time: 8/5/16 12:05:48 PM

Inspector: :

Note: Reading Column: Detector sensitivity in percentage and Waterflow Switch time delay in seconds.

Building:

The Individual Device Record lists each device type, it's exact location within the building, the corresponding zone or address of the device, and confirmation checkboxes indicating satisfactory test results for each ULC test requirement. Devices that are in need of service and repair are clearly indicated.

<input type="checkbox"/> Location	Device Type	Zone/Address	Reading	Correctly Installed	Requires Service or Repairs	Alarm Operation / Activation Confirmed	Annunciation Indication Confirmed	Supervision	Ground Circuit Confirmed
Basement By Electrical Panels	Control Panel	1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Basement Panel A Breaker #17	Disconnect	2		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Basement At Furnace Room	Bell	1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Basement Bathroom	Heat Detector	1-1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Basement Closet by Furnace Room	Heat Detector	1-1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Basement electrical panel	Battery	1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Basement entrance	End Of Line	1-1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Basement Entrance to Basement	Heat Detector	1-1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Basement Furnace Room	Heat Detector	1-1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Basement Open Area	Heat Detector	1-1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Basement Open Area	Heat Detector	1-1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Basement Outside Bathroom	Pull Station	1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Basement Outside Furnace Room	Pull Station	1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Basement Over Water Tanks	Heat Detector	1-1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Basement Paint Storage Room	Heat Detector	1-1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Basement Wine storage	Heat Detector	1-1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
1st Exit At Kitchen	Annunciator	1		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1st Front Entrance	Pull Station	1-3		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
1st Main Entrance	Bell	1-3		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
1st Top Of Basement Stair	Heat Detector	1-3		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
1st Top Of Basement Stair	Pull Station	1-3		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2nd By Bathroom	Bell	1-4		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2nd Top Of Stair	Bell	1-4		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
2nd Top Of Stair	End Of Line	1-4		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
2nd Top Of Stair	End Of Line	1-BCCT 2		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
2nd Top Of Stair	Pull Station	1-4		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
2nd Top Of Stair	Smoke Detector	1-4		<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>



Attic Attic	End Of Line	1-5	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Attic Attic	Heat Detector	1-5	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Attic Attic	Heat Detector	1-5	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Attic Attic	Heat Detector	1-5	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Ground Generator Room	Heat Detector	1-2	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>



Battery & Power Supply Testing

Generated by: BuildingReports.ca

Building: 3-TF		Control Panel: 1 - Edwards 2280					
<p><i>The Control & Power Testing section details the readings and measurements of batteries and power supplies used to provide power to the fire alarm and life safety systems. Items are grouped by Passed or Failed/Other.</i></p>							
Type	Location	Rated Ah	Rated Volts	Pre Test	Post Test	Min Ah	Tested Ah
<i>Passed</i>							
Battery	Basement electrical panel						
Control Panel	Basement By Electrical Panels						



Inventory & Warranty Report

Generated by: BuildingReports.ca

Building: Control Panel: 1 - Edwards 2280

The Inventory & Warranty Report lists each of the devices and items that are included in your Inspection Report. A complete inventory count by device type and category is provided. Items installed within the last 90 days, within the last year, and devices installed for two years or more are grouped together for easy reference.

Device or Item	Category	% of Inventory	Quantity
Heat Detector	Initiating	43.75%	14
Pull Station	Initiating	15.62%	5
End Of Line	Supervisory	12.50%	4
Bell	Indicating	12.50%	4
Disconnect	Control	3.12%	1
Battery	Control	3.12%	1
Control Panel	Control	3.12%	1
Annunciator	Control	3.12%	1
Smoke Detector	Initiating	3.12%	1

Type	Qty	Model #	Description	Install Date
<i>In Service - 2 Years to 3 Years</i>				
Battery	1	2x 12v 4.5AH		08/15/2014
End Of Line	4			08/15/2014
Edwards				
Annunciator	1		LED List	08/15/2014
Bell	4	20-24vcc/doc		08/15/2014
Control Panel	1	2280		08/15/2014
Heat Detector	6	281A		08/15/2014
Heat Detector	3	281A	Rate-of-Rise	08/15/2014
Heat Detector	4	281C	Fixed Temperature	08/15/2014
Heat Detector	1	281C	Rate-of-Rise	08/15/2014
Pull Station	5	SPO-270		08/15/2014
Smoke Detector	1	6249		08/15/2014



Building: 3-TF Control Panel: 2

The Inventory & Warranty Report lists each of the devices and items that are included in your Inspection Report. A complete inventory count by device type and category is provided. Items installed within the last 90 days, within the last year, and devices installed for two years or more are grouped together for easy reference.

Type	Qty	Model #	Description	Install Date
<i>In Service - 2 Years to 3 Years</i>				
Edwards				
Disconnect	1		Breaker	08/15/2014