

SMALL CRAFT HARBOURS
CENTRAL AND ARCTIC REGION



NOTES

- 1: NORTH SECTION SUPERSTRUCTURE TO BE DEMOLISHED
- 2: ALL TIMBER PILES TO BE REMOVED
- 3: STEEL SHEET PILES TO BE DRIVEN AROUND OUTLINE OF NEW STRUCTURE
- 4: CONCRETE ANCHOR BLOCK TO BE CAST IN PLACE AT STATION 323
- 5: TIE RODS TO BE INSTALLED AT 2.52m (E-W) AND 3.58m (N-S) SPACING
- 6: 6.35m OF 20-50mm CRUSHED STONE TO BE PLACED WITHIN NEW STEEL SHEET PILES
- 7: 600mm GRAN B TO BE POURED ATOP CRUSHED STONE, FOLLOWED BY GEOTEXTILE CLOTH, AND 150mm GRAN A
- 8: 150mm REINFORCED CONCRETE DECK TO BE PLACED ATOP FILL AND GEOTEXTILE

PLANMAC
ENGINEERING INC.

80 North Queen Street, Suite 302
Toronto, ON, Canada, M8Z 2C9
Tel. (416) 626 - 5300 FAX: (416) 622 - 6710

REVISIONS:	DATE:
4	100% SUBMISSION
3	99% SUBMISSION
2	66% SUBMISSION
1	PRELIMINARY DESIGN

SCALE:	CLASS:
AS NOTED	

PROJECT:

WEST PIER
REHABILITATION

DESCRIPTION:
PROPOSED NORTH END
AND CONNECTION DETAILS

DRAWN:	APPROVED:
S.D.	R.I.M.

DATE:	DATE:
MAR 2017	

LOCATION:

RONDEAU (ERIEAU)
HARBOUR
ONTARIO

DRAWING NO.:	LOCATOR CODE:
13	4797

