



**RETURN BIDS TO:
RETOURNER LES SOUMISSIONS À:**

**Bid Receiving - PWGSC / Réception des
soumissions - TPSGC**

11 Laurier St. / 11, rue Laurier

Place du Portage , Phase III

Core 0B2 / Noyau 0B2

Gatineau

Québec

K1A 0S5

Bid Fax: (819) 997-9776

**REQUEST FOR PROPOSAL
DEMANDE DE PROPOSITION**

**Proposal To: Public Works and Government
Services Canada**

We hereby offer to sell to Her Majesty the Queen in right of Canada, in accordance with the terms and conditions set out herein, referred to herein or attached hereto, the goods, services, and construction listed herein and on any attached sheets at the price(s) set out therefor.

**Proposition aux: Travaux Publics et Services
Gouvernementaux Canada**

Nous offrons par la présente de vendre à Sa Majesté la Reine du chef du Canada, aux conditions énoncées ou incluses par référence dans la présente et aux annexes ci-jointes, les biens, services et construction énumérés ici sur toute feuille ci-annexée, au(x) prix indiqué(s).

Comments - Commentaires

Vendor/Firm Name and Address

Raison sociale et adresse du

fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution

**Ship Construction, Refit and Related Services/Construction
navale, Radoubs et services connexes**

11 Laurier St. / 11, rue Laurier

6C2, Place du Portage

Gatineau

Québec

K1A 0S5

Title - Sujet 6.5 - 6.7m Aluminum Cabin Boat	
Solicitation No. - N° de l'invitation F7044-170014/A	Date 2017-06-28
Client Reference No. - N° de référence du client F7044-170014	
GETS Reference No. - N° de référence de SEAG PW-\$\$MC-032-26359	
File No. - N° de dossier 032mc.F7044-170014	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2017-08-08	Time Zone Fuseau horaire Eastern Daylight Saving Time EDT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Girard, Luc J.	Buyer Id - Id de l'acheteur 032mc
Telephone No. - N° de téléphone (819) 420-5807 ()	FAX No. - N° de FAX () -
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: Specified Herein Précisé dans les présentes	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée See Herein	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

TABLE OF CONTENTS

PART 1 - GENERAL INFORMATION	3
1.1 INTRODUCTION.....	3
1.2 SUMMARY	3
1.3 DEBRIEFINGS	3
PART 2 - BIDDER INSTRUCTIONS.....	4
2.1 STANDARD INSTRUCTIONS, CLAUSES AND CONDITIONS.....	4
2.2 SUBMISSION OF BIDS.....	4
2.3 ENQUIRIES - BID SOLICITATION.....	4
2.4 APPLICABLE LAWS.....	4
2.5 IMPROVEMENT OF REQUIREMENT DURING SOLICITATION PERIOD.....	5
PART 3 - BID PREPARATION INSTRUCTIONS.....	5
3.1 BID PREPARATION INSTRUCTIONS	5
3.2 SECTION I: TECHNICAL BID	6
3.3 SECTION II: MANAGEMENT BID	8
3.4 SECTION III: FINANCIAL BID.....	9
3.5 SECTION IV: CERTIFICATIONS.....	11
PART 4 - EVALUATION PROCEDURES AND BASIS OF SELECTION	11
4.1 EVALUATION PROCEDURES.....	11
4.2 BASIS OF SELECTION.....	12
PART 5 – CERTIFICATIONS	12
5.1 CERTIFICATIONS REQUIRED WITH THE BID	12
5.2 CERTIFICATIONS PRECEDENT TO CONTRACT AWARD AND ADDITIONAL INFORMATION	13
PART 6 - SECURITY, FINANCIAL AND OTHER REQUIREMENTS.....	13
6.1 SECURITY REQUIREMENT.....	13
6.2 FINANCIAL CAPABILITY	14
6.3 INSURANCE REQUIREMENTS	14
PART 7 - RESULTING CONTRACT CLAUSES	15
7.1 REQUIREMENT	15
7.2 STANDARD CLAUSES AND CONDITIONS.....	15
7.3 SECURITY REQUIREMENTS	15
7.4 TERM OF CONTRACT	15
7.5 AUTHORITIES	16
7.6 PAYMENT	17
7.7 INVOICING INSTRUCTIONS	18
7.8 CERTIFICATIONS	19
7.9 PROJECT SCHEDULE	20
7.10 PROGRESS REPORT	20
7.11 SACC MANUAL CLAUSES	21
7.12 TRADE QUALIFICATIONS.....	21
7.13 QUALITY MANAGEMENT SYSTEMS	21
7.14 POST CONTRACT AWARD/PRE-PRODUCTION MEETING	22
7.15 MANUALS	22

7.16	INSPECTION, TEST & TRIALS.....	22
7.17	INSURANCE REQUIREMENTS	22
7.18	APPLICABLE LAWS.....	25
7.19	PRIORITY OF DOCUMENTS	25
7.20	ACCEPTANCE.....	26
7.21	GOVERNMENT SUPPLIED MATERIAL	26
ANNEX "A"	27
	TECHNICAL STATEMENT OF REQUIREMENT (TSOR)	27
ANNEX "B"	28
	COST BREAKDOWN	28
ANNEX "C"	29
	SUBCONTRACTORS	29
ANNEX "D"	30
	BIDDERS QUESTIONS AND CANADA RESPONSES	30
ANNEX "E"	31
	INSPECTION / QUALITY ASSURANCE / QUALITY CONTROL	31

PART 1 - GENERAL INFORMATION

1.1 Introduction

The bid solicitation is divided into seven parts plus attachments and annexes, as follows:

- Part 1 General Information: provides a general description of the requirement;
- Part 2 Bidder Instructions: provides the instructions, clauses and conditions applicable to the bid solicitation;
- Part 3 Bid Preparation Instructions: provides Bidders with instructions on how to prepare their bid;
- Part 4 Evaluation Procedures and Basis of Selection: indicates how the evaluation will be conducted, the evaluation criteria that must be addressed in the bid, and the basis of selection;
- Part 5 Certifications and Additional Information: includes the certifications and additional information to be provided;
- Part 6 Security, Financial and Other Requirements: includes specific requirements that must be addressed by Bidders; and
- Part 7 Resulting Contract Clauses: includes the clauses and conditions that will apply to any resulting contract.

The Annexes include the Technical Statement of Requirement, the Cost Breakdown, the Subcontractors' list, Bidders Questions and Canada Responses, the Inspection /Quality Assurance/Quality Control and any other annexes.

1.2 Summary

The Department of Fisheries and Oceans Canada has a requirement to purchase one 6.5 to 6.7m aluminum cabin boat with trailer, built in accordance with Annex "A" - Technical Statement of Requirement (TSOR) and Annex "D" - Bidder Questions and Canada Responses.

All deliverables must be delivered to Fredericton, New Brunswick, Canada by December 15, 2017.

The requirement is subject to the provisions of the North American Free Trade Agreement (NAFTA) and the agreement on Internal Trade (AIT).

1.3 Debriefings

Bidders may request a debriefing on the results of the bid solicitation process. Bidders should make the request to the Contracting Authority within 15 working days from receipt of the results of the bid solicitation process. The debriefing may be in writing, by telephone or in person.

PART 2 - BIDDER INSTRUCTIONS

2.1 Standard Instructions, Clauses and Conditions

All instructions, clauses and conditions identified in the bid solicitation by number, date and title are set out in the *Standard Acquisition Clauses and Conditions Manual* (<https://buyandsell.gc.ca/policy-and-guidelines/standard-acquisition-clauses-and-conditions-manual>) issued by Public Works and Government Services Canada.

Bidders who submit a bid agree to be bound by the instructions, clauses and conditions of the bid solicitation and accept the clauses and conditions of the resulting contract.

The 2003 2017-04-27, Standard Instructions - Goods or Services - Competitive Requirements, are incorporated by reference into and form part of the bid solicitation.

2.1.1 SACC Manual Clauses

A9125T 2007-05-25, Valid Labour Agreement
B1000T 2014-06-26, Condition of Material – Bid
B3000T 2006-06-16, Equivalent Products

2.2 Submission of Bids

Bids must be submitted only to Public Works and Government Services Canada (PWGSC) Bid Receiving Unit by the date, time and place indicated on page 1 of the bid solicitation.

Due to the nature of the bid solicitation, bids transmitted by facsimile to PWGSC will not be accepted.

2.3 Enquiries - Bid Solicitation

All enquiries must be submitted in writing to the Contracting Authority no later than **seven** calendar days before the bid closing date. Enquiries received after that time may not be answered.

Bidders should reference as accurately as possible the numbered item of the bid solicitation to which the enquiry relates. Care should be taken by Bidders to explain each question in sufficient detail in order to enable Canada to provide an accurate answer. Technical enquiries that are of a proprietary nature must be clearly marked "proprietary" at each relevant item. Items identified as "proprietary" will be treated as such except where Canada determines that the enquiry is not of a proprietary nature. Canada may edit the question(s) or may request that the Bidder do so, so that the proprietary nature of the question(s) is eliminated and the enquiry can be answered to all Bidders. Enquiries not submitted in a form that can be distributed to all Bidders may not be answered by Canada.

2.4 Applicable Laws

Any resulting contract must be interpreted and governed, and the relations between the parties determined, by the laws in force in the Province of Ontario.

Bidders may, at their discretion, substitute the applicable laws of a Canadian province or territory of their choice without affecting the validity of their bid, by deleting the name of the Canadian province or territory specified and inserting the name of the Canadian province or territory of their choice. If no change is made, it acknowledges that the applicable laws specified are acceptable to the Bidders.

2.5 Improvement of Requirement during Solicitation Period

Should bidders consider that the specifications or Statement of Work contained in the bid solicitation could be improved technically or technologically, bidders are invited to make suggestions, in writing, to the Contracting Authority named in the bid solicitation. Bidders must clearly outline the suggested improvement as well as the reason for the suggestion. Suggestions that do not restrict the level of competition nor favour a particular bidder will be given consideration provided they are submitted to the Contracting Authority at least **seven** days before the bid closing date. Canada will have the right to accept or reject any or all suggestions.

PART 3 - BID PREPARATION INSTRUCTIONS

3.1 Bid Preparation Instructions

Canada requests that Bidders provide their bid in separately bound sections as follows:

- Section I: Technical Bid, two hard copies and one soft copy on USB drive
- Section II: Management Bid, two hard copies and one soft copy on USB drive
- Section III: Financial Bid, one hard copy and one soft copy on USB drive
- Section IV: Certifications, one hard copy and one soft copy on USB drive

If there is a discrepancy between the wording of the soft copy and the hard copy, the wording of the hard copy will have priority over the wording of the soft copy.

Two (2) packages must be provided with the bid as follows;

Package 1:

One hard copy of Sections I, II, III and IV; and one soft copy of sections I, II, III and IV.

Package 2:

One hard copy of sections I and II only.

Prices must appear in Section III, Financial bid only.

Canada requests that Bidders follow the format instructions described below in the preparation of their bid:

- (a) use 8.5 x 11 inch (216 mm x 279 mm) paper;
- (b) use a numbering system that corresponds to the bid solicitation.

In April 2006, Canada issued a policy directing federal departments and agencies to take the necessary steps to incorporate environmental considerations into the procurement process [Policy on Green Procurement](http://www.tpsgc-pwgsc.gc.ca/ecologisation-greening/achats-procurement/politique-policy-eng.html) (<http://www.tpsgc-pwgsc.gc.ca/ecologisation-greening/achats-procurement/politique-policy-eng.html>). To assist Canada in reaching its objectives, Bidders should:

- 1) use 8.5 x 11 inch (216 mm x 279 mm) paper containing fibre certified as originating from a sustainably-managed forest and containing minimum 30% recycled content; and

- 2) use an environmentally-preferable format including black and white printing instead of colour printing, printing double sided/duplex, using staples or clips instead of cerlox, duotangs or binders.

3.2 Section I: Technical Bid

In their technical bid, Bidders should demonstrate their understanding of the requirements contained in the bid solicitation and explain how they will meet these requirements. Bidders should demonstrate their capability in a thorough, concise and clear manner for carrying out the work.

The technical bid must address clearly and in sufficient depth the points that are subject to the evaluation criteria against which the bid will be evaluated. Simply repeating the statement contained in the bid solicitation is not sufficient. In order to facilitate the evaluation of the bid, Canada requests that Bidders address and present topics in the order of the evaluation criteria under the same headings. To avoid duplication, Bidders may refer to different sections of their bids by identifying the specific paragraph and page number where the subject topic has already been addressed.

In addition to providing the above mentioned documentation, Bidders must provide all documentation requested in the following articles, **3.2.1, 3.2.2, 3.2.3 and 3.2.4.**

3.2.1 Preliminary Project Schedule

1. As part of its technical bid, the Bidder must propose its preliminary project schedule, in MS Project format or equivalent. The project schedule must include the Bidder's work breakdown structure, the scheduling of main activities and milestone events, and any potential problem areas involved in completing the Work.
2. The Bidder's schedule must also provide a target date for each of the following significant events as applicable:

- (a) hull materials delivered to Contractor and sustained construction commenced;
- (b) hull and deck completed, but not closed in to allow for full inspection of the structure and welding.

The Contractor will be required to supply a hard copy of the material certs and construction drawings to the Technical/Inspection Authority **one week** prior to inspection by the Technical/Inspection Authority;

- (c) outfitting/electrical 75% complete but all equipment and components delivered to the Contractor and available for full inspection. The Contractor will be required to supply a hard copy of the list of equipment and electrical supplies to the Technical/Inspection Authority **one week** prior to inspection by the Technical/Inspection Authority;
- (d) technical manuals delivered to Canada for approval (no less than 14 days prior to the planned delivery date);
- (e) Contractor's tests and trial and final sea trials required by the TSOR;
- (f) boat and trailer delivered to Canada for approval;
- (g) the start and the end of the twelve month warranty period.

Note: Technical Manuals will not be returned once approved.

3. It is intended to award the Contract by August 30, 2017.

3.2.2 Proven Hull

The vessel must be built based on stock small working or commercial vessel hull forms with a minimum of customization as indicated in the TSOR. A prototype hull will not be considered for this requirement.

Bidders must provide documentation for a minimum of **two proven aluminum hulls similar to the requirement of this RFP (overall length between 5.8m and 8.5m)** which have been produced and in service within the last five (5) years in accordance with TP 1332 ISO category "C".

Documentation required for each proven hull must include:

- (a) general arrangement drawings;
- (b) photographs;
- (c) references; and
- (d) hull identification numbers (Transport Canada registration numbers)

3.2.3 Preliminary Data Package

Bidders must submit a preliminary data package to demonstrate that the vessel will be fully seaworthy, operable and fit in all regards for the purposes intended. **The Preliminary Data Package must be in accordance with the TSOR** and include at a minimum, the following technical drawings and information:

- (a) as identified in TP 14612, a certificate of approval following the procedures contained therein;
- (b) general arrangement;
- (c) structural drawings showing deck plan, centerline profile and frame station construction details;
- (d) detailed lines plan;
- (e) drawing of the fuel supply arrangement;
- (f) drawing of bilge pumping system;
- (g) electrical one-line diagram;
- (h) calculated lightship weight; and
- (i) draft stability calculation of the proposed vessel.

3.2.4 Government Supplied Material (GSM)

The following equipment will be Government Supplied Material (GSM) and must be installed, mounted, set-up, fully functional and in accordance with each manufacturer's installation recommendations.

1. Two 115 HP Yamaha gasoline outboard engines;
2. Raymarine C127 Multifunction Navigation Display with 12.1" Sunlight Viewable Color display, model E02022 or equivalent. Plotter mounted on vessel dash, and minimizes interference with operator's vision;
3. RD24-24"High Performance 4KW Raydome Antenna E-52067 with 15m cable;
4. Raymarine Raystar 125 GPS Sensor E32042 Navionics Chart for appropriate areas;
5. Raymarine E66008 in Hull Depth Adjustable Angled in Hull Transducer;
6. Raymarine DSM300 Digital Sounder Module, model E63069;
7. Raymarine Smart Heading System for Pathfinder model E12102 Gyro Stabilized Fluxgate Compass System;
8. ICOM IC M604 VHF DSC radio. Complete with loud hailer/intercom function plumbed to Radio;

9. Antenna, specification is Comrod AV60P 8 and Shakespeare 4187 HD ratchet mount;
10. Whelan Loud Hailer / Siren;
11. Clarion 435 CD AM/FM stereo; and
12. One (1) externally mounted EPIRB RLS 406MZ beacon.

Note: The engines and electronic parts will be shipped to the Contractor's facility within 1- 2 months after award of Contract for installation by the Contractor.

3.3 Section II: Management Bid

In their management bid, bidders must describe their capability and experience, the project management team and provide client contact(s) information including email address.

In addition of providing the above mentioned information, Bidders must provide all documentation as requested in the following articles, **3.3.1, 3.3.2, 3.3.3, 3.3.4, 3.3.5 and 3.3.6.**

3.3.1 Inspection and Test Plan (ITP)

1. Bidders must provide with their bid the inspection plan and testing procedures that will be used to verify, test and inspect all of the components and systems on the boat from initial construction to completion. The ITP must be in accordance with **Annex "E"** attached to this RFP.

Bidders must outline the process by which they will address and solve problems or delays with the fabrication, installations, testing and delivery of the boat.

3.3.2 Subcontractors

A list, in the form of the attached **Annex "C"** of subcontracts for labor and/or material must be included with the Bidder's Proposal, stating the name and address of each subcontractor, and a description (Make, Model No.) of the goods or services to be supplied by each.

3.3.3 Vessel Construction Experience

The Bidder must provide objective evidence that it has a proven capability in the construction of vessels of the size, type and complexity which is the subject to this RFP, by providing a detailed list of such boats built within the last **five** years.

The technical bid must also demonstrate the firm has the facilities, management and the technical expertise.

3.3.4 Marine Drafting and Engineering Capability

The Bidder must provide objective evidence that it has either in-house capabilities, or has a written commitment for the duration of the Contract from a supplier to provide marine drafting and engineering services. The supplier must have the experience and capabilities on similar vessel construction projects (same size, type and complexity).

3.3.5 Contractor Quality Management System

1. The Bidder must provide objective evidence that it has a Quality Assurance Program, which must be in place during the performance of the Work, and should address the quality control elements below.

2. The objective evidence may be in the form of a copy of the Bidder's Quality Assurance Manual which should address these elements. Proof of registration with a recognized quality assurance organization whose system should address the minimum requirements below, may be submitted for consideration.

3. The quality control elements should, as a minimum, be:

- Management Representative
- Quality Assurance Manual
- Quality Assurance Program Descriptions
- Quality Reporting Organization
- Documentation
- Measuring and Testing Equipment
- Procurement
- Inspection and Test Plan
- Incoming Inspection
- In-Process Inspection
- Final Inspection
- Special Processes
- Quality Records
- Non Conformance
- Corrective Action

4. Bidder facilities may be audited by Canada, or its authorized representative, prior to award of contract to ensure that a system is in place in accordance with the foregoing requirement.

5. The Contractor will be required to submit completed quality assurance documentation with each claim for payment, as applicable.

3.3.6 Contractor's Representative

Bidder must provide their contact information:

Name: _____

Title: _____

Telephone: _____

E-mail address: _____

3.4 Section III: Financial Bid

Bidders must submit their financial bid in accordance with the BASIS OF PAYMENT and the following articles, 3.4.1, 3.4.2, 3.4.3, 3.4.4 and 3.4.5. The total amount of the applicable taxes must be shown separately.

3.4.1 Exchange Rate Fluctuation

The requirement does not offer exchange rate fluctuation risk mitigation. Requests for exchange rate fluctuation risk mitigation will not be considered. All bids including such provision will render the bid non-responsive.

3.4.2 Firm Price

Bidders must indicate for each of the following Items, their Bid price excluding taxes.

Description	Firm Price (CAD\$)
Item 1: One 6.5 to 6.7m aluminum hull, cabin boat built in accordance with Annex "A" and "D".	\$ _____
Item 2: One boat trailer built in accordance with Annex "A" and "D"	\$ _____
Item 3: Delivery of boat and trailer, FOB Destination to Fredericton, New Brunswick, Canada	\$ _____
TOTAL WITHOUT GST/HST (sum of Items 1, 2 & 3)	\$ _____

3.4.3 Cost Breakdown

1. Bidders must include with their financial bid a complete cost breakdown of its bid price for the Work. Each item of work or services in the TSOR is to be priced individually to indicate labour, material, overhead and profit. Each item of cost must be cross referenced to the matching article numbers of the TSOR.
2. The cost breakdown must itemize all costs included in its price for the Work in accordance with the Bidder's cost accounting or cost schedule system. Alternatively, Bidders may complete the attached **Annex "B"** which is the minimum amount of information required.
3. The information submitted as a mandatory item will be held as confidential business information. The details of this information may be used for contractual evaluation purposes and/or contract administration purposes.

3.4.4 Unscheduled Work Rates

Bidders must provide the following requested rates:

1. The Charge-out Rate specified below includes all classes of labor, engineering and foreperson, and all overheads, supervision and profit. The Charge-out Rate will be used for pricing unscheduled work that results in an increase or decrease in the Work Period, except as noted in the clause entitled "Overtime."

Charge-out Rate - \$..... /person/hour.

2. Overtime:

Occasionally, Canada may elect to authorize overtime, for Unscheduled Work only. If this is the case, and the rate is greater than the Charge-out Rate, cost of labor hours will be determined on the following basis;

Time and one-half rate: \$..... /person/hour

Double Time Rate: \$..... /person/hour

3. The cost of material must be the net laid-down cost of the material to which must be added a mark-up of 10% of the net laid-down cost of the material. For the purposes of pricing, Unscheduled Work and material must be deemed to include subcontracts.

The unscheduled work rates will be included in the Basis of Payment, however it will not form part of the bid evaluation.

3.4.5 Life Cycle Costing Projections

The boat must have a service life of at least ten (12) years with an expected usage of between 350 and 500 hours per year. Bidders must provide the life cycle costing projections for the following:

- (a) hull;
- (b) propulsion system;
- (c) steering system; and
- (d) other components and systems.

3.5 Section IV: Certifications

Bidders must submit the certifications required under Part 5.

PART 4 - EVALUATION PROCEDURES AND BASIS OF SELECTION

4.1 Evaluation Procedures

(a) Bids will be assessed in accordance with the entire requirement of the bid solicitation including the technical, management & financial evaluation criteria.

(b) An evaluation team composed of representatives of Canada will evaluate the bids.

4.1.1 Technical Evaluation

4.1.1.1 Mandatory Technical Criteria

In order to be compliant, Bidder's proposal must, to the satisfaction of Canada, meet all requirements of the TSOR and provide all information as requested in **PART 3 - BID PREPARATION INSTRUCTIONS, 3.2 Section I - Technical Bid.**

4.1.2 Management Evaluation

4.1.2.1 Mandatory Management Criteria

In order to be compliant, Bidder's proposal must, to the satisfaction of Canada, meet all requirements and provide all information as requested in **PART 3 - BID PREPARATION INSTRUCTIONS, 3.3 Section II – Management Bid.**

4.1.3 Financial Evaluation

SACC Manual Clause [A0220T](#) (2014-06-26), Evaluation of Price - Bid

4.1.3.1 Mandatory Financial Criteria

In order to be compliant, Bidder's proposal must, to the satisfaction of Canada, meet all requirements and provide all information as requested in **PART 3 - BID PREPARATION INSTRUCTIONS, 3.4 Section III – Financial Bid.**

4.2 Basis of Selection

A bid must comply with the requirements of the bid solicitation and meet all mandatory technical evaluation criteria to be declared responsive. The responsive bid with the lowest evaluated price will be recommended for award of a contract.

A mandatory requirement is described using the words "shall", "must", "will" "is required" or "is mandatory".

PART 5 – CERTIFICATIONS

Bidders must provide the required certifications and additional information to be awarded a contract.

The certifications provided by Bidders to Canada are subject to verification by Canada at all times. Unless specified otherwise, Canada will declare a bid non-responsive, or will declare a contractor in default if any certification made by the Bidder is found to be untrue, whether made knowingly or unknowingly, during the bid evaluation period or during the contract period.

The Contracting Authority will have the right to ask for additional information to verify the Bidder's certifications. Failure to comply and to cooperate with any request or requirement imposed by the Contracting Authority will render the bid non-responsive or constitute a default under the Contract.

5.1 Certifications Required with the Bid

Bidders must submit the following duly completed certifications as part of their bid.

5.1.1 Integrity Provisions - Declaration of Convicted Offences

In accordance with the [Integrity and Suspension Policy](http://www.tpsgc-pwgsc.gc.ca/ci-if/politique-policy-eng.html) (<http://www.tpsgc-pwgsc.gc.ca/ci-if/politique-policy-eng.html>), the Bidder must provide with its bid the required documentation, as applicable, to be given further consideration in the procurement process.

5.2 Certifications Precedent to Contract Award and Additional Information

The certifications listed below should be completed and submitted with the bid but may be submitted afterwards. If any of these required certifications is not completed and submitted as requested, the Contracting Authority will inform the Bidder of a time frame within which to provide the information. Failure to comply with the request of the Contracting Authority and to provide the certifications within the time frame specified will render the bid non-responsive.

5.2.1 Integrity Provisions – Required Documentation

In accordance with the [Ineligibility and Suspension Policy](http://www.tpsgc-pwgsc.gc.ca/ci-if/politique-policy-eng.html) (<http://www.tpsgc-pwgsc.gc.ca/ci-if/politique-policy-eng.html>), the Bidder must provide the required documentation, as applicable, to be given further consideration in the procurement process.

5.2.2 Federal Contractors Program for Employment Equity - Bid Certification

By submitting a bid, the Bidder certifies that the Bidder, and any of the Bidder's members if the Bidder is a Joint Venture, is not named on the Federal Contractors Program (FCP) for employment equity "[FCP Limited Eligibility to Bid](http://www.labour.gc.ca/eng/standards_equity/eq/emp/fcp/list/inelig.shtml)" list (http://www.labour.gc.ca/eng/standards_equity/eq/emp/fcp/list/inelig.shtml) available from [Employment and Social Development Canada \(ESDC\) - Labour's](http://www.esdc.gc.ca/eng/employment/employment-equity/employment-equity-eng.html) website.

Canada will have the right to declare a bid non-responsive if the Bidder, or any member of the Bidder if the Bidder is a Joint Venture, appears on the "[FCP Limited Eligibility to Bid](http://www.labour.gc.ca/eng/standards_equity/eq/emp/fcp/list/inelig.shtml)" list at the time of contract award.

5.2.3 Workers Compensation Certification – Letter of Good Standing

The Bidder must have an account in good standing with the applicable provincial or territorial Workers' Compensation Board.

The Bidder must provide, **within five calendar days** following a request from the Contracting Authority, a certificate or letter from the applicable Workers' Compensation Board confirming the Bidder's good standing account. Failure to comply with the request may result in the bid being declared non-responsive.

5.2.4 Welding Certification

1. Welding must be performed by a welder certified by the Canadian Welding Bureau and in accordance with the requirements of the following standards:
 - (a) CT-043-EQ-EG-001-E, Canadian Coast Guard Welding Specification, March 2014;
 - (b) CSA W47.2-11, Certification of Companies for Fusion Welding of Aluminum, division 2.
2. Before contract award and **within five calendar days** of the written request by the Contracting Authority, the successful Bidder must submit evidence demonstrating its certification to the welding standards.

PART 6 - SECURITY, FINANCIAL AND OTHER REQUIREMENTS

6.1 Security Requirement

There is no security requirement applicable to this Contract.

6.2 Financial Capability

SACC Manual clause A9033T, 2012-07-16, Financial Capability

6.3 Insurance Requirements

The Bidder must provide a letter from an insurance broker or an insurance company licensed to operate in Canada stating that the Bidder, if awarded a contract as a result of the bid solicitation, can be insured in accordance with the Insurance Requirements specified in *Part 7 - Resulting Contract Clause 7.17*.

If the information is not provided in the bid, the Contracting Authority will so inform the Bidder and provide the Bidder with a time frame within which to meet the requirement. Failure to comply with the request of the Contracting Authority and meet the requirement within that time period will render the bid nonresponsive.

PART 7 - RESULTING CONTRACT CLAUSES

The following clauses and conditions apply to and form part of any contract resulting from the bid solicitation.

7.1 Requirement

The Contractor must deliver to the Department of Fisheries and Oceans, one 6.5m to 6.7m aluminum cabin boat with trailer, in accordance with Annex "A" Technical Statement of Requirement (TSOR) and Annex "D" Bidders Questions and Canada Responses.

7.2 Standard Clauses and Conditions

All clauses and conditions identified in the Contract by number, date and title are set out in the [Standard Acquisition Clauses and Conditions Manual](https://buyandsell.gc.ca/policy-and-guidelines/standard-acquisition-clauses-and-conditions-manual) (<https://buyandsell.gc.ca/policy-and-guidelines/standard-acquisition-clauses-and-conditions-manual>) issued by Public Works and Government Services Canada.

7.2.1 General Conditions

2030 2016-04-04, Goods - Higher Complexity - Goods, apply to and form part of the Contract.

7.2.2 Supplemental General Conditions

1028 2010-08-16, Ship Construction – Firm Price, apply to and form part of the Contract.

Warranty

The Supplemental General Conditions 1028, article 12 – Warranty, paragraph 3 is deleted and replaced with the following:

The warranty period for the propelling machinery and auxiliaries, fittings and equipment of all kinds (excluding GSM) is twelve (12) months and the warranty period for the hull is 24 months from the date of delivery and acceptance by Canada.

7.3 Security Requirements

7.3.1 There is no security requirement applicable to the Contract.

7.4 Term of Contract

7.4.1 Period of the Contract

The period of the Contract is from date of Contract to March 15, 2018 inclusive.

7.4.2 Delivery Date

All the deliverables must be received on or before December 15, 2017.

7.4.3 Delivery Point

Delivery of the requirement will be made to Fisheries and Oceans Canada, 40 Avonlea Court
Fredericton, New Brunswick, E3B 4Y9.

7.5 Authorities

7.5.1 Contracting Authority

The Contracting Authority for the Contract is:

Luc Girard
Supply Specialist
Public Works and Government Services Canada
Acquisitions Branch
Marine Systems Directorate
Portage III - Floor: 6C2
11, rue Laurier, Gatineau (Québec), K1A 0S5 Canada
Luc.Girard@tpsgc-pwgsc.gc.ca
Téléphone : 819-420-5807
Télécopieur/Facsimile : 819-956-6648

The Contracting Authority is responsible for the management of the Contract and any changes to the Contract must be authorized in writing by the Contracting Authority. The Contractor must not perform work in excess of or outside the scope of the Contract based on verbal or written requests or instructions from anybody other than the Contracting Authority.

7.5.2 Technical Authority *to be provided at contract award*

The Technical Authority for the Contract is:

The Technical Authority named above is the representative of the department or agency for whom the Work is being carried out under the Contract and is responsible for all matters concerning the technical content of the Work under the Contract. Technical matters may be discussed with the Technical Authority, however the Technical Authority has no authority to authorize changes to the scope of the Work. Changes to the scope of the Work can only be made through a contract amendment issued by the Contracting Authority.

7.5.3 Inspection Authority *to be provided at contract award*

The Inspection Authority for the Contract is:

The Inspection Authority is the representative of the department or agency for whom the Work is being carried out under the Contract and is responsible for inspection of the Work and acceptance of the finished work. The Inspection Authority may be represented on-site by a designated inspector and any other Government of Canada Inspector who may from time to time be assigned in support of the designated Inspector.

7.5.4 Contractor's Representative

[Fill in](#)

7.6 Payment

7.6.1 Basis of Payment

In consideration of the Contractor satisfactorily completing all of its obligations under the Contract, the Contractor will be paid a firm price of \$ _____ (*insert the amount at contract award*). Customs duties are included and Applicable Goods and Services or Harmonized Sales Taxes are extra, if applicable.

7.6.1.1 Charge-out Rate / Material Mark-up for Unscheduled Work

The following rates are included in the Basis of Payment and must remain valid for the duration of the contract:

1. The Charge-out Rate specified below includes all classes of labor, engineering and foreperson, and all overheads, supervision and profit. The Charge-out Rate will be used for pricing unscheduled work that results in an increase or decrease in the Work Period, except as noted in the clause entitled "Overtime."

Charge-out Rate - \$..... /person/hour.

2. Overtime:

Occasionally, Canada may elect to authorize overtime, for Unscheduled Work only. If this is the case, and the rate is greater than the Charge-out Rate, cost of labor hours will be determined on the following basis;

Time and one-half rate: \$..... /person/hour

Double Time Rate: \$..... /person/hour

3. The cost of material must be the net laid-down cost of the material to which must be added a mark-up of 10% of the net laid-down cost of the material. For the purposes of pricing, Unscheduled Work and material must be deemed to include subcontracts.

7.6.2 Payment for Fuels, Oils and Lubricants

The Contractor is responsible for the supply and cost of all fuel, lubricating oil, hydraulic oil and other lubricants sufficient for fully charging all systems as required for operating the machinery and other equipment and for performing all tests and trials.

7.6.3 Field Engineering and Supervisory Services

If Field Service Representatives (FSR) and/or Supervisory Services are required for the Work, the cost of all such services is to be included in the price for the Work.

7.6.4 Limitation of Price

Canada will not pay the Contractor for any design changes, modifications or interpretations of the Work unless they have been approved, in writing, by the Contracting Authority before their incorporation into the Work.

7.6.5 Milestone Payments

Canada will make milestone payments in accordance with the Schedule of Milestones detailed in the Contract and the payment provisions of the Contract if:

- (a) an accurate and complete claim for payment using PWGSC-TPSGC 1111, Claim for Progress Payment, and any other document required by the Contract have been submitted in accordance with the invoicing instructions provided in the Contract;
- (b) all the certificates appearing on form PWGSC-TPSGC 1111 have been signed by the respective authorized representatives;
- (c) all work associated with the milestone and as applicable any deliverable required has been completed and accepted by Canada.

7.6.6 Schedule of Milestones

The schedule of milestones for which payments will be made in accordance with the Contract is as follows:

Milestone No.	National Asset Code (NAC)	Description of deliverable(s)	% of contract value	Firm Amount CDN \$
A	VXC02	Hull materials delivered to Contractor and sustained construction commenced	30	
B		Boat, Trailer and technical manuals delivered and accepted by Canada	67	
C		End of 12 month warranty period – Final acceptance	3	
		Total	100	

The milestones shown above must be included and identified in all production schedules.

The payment for the delivery, **Milestone “B”** will be payable by Canada upon delivery of the boat, trailer and manuals and Acceptance by Canada, minus the holdback for double the total estimated value of any outstanding work items.

The holdback for outstanding work will be payable by Canada upon completion of the outstanding work and when the work is accepted by Canada.

The payment for completion of the twelve month warranty period, **Milestone “C”**, will be payable by Canada upon completion of the warranty period of the workboat, minus the total cost of any work undertaken by Canada to repair any defects subject to warranty.

7.7 Invoicing Instructions

1. The Contractor must submit a claim for payment using form PWGSC-TPSGC 1111, Claim for Progress Payment.

Each claim must show:

- (a) all information required on form PWGSC-TPSGC 1111;
- (b) all applicable information detailed under the section entitled "Invoice Submission" of the general conditions;
- (c) the description and value of the milestone claimed as detailed in the Contract;
- (d) Quality assurance documentation when applicable and/or as requested by the Contracting Authority.

2. The Goods and Services Tax or Harmonized Sales Tax (GST/HST), as applicable, must be calculated on the total amount of the claim before the holdback is applied. At the time the holdback is claimed, there will be no GST/HST payable as it was claimed and payable under the previous claims for progress payments.

3. The Contractor must prepare and certify one original and one (1) copy of the claim on form PWGSC-TPSGC 1111, and forward it to the Contracting Authority identified under the section entitled "Authorities" of the Contract for appropriate certification after inspection and acceptance of the Work takes place.

4. The Contracting Authority will then forward the original of the claim to the Technical Authority for certification and onward submission to the Payment Office for the remaining certification and payment action.

5. The Contractor must not submit claims until all work identified in the claim is completed.

7.8 Certifications

7.8.1 Compliance

The continuous compliance with the certifications provided by the Contractor in its bid and the ongoing cooperation in providing associated information are conditions of the Contract. Certifications are subject to verification by Canada during the entire period of the Contract. If the Contractor does not comply with any certification, fails to provide the associated information, or if it is determined that any certification made by the Contractor in its bid is untrue, whether made knowingly or unknowingly, Canada has the right, pursuant to the default provision of the Contract, to terminate the Contract for default.

7.8.2 Welding

1. The Contractor must ensure that welding is performed by a welder certified by the Canadian Welding Bureau (CWB) in accordance with the requirements of the following standards:

- (a) CT-043-EQ-EG-001-E, Canadian Coast Guard Welding Specification, March 2014;
- (b) CSA W47.2-M1987, Certification of Companies for Fusion Welding of Aluminum.

2. In addition, welding must be done in accordance with the requirements of the applicable drawings and specifications.

3. Before the commencement of any fabrication work, and upon request from the Inspection Authority, the Contractor must provide approved welding procedures and/or a list of welding personnel he intends to use in the performance of the Work. The list must identify the CWB welding procedure qualifications attained by each of the personnel listed and must be accompanied by a copy of each person's current CWB welding certification.

7.8.3 Workers Compensation

The Contractor must maintain its account in good standing with the applicable provincial or territorial Workers' Compensation Board for the duration of the Contract.

7.9 Project Schedule

1. The Contractor must provide an updated detailed project schedule in MS Project format or equivalent to the Contracting Authority and the Technical Authority **five days after award of Contract**.
2. This schedule must highlight the specific dates for the events listed below.
 - (a) hull materials delivered to Contractor and sustained construction commenced;
 - (b) hull and deck completed, but not closed in to allow for full inspection of the structure and welding. The Contractor must supply a hard copy of the material certs and construction drawings to the Technical/Inspection Authority one (1) week prior to inspection by the Technical/Inspection Authority;
 - (c) outfitting/electrical 75% complete but all equipment and components delivered to the Contractor and available for full inspection. The Contractor must supply a hard copy of the list of equipment and electrical supplies to the Technical/Inspection Authority one (1) week prior to inspection by the Technical/Inspection Authority;
 - (d) technical manuals delivered to Canada for approval (no less than 14 days prior to the planned delivery date);
 - (e) Contractor's tests and trial and final sea trials required by the TSOR;
 - (f) boat and trailer delivered to Canada for approval;
 - (g) the start and the end of the twelve (12) month warranty period.

Note: Technical Manuals will not be returned once approved.

3. The schedule is to be regularly updated and available in the Contractor's office for review by Canada's authorities to determine the progress of the Work.

7.10 Progress Report

1. The Contractor must submit monthly reports on the progress of the Work in an electronic format to the Technical Authority and to the Contracting Authority.
2. The progress report must contain two (2) Parts:

PART 1: The Contractor must answer the following three questions:

- (i) is the project on schedule?
- (ii) is the project within budget?
- (iii) is the project free of any areas of concern in which the assistance or guidance of Canada may be required?

Each negative response must be supported by an explanation.

PART 2: A narrative report, brief, yet sufficiently detailed to enable the Technical Authority to evaluate the progress of the Work, containing as a minimum:

- (i) a description of the progress of each task and of the Work as a whole during the period of the report.

Sufficient sketches, diagrams, photographs, etc., must be included, if necessary, to describe the progress accomplished.

- (ii) an explanation of any variation from the schedule.

7.11 SACC Manual Clauses

B5007C - Procedures for Design Change or Additional Work, 2010-01-11

B9035C - Progress Meetings, 2008-05-12

C0711C - Time Verification, 2008-05-12

C2604C - Customs Duties, Excise Taxes and Applicable Taxes – Non-resident, 2013-04-25

D3015C - Dangerous Goods/Hazardous Products – Labelling and Packaging Compliance, 2014-09-25

H4500C - Lien - Section 427 of the Bank Act, 2010-01-11

7.12 Trade Qualifications

The Contractor must use qualified, certified (where applicable) and competent tradespeople and supervision to ensure a uniform high level of workmanship. The Contracting Authority may request to view and record details of the certification and/or qualifications held by the Contractor's tradespeople. This request should not be unduly exercised but only to ensure qualified tradespeople are on the job.

7.13 Quality Management Systems

1. The Contractor must have in place a Quality Assurance Program approved by the Inspection Authority during the performance of the Work which addresses the quality control elements below.

2. The quality control elements should include, as a minimum:

Management Representative
Quality Assurance Manual
Quality Assurance Program Descriptions
Quality Reporting Organization
Documentation
Measuring and Testing Equipment
Procurement
Inspection and Test Plan
Incoming Inspection
In-Process Inspection
Final Inspection
Special Processes
Quality Records
Non Conformance
Corrective Action

3. The Contractor's facilities may be audited by Canada, or its authorized representative, during the performance of the Work to ensure that the approved system is in place and in accordance with the foregoing requirement.

4. The Contractor will be required to submit completed quality assurance documentation with each claim for payment as applicable.

7.14 Post Contract Award/Pre-Production Meeting

Within **three working days** of the receipt of the Contract, the Contractor must contact the Contracting Authority to determine the details of a pre-production meeting. The meeting will be held at the Contractor's plant. Cost of holding such pre-production meeting must be included in the price of the bid. Please note that the travel and living expenses for Government Personnel will be arranged and paid for by Canada.

7.15 Manuals

1. The Contractor must obtain and deliver to the Technical Authority for approval, no later than fourteen calendar days prior to delivery of the boat, all Data Books, Operating Instruction Books, Maintenance Manuals and Spare Parts Lists (including part numbers and ordering instructions) for all machinery and equipment fitted on the vessel as required. Once approved by the TA, the Contractor will provide two complete copies in accordance with and as specified in the TSOR.

2. Where manuals are examined by Canada, such examination does not relieve the Contractor of any responsibility under the Contract for ensuring the correctness of all details and adequacy of performance of the vessel, nor does it obligate Canada to accept, in part or in whole, an item of Work completed in accordance with such manual, nor does it mean such an item of Work meets the requirements of the TSOR.

7.16 Inspection, Test & Trials

1. During construction of the vessel, the Contractor must arrange for regular inspections and upon completion of the construction of the vessel, the Contractor must arrange trials. All Inspections and test and trials performed must be in accordance with the Annex "A" TSOR and Annex "E" - Inspection/Quality Assurance/Quality Control. The Inspection Authority must approve any additional testing not specified in the TSOR.

2. The Contractor must update as required the Inspection and Test Plan (ITP) provided with its bid and submit to the Contracting Authority and the Inspection Authority **seven days after contract award** for review and amended by the Contractor to the satisfaction of the Inspection Authority.

3. Once approved, any modification to the ITP must be pre-approved by the Inspection Authority. A revised ITP will be required should any modification be made.

7.17 Insurance Requirements

1. The Contractor must comply with the insurance requirements specified in Articles 7.17.1 and 7.17.2 below. The Contractor must maintain the required insurance coverage for the duration of the Contract. Compliance with the insurance requirements does not release the Contractor from or reduce its liability under the Contract.

2. The Contractor is responsible for deciding if additional insurance coverage is necessary to fulfill its obligation under the Contract and to ensure compliance with any applicable law. Any additional insurance coverage is at the Contractor's expense, and for its own benefit and protection.

3. The Contractor must forward to the Contracting Authority within ten days after the date of award of the Contract, a Certificate of Insurance evidencing the insurance coverage and confirming that the insurance policy complying with the requirements is in force. Coverage must be placed with an Insurer licensed to carry out business in Canada. The Contractor must, if requested by the Contracting Authority, forward to Canada a certified true copy of all applicable insurance policies.

7.17.1 General Commercial Insurance

1. The Contractor must obtain Commercial General Liability Insurance, and maintain it in force throughout the duration of the Contract, in an amount usual for a contract of this nature, but for not less than \$2,000,000 per accident or occurrence and in the annual aggregate.

2. The Commercial General Liability policy must include the following:

- (a) Additional Insured: Canada is added as an additional insured, but only with respect to liability arising out of the Contractor's performance of the Contract. The interest of Canada should read as follows: Canada, as represented by Public Works and Government Services Canada.
- (b) Bodily Injury and Property Damage to third parties arising out of the operations of the Contractor.
- (c) Products and Completed Operations: Coverage for bodily injury or property damage arising out of goods or products manufactured, sold, handled, or distributed by the Contractor and/or arising out of operations that have been completed by the Contractor.
- (d) Personal Injury: While not limited to, the coverage must include Violation of Privacy, Libel and Slander, False Arrest, Detention or Imprisonment and Defamation of Character.
- (e) Cross Liability/Separation of Insureds: Without increasing the limit of liability, the policy must protect all insured parties to the full extent of coverage provided. Further, the policy must apply to each Insured in the same manner and to the same extent as if a separate policy had been issued to each.
- (f) Blanket Contractual Liability: The policy must, on a blanket basis or by specific reference to the Contract, extend to assumed liabilities with respect to contractual provisions.
- (g) Employees and, if applicable, Volunteers must be included as Additional Insured.
- (h) Employers' Liability (or confirmation that all employees are covered by Worker's compensation (WSIB) or similar program).
- (i) Broad Form Property Damage including Completed Operations: Expands the Property Damage coverage to include certain losses that would otherwise be excluded by the standard care, custody or control exclusion found in a standard policy.
- (j) Notice of Cancellation: The Insurer will endeavour to provide the Contracting Authority thirty days written notice of policy cancellation.
- (k) If the policy is written on a claims-made basis, coverage must be in place for a period of at least 12 months after the completion or termination of the Contract.

(l) Owners' or Contractors' Protective Liability: Covers the damages that the Contractor becomes legally obligated to pay arising out of the operations of a subcontractor.

(m) Non-Owned Automobile Liability - Coverage for suits against the Contractor resulting from the use of hired or non-owned vehicles.

(n), (o), (p), (q) not used.

(r) Litigation Rights: Pursuant to subsection 5(d) of the Department of Justice Act, S.C. 1993, c. J-2, s.1, if a suit is instituted for or against Canada which the Insurer would, but for this clause, have the right to pursue or defend on behalf of Canada as an Additional Named Insured under the insurance policy, the Insurer must promptly contact the Attorney General of Canada to agree on the legal strategies by sending a letter, by registered mail or by courier, with an acknowledgement of receipt.

For the province of Quebec, send to:
Director Business Law Directorate,
Quebec Regional Office (Ottawa),
Department of Justice,
284 Wellington Street, Room SAT-6042,
Ottawa, Ontario, K1A 0H8

For other provinces and territories, send to:
Senior General Counsel,
Civil Litigation Section,
Department of Justice
234 Wellington Street, East Tower
Ottawa, Ontario K1A 0H8

A copy of the letter must be sent to the Contracting Authority. Canada reserves the right to co-defend any action brought against Canada. All expenses incurred by Canada to co-defend such actions will be at Canada's expense. If Canada decides to co-defend any action brought against it, and Canada does not agree to a proposed settlement agreed to by the Contractor's insurer and the plaintiff(s) that would result in the settlement or dismissal of the action against Canada, then Canada will be responsible to the Contractor's insurer for any difference between the proposed settlement amount and the amount finally awarded or paid to the plaintiffs (inclusive of costs and interest) on behalf of Canada.

7.17.2 Marine Liability Insurance

1. The Contractor must obtain Protection & Indemnity (P&I) insurance that must include excess collision liability and pollution liability. The insurance must be placed with a member of the International Group of Protection and Indemnity Associations or with a fixed market in an amount of not less than the limits determined by the Marine Liability Act, S.C. 2001, c. 6. Coverage must include crew liability, if it is not covered by Worker's Compensation as detailed in paragraph (2.) below.

2. The Contractor must obtain Worker's Compensation insurance covering all employees engaged in the Work in accordance with the statutory requirements of the Territory or Province or state of nationality, domicile, employment, having jurisdiction over such employees. If the Contractor is assessed any additional levy, extra assessment or super-assessment by a Worker's Compensation Board, as a result of an accident causing injury or death to an employee of the Contractor or subcontractor, or due to unsafe working conditions, then such levy or assessment must be paid by the Contractor at its sole cost.

3. The Protection and Indemnity insurance policy must include the following:

- (a) Additional Insured: Canada is added as an additional insured, but only with respect to liability arising out of the Contractor's performance of the Contract. The interest of Canada as additional insured should read as follows: Canada, represented by Public Works and Government Services Canada.
- (b) Waiver of Subrogation Rights: Contractor's Insurer to waive all rights of subrogation against Canada as represented by Fisheries and Oceans Canada and Public Works and Government Services Canada for any and all loss of or damage to the watercraft however caused.
- (c) Notice of Cancellation: The Insurer will endeavour to provide the Contracting Authority thirty (30) days written notice of cancellation.
- (d) Cross Liability/Separation of Insureds: Without increasing the limit of liability, the policy must protect all insured parties to the full extent of coverage provided. Further, the policy must apply to each Insured in the same manner and to the same extent as if a separate policy had been issued to each.
- (e) Litigation Rights: Pursuant to subsection 5(d) of the Department of Justice Act, S.C. 1993, c. J-2, s.1, if a suit is instituted for or against Canada which the Insurer would, but for this clause, have the right to pursue or defend on behalf of Canada as an Additional Named Insured under the insurance policy, the Insurer must promptly contact the Attorney General of Canada to agree on the legal strategies by sending a letter, by registered mail or by courier, with an acknowledgement of receipt.

For the province of Quebec, send to:
Director Business Law Directorate,
Quebec Regional Office (Ottawa),
Department of Justice,
284 Wellington Street, Room SAT-6042,
Ottawa, Ontario, K1A 0H8

For other provinces and territories, send to:
Senior General Counsel,
Civil Litigation Section,
Department of Justice
234 Wellington Street, East Tower
Ottawa, Ontario K1A 0H8

4. A copy of the letter must be sent to the Contracting Authority. Canada reserves the right to co-defend any action brought against Canada. All expenses incurred by Canada to co-defend such actions will be at Canada's expense. If Canada decides to co-defend any action brought against it, and Canada does not agree to a proposed settlement agreed to by the Contractor's insurer and the plaintiff(s) that would result in the settlement or dismissal of the action against Canada, then Canada will be responsible to the Contractor's insurer for any difference between the proposed settlement amount and the amount finally awarded or paid to the plaintiffs (inclusive of costs and interest) on behalf of Canada.

7.18 Applicable Laws

The Contract must be interpreted and governed, and the relations between the parties determined, by the laws in force in the Province of Ontario.

7.19 Priority of Documents

If there is a discrepancy between the wordings of any documents that appear on the list, the wording of the document that first appears on the list has priority over the wording of any document that subsequently appears on the list.

- a) The Articles of Agreement;
- b) The Supplemental General Conditions 1028, 2010-08-16, Ship Construction Firm Price;
- c) The General Conditions 2030, 2016-04-04, Goods (Higher Complexity);
- d) Annex "A", Technical Statement of Requirement;
- e) Annex "B", Cost Breakdown;
- f) Annex "C", Subcontractors;
- g) Annex "D", Bidder Questions and Canada Responses;
- h) Annex "E", Inspection/Quality Assurance/Quality Control;
- i) The Contractor's bid dated _____.

7.20 Acceptance

1. Canada's provisional acceptance for delivery of the vessel must occur with the execution of a certificate in accordance with **form PWGSC 1105** upon satisfactory completion of the vessel and all trials. The execution of the certificates must in no way relieve the Contractor of any obligations under the Contract.

2. It is understood and agreed that where the work has been substantially completed and the parties have agreed upon the terms and conditions for the Contractor to make good any deficiencies, the certificate referred to above may be executed with a statement attached concerning the rectification of the deficiencies by the Contractor.

3. Canada's final acceptance must occur upon completion of the twelve (12) month warranty period and settlement of all accounts between the parties in relation to the Contract.

7.21 Government Supplied Material

The following equipment will be Government Supplied Material (GSM) and must be installed, mounted, set-up, fully functional and in accordance with each manufacturer's installation recommendations:

1. Two 115 HP Yamaha gasoline outboard engines;
2. Raymarine C127 Multifunction Navigation Display with 12.1" Sunlight Viewable Color display, model E02022 or equivalent. Plotter mounted on vessel dash, and minimizes interference with operator's vision;
3. RD24-24" High Performance 4KW Raydome Antenna E-52067 with 15m cable;
4. Raymarine Raystar 125 GPS Sensor E32042 Navionics Chart for appropriate areas;
5. Raymarine E66008 in Hull Depth Adjustable Angled in Hull Transducer;
6. Raymarine DSM300 Digital Sounder Module, model E63069;
7. Raymarine Smart Heading System for Pathfinder model E12102 Gyro Stabilized Fluxgate Compass System;
8. ICOM IC M604 VHF DSC radio. Complete with loud hailer/intercom function plumbed to Radio;
9. Antenna, specification is Comrod AV60P 8 and Shakespeare 4187 HD ratchet mount;
10. Whelan Loud Hailer / Siren;
11. Clarion 435 CD AM/FM stereo; and
12. One (1) externally mounted EPIRB RLS 406MZ beacon.

Note: The engines and electronic parts will be shipped to the Contractor's facility within 1- 2 months after award of Contract for installation by the Contractor.

Solicitation No. - N° de l'invitation
F7044-170014/A
Client Ref. No. - N° de réf. du client
F7044-170014

Amd. No. - N° de la modif.
File No. - N° du dossier
032mc.F7044-170014

Buyer ID - Id de l'acheteur
032mc
CCC No./N° CCC - FMS No./N° VME

ANNEX "A"

TECHNICAL STATEMENT OF REQUIREMENT (TSOR)

See attached

ANNEX “C”

SUBCONTRACTORS

Specification Item	Description of Goods/Services (Incl. Make, Model Number as applicable)	Name of Supplier	Address of Supplier

Solicitation No. - N° de l'invitation
F7044-170014/A
Client Ref. No. - N° de réf. du client
F7044-170014

Amd. No. - N° de la modif.
File No. - N° du dossier
032mc.F7044-170014

Buyer ID - Id de l'acheteur
032mc
CCC No./N° CCC - FMS No./N° VME

ANNEX "D"

BIDDERS QUESTIONS AND CANADA RESPONSES

To be completed as required during the bid solicitation and inserted here

ANNEX "E"

INSPECTION / QUALITY ASSURANCE / QUALITY CONTROL

1. Conduct of Inspection

- (a) Inspections will be conducted in accordance with the ITP provided and accepted by the Inspection Authority and as detailed in this Annex.
- (b) The Contractor must provide its own staff or subcontractors to conduct inspections, tests and trials; excepting that Technical Authority or Inspection Authority personnel may be designated in the specifications, in which case the Contractor must ensure that its own staff are provided in support of such inspection/test/trial.
- (c) As applicable, the Contractor must ensure that the required conditions stated in the specification prevail at the commencement of, and for the duration of, each inspection/test/trial.
- (d) The Contractor must ensure that personnel required for equipment operation and records taking during the inspection/test/trial are briefed and available at the start and throughout the duration of the inspection/test/trial. Tradesmen or FSRs who may be required to effect minor changes or adjustments in the installation must be available at short notice.
- (e) The Contractor is to coordinate the activities of all personnel taking part in each inspection/test/trial and ensure that safe conditions prevail throughout the inspection/test/trial.

2. Inspection Records and Reports

- (a) The Contractor on the inspection record, test or trials sheets as applicable must record the results of each inspection. The Contractor must maintain files of completed inspection records.
- (b) The Contractor's Quality Control (QC) representative (and the FSR when required) must sign as having witnessed the inspection, test or trial on the inspection record. The Contractor must forward originals of completed inspection records, together with completed test(s) and/or trials sheets to the Inspection Authority as they are completed.
- (c) Unsatisfactory inspection/test/trial results, for which corrective action cannot be completed during the normal course of the inspection/test/trial, will require the Contractor to establish and record the cause of the unsatisfactory condition to the satisfaction of the Inspection Authority. Canada representatives may assist in identification where appropriate.
- (d) Corrective action to remove cause of unsatisfactory inspections must be submitted to the Contracting Authority and to the Inspection Authority in writing by the Contractor, for approval before affecting such repairs and rescheduling of the unsatisfactory inspection/test/trial. Such notices must be included in the final records passed to the Contracting Authority and to the Inspection Authority.
- (e) The Contractor must undertake rectification of defects and deficiencies in the Contractor's installation or repair as soon as practicable. The Contractor is responsible to schedule such repairs at its own risk.
- (f) The Contractor must reschedule unsatisfactory inspections after any required repairs have been completed.

- (g) Quality Control, Inspection and Test records that substantiate conformance to the specified requirements, including records of corrective actions, must be retained by the Contractor for three (3) years from the date of completion or termination of the Contract and must be made available to the Contracting Authority and to the Inspection Authority upon request.

3. Inspection and Trials Process

3.1 Drawings and Purchase Orders

- (a) Upon receipt of two (2) copies of each drawing or purchase order, the designated Inspection Authority will review its content against the provisions of the TSOR. Where discrepancies are noted, the Inspection Authority will formally advise all concerned, in writing using a Discrepancy Notice. The resolution of any such discrepancy is a matter for consultation between the Contractor and other Government of Canada Authorities.

3.2 Inspection

- (a) Upon receipt and acceptance of the Contractor's ITP, inspection will consist of a number of Inspection Points supplemented by such other inspections, tests, demonstrations and trials as may be deemed necessary by the Inspection Authority to permit him to certify that the work has been performed in compliance with the provisions of the specification. The Contractor must be responsible for notifying the designated Inspection Authority of when the work will be available for inspection, sufficiently in advance to permit the designated Inspection Authority to arrange for the appropriate inspection.
- (b) The Inspection Authority will inspect the materials, equipment and work throughout the project against the provisions of the specification and, where non-conformances are noted, will issue appropriate INSPECTION NON-CONFORMANCE REPORTS.
- (c) The Contract requires the implementation of a Quality Assurance/Quality Control system, so the Inspection authority must require that the Contractor provide a copy of its internal inspection report pertaining to a work item before conducting the requested inspection. If third party inspections are required by the Contract (e.g. inspections by a certified CWB 178.2 welding inspector), the reports of these inspections must be required before the Work is inspected by the Inspection Authority.
- (d) The QA/QC system is a requirement, so if the documentation is presented to the Inspection Authority before an inspection stating that the Work is satisfactory but the Inspection Authority finds that the Work has not been satisfactorily inspected, the Inspection Authority must issue an Inspection Non-conformance Report against the Work and another against the failure of the Contractor's QA/QC system.
- (e) Before carrying out any inspection, the Inspection Authority must review the requirements for the Work and the acceptance and/or rejection standards to be applied. Where more than one standard or requirement is called up and they are potentially conflicting, the Inspection Authority must refer to the order of precedence in the Contract to determine the standard or requirement to be applied.

3.3 Inspection Non-conformance report

- (a) An Inspection Non-conformance report will be issued for each non-conformance noted by the Inspection Authority. Each report will be uniquely numbered for reference purposes, will be signed and dated by the Inspection Authority, and will describe the non-conformance.
- (b) When the non-conformance has been corrected by the Contractor and has been re-inspected and accepted by the Inspection Authority, the Inspection Authority will complete the Report by adding an applicable signed and dated notation.

- (c) At the end of the project, the content of all Inspection Non-conformance Reports which have not been signed-off by the Inspection Authority will be transferred to the Acceptance documents before the Inspection Authority's certification of such documents.

3.4 Tests, Trials, and Demonstrations

(a) To enable the Inspection Authority to certify that the Work has been performed satisfactorily, in accordance with the Contract and specifications, the Contractor must schedule, co-ordinate, perform, and record all specified tests, trials and demonstrations required by the Inspection Authority and the Specifications and any additional tests and trials performed by the Contractor required by the Inspection Authority.

(b) Where the specifications contain a specific performance requirement for any component, equipment, sub-system or system, the Contractor must test such component, equipment, sub-system or system to the satisfaction of the Inspection Authority, to prove that the specified performance has been achieved and that the component, equipment, sub-system or system performs as required by the specifications.

(c) Tests, trials and demonstrations must be conducted in accordance with a logical, systematic schedule which must ensure that all associated components and equipment are proven before sub-systems demonstration or testing, and that sub-systems are proven before system demonstration or testing.

(d) Where the Specifications do not contain specific performance requirements for any component, equipment, sub-system or system, the Contractor must demonstrate such component, equipment, sub-system or system to the satisfaction of the Inspection Authority.

(e) The Contractor must co-ordinate each test, trial and demonstration with all interested parties, including the Inspection, Contracting and Technical Authorities; regulatory authorities; Classification Society; Sub-contractors; etc. The Contractor must provide the Inspection Authority and other Government of Canada Authorities with a minimum of ten (10) working days' notice of each scheduled test, trial, or demonstration.

(f) The Contractor must keep written records of all tests, trials, and demonstrations conducted required by the QA System.

(g) The Contractor must in all respects be responsible for the conduct of all tests and trials in accordance with the requirements of the Contract.

(h) The Contracting Authority and the Inspection/Technical Authority reserve the right to defer starting or continuing with any sea trials for any reasonable cause including but not limited to adverse weather, visibility, equipment failure or degradation, lack of qualified personnel and inadequate compliance with safety standards.



Fisheries and Oceans
Canada

Pêches et Océans
Canada



DEPARTMENT OF FISHERIES AND OCEANS

ANNEX A

**Technical Statement of Requirements
Requisition number F7044-170014 for one (1)
6.5 to 6.7 metre aluminum boat with cabin and trailer**

May 30, 2017, Revision 0

**TRANSPORT CANADA MARINE SAFETY BRANCH (TCMSB)
TP1332 APPROVED CONSTRUCTION**

Canada



Document Control

Record of Amendments

#	Date	Description	Initials
0	May 30, 2017	Original release	KA

TABLE OF CONTENTS

ABBREVIATIONS	3
LIST OF REFERENCE DOCUMENTS	3
OVERVIEW	4
1.1 REQUIREMENT	4
2.0 DESIGN AND CONSTRUCTION REQUIREMENTS	4
2.1 ERGONOMIC DESIGN – GENERAL	4
2.2 VIBRATION	4
2.3 EQUIPMENT PROTECTION	4
2.4 SITE CLEANLINESS	5
2.5 STRUCTURAL STRENGTH	5
2.6 STANDARDS	5
2.7 MATERIALS	5
2.8 FASTENERS	6
3.0 OPERATIONAL REQUIREMENTS	6
3.1 GENERAL	6
3.2 ENVIRONMENTAL CONDITIONS	6
3.3 LAUNCHING, RECOVERY & TRANSPORTATION	6
3.4 BEACHING	7
4.0 PHYSICAL CHARACTERISTICS	7
4.1 VESSEL PARTICULARS	7
4.2 HULL FORM & STRUCTURE	7
5.0 VESSEL CONFIGURATION	8
5.1 GENERAL DECK ARRANGEMENT	8
5.2 CABIN – GENERAL	8
5.3 CABIN – OUTFIT	8
5.4 UTILITY LIGHTING	9
6.0 OUTFIT GENERAL	10
6.1 HULL OUTFIT	10
6.2 DECK OUTFIT	11
6.3 LIFESAVING & EMERGENCY EQUIPMENT	11
7.0 SYSTEMS GENERAL	11
7.2 PROPELLER(S)	12
7.3 CONTROLS	12
7.4 ALARMS	12
7.5 VERIFICATION OF INSTALATION	12
7.6 ENGINE BREAK-IN	12
7.7 PROTECTION OF CONTROLS	13
7.8 FUEL SYSTEM	13
7.9 FUEL TANK	13
7.10 ELECTRICAL SYSTEM	13
7.11 BATTERIES, CABLES AND CHARGING SYSTEMS	14
7.12 CABLING INSTALLATION	15
7.13 NAVIGATION LIGHTING	15
7.14 ELECTRONIC AND NAVIGATION EQUIPMENT	15

7.15 DRAINAGE & BILGE SYSTEMS.....	16
7.16 PAINTING AND CORROSION PROTECTION.....	17
8.0 TESTS & TRIALS.....	17
8.1 TESTS - GENERAL.....	17
8.2 SEA TRIALS - GENERAL.....	18
9.0 DOCUMENTATION.....	19
9.1 GENERAL.....	19
9.2 NATIONAL ASSET CODE.....	19
9.3 BUILDER'S PLATE.....	19
9.4 TECHNICAL PUBLICATIONS.....	19
9.5 GENERAL INFORMATION SECTION.....	20
9.6 ADDITIONAL DELIVERABLE DOCUMENTATION.....	20
10.0 SHIPPING AND DELIVERY.....	20
11.0 WARRANTY AND SERVICE PROVISIONS.....	21
11.1 COMPONENTS AND EQUIPMENT SUPPORT.....	21
11.2 SPARE PARTS.....	21
12.0 TRAILER.....	21
APPENDIX A.....	23

ABBREVIATIONS

ABYC	American Boat and Yacht Council
AC	Alternating Current
ASTM	American Society for Testing and Materials
CFM	Contractor Furnished Material
CSA	<i>Canadian Shipping Act</i>
CSA	Canadian Standards Association
COLREGS	Collision Regulations
DC	Direct Current
GPS	Global Positioning System
GSM	Government Supplied Material
ISO	International Organization for Standardization
PVC	Polyvinylchloride
TA	Technical Authority (As defined by the Contract)
TCMS	Transport Canada Marine Safety
TSOR	Technical Statement of Requirements
UV	Ultraviolet
VHF	Very High Frequency
WMO	World Meteorological Organization

LIST OF REFERENCE DOCUMENTS

REFERENCE	TITLE
ASTM F1166	Standard Practice for Human Engineering Design for Marine Systems, Equipment and Facilities
TP 1332	Construction Standards for Small Boats
TP 13430	Standard For Tonnage Measurement of Ships
TP 14070	Small Commercial Vessel Safety Guide
ISO 12217	Small Boat – Stability and Buoyancy Assessment and Categorization
Canada Shipping Act	Small Vessel Regulations
Canada Shipping Act	Collision Regulations (COLREGS)
ABYC	American Boat and Yacht Council Standards
Canadian Standards Association (CSA) CSA W47.2-M1987	Certification of Companies for Fusion Welding of Aluminium
(CSA) C22.2 No. 183.2-M1983 (R1999)	Standards for DC Electrical Installations on Boats
CT-043-EQ-EG-001-E	Canadian Coast Guard Welding Specification, March 2014

OVERVIEW

1.1 REQUIREMENT

- 1.1.1 The Contractor shall design, fabricate and supply quantity one (1) 6.5 -6.7 meter aluminum hull and cabin boat and trailer based on the current Transport Canada Marine Safety Branch (TCMSB) Marine Safety Publication TP 1332 “Construction Standards for Small Vessels” (hereinafter referred to as TCMSB TP 1332). The boat shall be a twin 115hp Yamaha outboard configuration.
- 1.1.2 The primary role of this boat will be Fisheries Conservation and Protection (C&P) for the Maritimes Region, Fredericton New Brunswick Detachment. Operations will be conducted on Grand Lake, French Lake and the Saint John River system from early spring to late fall. The vessel will be used for patrolling and seizing of illegal gear such as gillnets and fyke nets.
- 1.1.3 The secondary roles will be search and rescue and other fisheries enforcement duties such as boarding and surveillance duties within the reasonable capabilities for this type and size of craft.
- 1.1.4 This boat will be shore-based and launched and recovered by trailer.

2.0 DESIGN AND CONSTRUCTION REQUIREMENTS

Unless stated otherwise all components, equipment and material must be contractor supplied.

2.1 ERGONOMIC DESIGN – GENERAL

Hazardous operating conditions must be prevented by arranging machinery and equipment in a safe manner; providing guards for all electrical, mechanical and thermal hazards to personnel; and providing guards or covers for any controls that might accidentally be activated by contact of personnel. Human engineering factors considered in design must include accessibility, visibility, readability, crew efficiency and comfort for a range of physiques for individuals from approx. 5 ft. to 6' 5" in height, wearing cold weather clothing and equipment which must be accessible for use, inspection, cleaning and maintenance per ASTM F1166-88.

2.2 VIBRATION

The boats and all components must be free of local vibration that could endanger boat personnel, damage boat structure, machinery or systems, or interfere with the operation or maintenance of boat machinery or sonar systems.

- 2.2.1 Mounts for movable components, including items moved for stowage, towing or transport must be provided with resilient material as necessary to prevent rattling.
- 2.2.2 Loosening of fasteners under vibration must be prevented by the use of self-locking fasteners, as applicable.

2.3 EQUIPMENT PROTECTION

The Contractor is responsible for the care of all equipment. All parts, especially those having working surfaces or passages intended for lubricating oil, must be kept clean and protected during manufacture, storage, assembly and after installation. Equipment must at all times be protected against dust, moisture or foreign matter and must not be subject to rapid temperature changes or extremes in temperature.

2.4 SITE CLEANLINESS

During construction, all chips, shavings, refuse, dirt and water must be removed at the completion of the work shift or sooner. The Contractor must ensure measures are taken to avoid wear and damage incident to construction, and to prevent corrosion or other deterioration. Equipment subject to freezing must be kept drained, except during test and trials. Equipment must be kept clean and protected from the environment prior to installation.

2.5 STRUCTURAL STRENGTH

All structures and components (hull, deck, seating, etc.) must be of sufficient strength to withstand the lateral and vertical impact-loading that equates to the conditions of the operational requirements.

2.6 STANDARDS

2.6.1 The boats must be designed, constructed, inspected, and certified to meet the requirements of the following standards, regulations and codes:

2.6.1.1 Transport Canada Marine Safety Regulation TP 1332 (current edition) Construction Standards for Small Boats. This standard references ISO and ABYC standards covering structure, fuel, electrical, stability and drainage requirements;

2.6.1.2 CSA C22.2 No. 183.2-M1983 (R1999) Standards for DC Electrical Installations on Boats and ABYC 'E' Electrical Standards; and

2.6.1.3 CT-043-EQ-EG-001-E - Canadian Coast Guard Welding Specification, March 2014.

2.6.2 The Contractor must supply the boats as per this TSOR and where this TSOR interferes or contravenes the above standard; the above TCMSB TP 1332 standard will take precedence.

2.6.3 The Contractor must supply a certificate of approval insuring the proposed boats complies with TCMSB TP 1332, to ensure compliance with the current Canadian Coast Guard, Maritime Services Policies.

2.7 MATERIALS

2.7.1 All materials must be corrosion resistant and suitable for use in a salt water environment as detailed in the Operational Requirements. All materials normally subjected to sunlight must resist degradation caused by ultraviolet radiation. Galvanized materials are unacceptable.

2.7.2 Direct contact of electrolytically dissimilar metals is not allowed. Electrolytic corrosion must be prevented by insulating dissimilar materials from each other with gaskets, washers, sleeves, or bushings of suitable insulating material.

2.7.3 Stainless steel type 316L or 316 must be used for all stainless steel applications except as noted. Alloy 316L must be used in any welded underwater components.

2.7.4 Fittings and clamps must be stainless steel. Bolts used in all fittings must be Type 316 stainless steel.

2.7.5 Where flexible connections are required for steering and fuel systems, suitable hose with permanently crimped, detachable reusable type fittings must be used.

2.7.6 All materials and equipment must be stored installed and tested in accordance with the manufacturer's guidelines, recommendations and requirements.

2.8 FASTENERS

- 2.8.1 All fasteners must be of corrosion resistant materials.
- 2.8.2 Cadmium plated parts and fasteners, including washers, must not be used.
- 2.8.3 Direct attachment of alloys containing copper to aluminium is not permitted except for an electrical bonding strap.
- 2.8.4 Where nuts will become inaccessible after assembly of the boats, nuts must be captured or anchored to allow reassembly and prevent backing off.
- 2.8.5 Unless otherwise specified, self-locking nuts must be installed to prevent loosening of fasteners due to shock and vibration.
- 2.8.6 Fasteners in deck traffic areas must be flush-mounted to eliminate tripping and snagging hazards.

3.0 OPERATIONAL REQUIREMENTS

3.1 GENERAL

Unless otherwise stated, performance must be for conditions of zero sea state and no wind, fresh water with Normal Load and complement. The boats must be designed and constructed for ease of maintenance and repair, long life, and to be easily supportable by local commercial facilities and suppliers. Unless otherwise stated, performance must be for conditions of zero sea state and no wind, in fresh water with Normal Load Condition. The boat is expected to have a service life of at least 12 years, with an expected usage of between 350 and 500 hours per year and meet the following minimum operational requirements:

- 3.1.1 Must meet ISO design category "C".
- 3.1.2 Maximum speed: 34 knots (at normal load condition);
- 3.1.3 Cruising speed: 26 knots;
- 3.1.4 Endurance: maximum speed for 2 hours. Run at 26 knots for 4 hours;
- 3.1.5 Capable of steering 15° from heading, in Beaufort Force 5, with seas from any direction;
- 3.1.6 Steer and manoeuvre effectively at 3 knots in Beaufort Force 5;
- 3.1.7 Maintain course, made good over ground, when proceeding at 3 knots with relative cross wind of 21 knots;
- 3.1.8 Operate carefully in depths of 1.0 meter with outboards lowered; and
- 3.1.9 Manoeuvring in depths of 0.8 meters with outboards partially raised position.

3.2 ENVIRONMENTAL CONDITIONS

Capable of operating day or night in the following conditions:

- 3.2.1 Average ambient air temperature range: -15°C to + 35°C
- 3.2.2 Average water temperature: 0°C to +20°C.
- 3.2.3 Wave heights of up to 1.5 meters (Beaufort Force 4).
- 3.2.4 Wind speeds of 17 - 21 knots (Beaufort Force 5).
- 3.2.5 Operate in freezing spray or freezing rain with accumulations of up to 6.0 mm while maintaining stability to allow for safe transit in Beaufort Force 4.

3.3 LAUNCHING, RECOVERY & TRANSPORTATION

- 3.3.1 The boat must be readily road transportable on a trailer, must be able to be launched and recovered using the trailer at launch ramps.

3.3.2 The vessel must be equipped with a four-(4) leg, webbing lifting bridle. The location and arrangement of lifting gear must be such that it does not pose a safety hazard to the operator or crew nor interfere with boat operation. All bridle lifting lugs must be reinforced and proof tested in accordance with CSA Tackle Regulations. Lifting points must not be located below the deck or within lockers or compartments. Lifting points must be located so that the bridle does not snag on the boat structure, outfit or machinery. Lifting slings provided must be webbing strap type certified to safely lift the vessel in the Normal Loaded condition. Test margin 150% for four straps, or per CSA if higher standard.

3.4 BEACHING

3.4.1 Capable of beaching on soft (sand, earth or clay) surfaces at a speed of up to 5 knots without damage to the hull.

3.4.2 Capable of beaching on hard (stone or concrete) surfaces at speeds of up to 3 knots without damage to the hull.

4.0 PHYSICAL CHARACTERISTICS

4.1 VESSEL PARTICULARS

4.1.1 Length overall – between 6.5 and 6.7 metres (not including swim grid)

4.1.2 Breadth overall – 2.56 metres

4.1.3 Maximum draft (outboard motor lowered) - between 0.35 and 0.45 meters.

4.1.4 Displacement (in normal load condition) between 2200kg and 2500kg.

4.1.5 Normal load conditions:

4.1.5.1 Crew of 4 = 400kg

4.1.5.2 Fuel = 303 liters = 225kg

4.1.5.3 Equipment and supplies = 300kg

4.1.6 Vessel stern configured to accommodate – twin Yamaha 115 hp outboards – Government Supplied Material (GSM) and installed by the Contractor.

4.2 HULL FORM & STRUCTURE

4.2.1 The hull is to be a 18 degree dead rise at transom, “V” style monohull with a reverse chine flat and hull bottom to incorporate minimum one substantial (~1.5” vertical, aft, located approx. mid bottom panel) or a combination of smaller spray strakes on the bottom, per side, which run out to the stem. Dead rise at 25% aft from stem must be minimum 30 degrees.

4.2.2 Hull shape must not impede water flow to the propulsion units and must direct spray and waves away from onboard personnel.

4.2.3 Hull and side plate – minimum ¼” thick aluminum hull with side plates minimum 3/16”. Deck plate minimum 3/16” thick aluminum.

4.2.4 Cabin sides minimum 1/8” thick aluminum and cabin top minimum 3/16” thick aluminum.

4.2.5 Cabin top must have a minimum camber of 1” Cabin top to extend past the forward raked bulkhead providing a brim for additional sunlight deflection.

4.2.6 The hull and decks are to be transversely framed and longitudinally stringered (minimum of two longitudinal members each side, port and stbd). Internal structure at outer perimeter at top of bulwarks and foc’sle deck must be constructed with an aluminum channel to provide additional structural strength.

- 4.2.7 An aluminum beaching shoe is required minimum 3/16" thick and 5" wide on centerline, from just below the bow eye along the length of the hull extending to the transom of the vessel to protect against damage from grounding or similar hazards. This shoe shall not detract from performance or sea keeping capabilities, and it shall be capable of withstanding the horizontal and vertical impact loading associated with the boats operational requirements. (See section 3.4 Operational Performance - Beaching).

5.0 VESSEL CONFIGURATION

Aluminum hull/cabin workboat with a primary working deck aft and secondary working deck forward of the cabin. Cabin forward of amidships.

5.1 GENERAL DECK ARRANGEMENT

- 5.1.1 Open aft deck, length of working space to be minimum 2.6 meters, self-bailing deck with "non-return" auto scuppers.
- 5.1.2 Full breadth cabin with bulwark walk around access on port and stbd sides. Minimum length 2.1 meters with sliding door access from the aft deck and hinged door access to the fore deck.
- 5.1.3 Open forward working deck to be maximised to meet the design of the vessel, minimum 1.2 meters long.
- 5.1.4 The forward side of the cabin must be aft raked and located just forward amidships with step down access from the aft deck and step up access to the fore deck.
- 5.1.5 Top of bulwarks around the perimeter of the vessel must be flat across their whole width.

5.2 CABIN – GENERAL

- 5.2.1 The cabin inside length must be a minimum of 2.1 meters, to meet the requirements of this TSOR.
- 5.2.2 The cabin must have 180 centimetres of headroom internal clearance (5'-10 3/4") on centreline with walkthrough access from the aft deck to the fore deck.
- 5.2.3 There must be one sliding weathertight access door on the aft end of the cabin with a sliding/locking aluminium framed window and a weathertight hinged door with a window for access to the fore deck.
- 5.2.4 The doors must have positive retention in the open position with locksets. All locks and hardware must be of stainless steel construction. Aft door to slide to port and forward door must be hinged on the port side.
- 5.2.5 The cabin must be fitted with proven manufacturers' aluminum framed windows (with screens for sliders), ISO Category B certified and sized to maximize visibility, as follows:
- 5.2.5.1 Three (3) forward facing fixed windows (one (1) of which has been identified in the forward door);
- 5.2.5.2 Two (2) side sliding window assemblies, one stbd and one port maximized on the length of the cabin for operator visibility; and
- 5.2.5.3 Two (2) fixed windows, aft bulkhead on either side of the sliding door.

5.3 CABIN – OUTFIT

- 5.3.1 This boat must be equipped with two (2) marine seats in the cabin for the operator

- and the navigator, as a minimum these seats must meet the requirements of a Grammer MSG85/722 seat with arm rests, head rests, swivel, slide and height adjust functions. Also, two (2) foldable drop down seats on the aft bulkhead on either side of the sliding door for two (2) additional passengers.
- 5.3.2 An overhead console must be fitted at the operator's position with space adequate for one VHF radio and a lockable storage compartment, which must not protrude into the headroom of the operator.
- 5.3.3 Grab Handles interior - There must be grab handles positioned as follows:
- 5.3.3.1 Two (2) overhead in way of the seats in the cabin. Locate over foot space ahead of seats; and
- 5.3.3.2 Two (2) at the aft door exterior one vertical on port side of door opening and one at the door opening under the cabin top.
- 5.3.4 Grab handles are required around the exterior perimeter of the cabin top, one (1) vertical grab handle just outside the sliding door on the stbd side.
- 5.3.5 Flooring: All interior floor covering must be non-slip approx 3/8" shock and sound absorbing rubber with embossed tread pattern.
- 5.3.6 Interior Finish: The interior of the boats must be in a speckled grey colour, Zolotone "Granite" or equal. All rough edges and sharp angled corners must be rounded and ergonomically adapted. The space must have screwed on interior lining plates with thermal insulation between frames. Frame faces must have thermal barrier strip isolating interior panels.
- 5.3.7 Foot Rests - There must be two (2) footrests, one (1) for the operator and the second for the navigator, foldable footrests.
- 5.3.8 Helm Station:
- 5.3.8.1 The Helm station will be on the stbd side of the console, with controls on stbd;
- 5.3.8.2 The helm will incorporate a steering system, capable of handling the horsepower of the vessel, with manufacturers' engine controls designed for the power unit;
- 5.3.8.3 There will be provision for an array of control gauges and electronic equipment at the helm position, see section 7.4;
- 5.3.8.4 There will be a console mounted magnetic compass, see 7.13.11; and
- 5.3.8.5 All lights switches and breakers must be within easy reach of the operator.
- 5.3.9 The contractor must supply and install a diesel furnace heating system. This heating system shall be a Webasto Air Top 2000 forced air diesel furnace, Model no Artikel Nr. 1312517C (or equivalent), configured to perform cabin heating and window defogging with optional inline speed controlled fan for forced air supply. The Contractor shall calculate the required size of the total space being serviced by the heater and use this measurement when ordering the system. The Contractor shall install the system as per the manufacturer's recommendations.

5.4 UTILITY LIGHTING

ALL LIGHTING IS TO BE LED POWER MANAGEMENT IS CRITICAL DUE TO VOLUME OF ELECTRONICS

- 5.4.1 Lighting interior, all lights must have individual switches.

- 5.4.2 The interior cabin must be equipped with two rows of two overhead LED red/white lights, on port and stbd sides.
- 5.4.3 Exterior lighting; there must be two (2) flood lights fitted on the cabin top, facing the stern, Hella model 1GB-998-541-001 or equal. In addition one (1) remote control spotlight to be mounted on cabin top facing the bow, Guest Model SPL 12W or equal.
- 5.4.4 Three (3) 12 VDC power points required, one (1) at the console for the operator, one(1) for the navigator one (1) on the aft bulkhead, stbd side.
- 5.4.5 Dual isolation transformers and galvanic isolators must be integrated into the vessels electrical system.
- 5.4.6 There must be one (1) 110 VAC power receptacles in the main cabin on the aft bulkhead, port side.
- 5.4.7 There must be one (1) shore power 110v receptacles, 30-amp connections, on aft exterior bulkhead of cabin to service the vessel.
- 5.4.8 A front windshield defroster(s) must have a variable three-speed fan and be ducted and integrated with the heater to multiple outlets to be capable of clearing the entire front windshield area of the vessel and blowing either cold or heated air.
- 5.4.9 Two wipers with pantograph arms must be installed on the port and starboard forward windows. A variable speed switch located on the operator's console must activate wipers individually.
- 5.4.10 Two recessed bow lights that are spot /flood combination made by Rigid or equivalent, to be place on either side of the bow. Lights must not protrude from the hull and be waterproof.

6.0 OUTFIT GENERAL

6.1 HULL OUTFIT

- 6.1.1 Bow Eye: A recessed system is to be designed and incorporated into the construction of the stem that allows for the bowline and or trailering hook to be attached to the bow. Port and Starboard stainless steel trailering tie down points to be incorporated in transom.
- 6.1.2 The boats must be equipped with spring-line cleats, three (3) on the port side and three (3) on the stbd side.
- 6.1.3 Forward of the cabin, the boats must be equipped with removable aluminium or stainless steel side grab rails, split bow rail providing a minimum of 36" height from top of the foc'sle deck, both port and starboard sides.
- 6.1.4 Aft of the cabin, the boats must be equipped with removable aluminium or stainless steel grab rails providing a minimum of 36" height from the inner deck to the top of the rail and that extend around the perimeter of the transom, continuing along the side of the boat and allowing for a 610mm gap with no rail just aft of the cabin both port and stbd sides.
- 6.1.5 Boats must be fitted with aluminium protective pipe bracket guard for the outboards.
- 6.1.6 A welded swim platform must be installed on both port and stbd sides of the outboards, minimum length one (1) meter to allow easy access to the outboards

in the raised or lowered positions.

6.2 DECK OUTFIT

- 6.2.1 There must be a minimum of four (4) recessed deck tie downs on the aft deck;
- 6.2.2 One (1) anchor bit and anchor storage mount with quick release on the fore deck;
- 6.2.3 One (1) 15" X 24" BOMAR model C41524-H (hinged) hatch must be installed on the aft deck for stowage of operational kit;
- 6.2.4 One (1) 15" X 24" BOMAR model C41524 (Non-hinged) shall be installed in the deck of the cabin;
- 6.2.5 There must be Chain plates with lifting eyes of sufficient rating to lift the vessel in normal load condition, loaded in the Contractor supplied four (4) legged sling; and
- 6.2.6 A cruciform tow post must be fitted at the transom for emergency towing. Sized and certified with safe working load equivalent to 1.5 times the maximum hp of the vessel. The safe working load is to be permanently stamped and clearly identified on the top of the tow post.

6.3 LIFESAVING & EMERGENCY EQUIPMENT

The following items must be supplied and provided with stowage / securing arrangements (as appropriate for each item). All fittings, Contractor supplied, must be heavy duty, corrosion resistant stainless steel fittings. All items must be readily accessible:

- 6.3.1 One (1) Fire extinguisher (Class B1, marine type);
- 6.3.2 Two (2) paddles;
- 6.3.3 One (1) manual bilge pump (built in), for the hull, Whale Gusher type;
- 6.3.4 One (1) life buoy with heaving line not less than 15 meters;
- 6.3.5 One (1) watertight flashlight;
- 6.3.6 Pyrotechnics Type A Qty: 3, Type B or C Qty: 3;
- 6.3.7 First Aid Kit;
- 6.3.8 One (1) Air horn;
- 6.3.9 Boat hook, 8 feet long (retractable);
- 6.3.10 One (1) Transport Canada approved radar reflector;
- 6.3.11 Anchor (Fortress FX16 model or equivalent) with 200 feet of $\frac{3}{4}$ line and a 5 meter galvanized chain;
- 6.3.12 Drogue sea anchor and 100 feet of $\frac{1}{2}$ " braided nylon line; and
- 6.3.13 Mooring lines, four (4) X 20' X $\frac{5}{8}$ " braided nylon line with eye spliced into one end.

7.0 SYSTEMS GENERAL

7.1 PROPULSION

- 7.1.1 Outboard motors will be Government Supplied Materiel (GSM) twin (2) 115 HP Yamaha gasoline outboard engines. The Contractor must install the outboards, supply and install the controls for the outboards.
- 7.1.2 The engines must be installed, mounted and operated in accordance with the engine manufacturer's recommendations by the Contractor. The Contractor must supply and install the engine manufacturer's approved accessories and equipment. Equipment and components must not be used, or trials performed

on the engines that would, in any way, void the engine manufacturer's warranties.

7.2 PROPELLER(S)

7.2.1 Four (4) identical propellers (two (2) spares) must be provided by the contractor (CFM) for the vessel built.

7.2.2 Propeller(s) must be properly sized and contractor installed.

7.2.3 The Contractor must inform the Technical Authority of appropriate pitch and diameter to meet the Performance Requirements as determined by the contractor developed design check.

7.2.4 The propellers must be of stainless steel.

7.3 CONTROLS

7.3.1 Propulsion control system installation must include a dual binnacle engine controls located on the starboard side of the helm console. The controls must conform to engine manufacturer's recommendations and must not interfere with any of the other controls.

7.3.2 Engine package must incorporate a lanyard style automatic shutdown feature (kill switch) for the engines, to be mounted near the ignition switch

7.4 ALARMS

Monitoring system for the engines must include the following alarms:

7.4.1 Oil level gauge, for the remote tank;

7.4.2 Coolant flow alarm, if applicable;

7.4.3 Engine overheat/high temperature alarm.

7.5 VERIFICATION OF INSTALATION

Installation of the motors, controls, lubrication and fuel systems, manometers, battery connections, are to be verified by an authorized technician. The motors are to be started by the authorized technician, who must provide a written report with a copy for the Technical Authority.

7.6 ENGINE BREAK-IN

The Contractor is to respect the engine manufacturer's break-in procedures and must have the appropriate authorized technician present during the break in period to resolve any issues.

7.7 STEERING

7.7.1 Steering system must be remote hydraulic with self-contained oil reservoir, and replaceable seals on the rams, unless propulsion system builder requires alternate steering arrangement.

7.7.2 Hydraulic hoses must be of sufficient size and length to prevent pulsing. Hoses must be suitable for use in an exposed marine environment complete with stainless steel fittings.

7.7.3 Steering systems must be hydraulic with a maximum of 3.5 turns from hard over to hard over. (The SeaStar® and / or DayStar steering systems, depending on vessel horsepower, from Teleflex meet this requirement).

7.7.4 All hydraulic steering hoses must be routed below deck and all hoses must be routed so that there are no pinch points on the hoses.

7.7.5 The wheel / console connection must be of robust construction, to eliminate fore and aft or lateral movement of wheel / steering shaft fixture.

7.7.6 The steering wheel must be stiff enough that during rough water operations there is no flexing of the wheel and the wheel should be padded to provide a comfortable non-slip surface for the operator to grip. (Momo Marine steering wheels meet these requirements).

7.8 PROTECTION OF CONTROLS

All control cables, electrical wiring for the motors and the steering hydraulic hoses are to be installed in UV resistant plastic pipes (LOOM) or equal. These pipes are to be installed in such a manner as to ensure that no cable is immersed in water.

7.9 FUEL SYSTEM

The complete fuel systems must be supplied, installed, labeled and tested in accordance with Section 7 of TCMSB TP 1332 and ABYC specifications.

7.9.1 The fuel system must include two (2) Racor filter/separators with see-thru bowls, suitable for fuel supply to the twin gasoline outboard motors.

7.9.2 All fuel valves must be readily accessible and labeled as per TCMSB TP 1332.

7.9.3 Locking Fuel filler must be located in an accessible watertight / vented compartment designed to catch fuel from over filling or blow back, so that the fuel does not enter the vessel as per TCMSB TP 1332 requirements.

7.9.4 Remote fuel shutoff maintenance valves are to be installed at filter/ manifold system and be easily accessible by vessel operators.

7.9.5 Shut-off valves must be installed in accordance with TP1332 and ABYC requirements, remote from the fuel tanks and engine compartments. Labeled as per TCMSB TP 1332 requirements.

7.9.6 The fuel tank must be equipped with an anti-syphon valve installed on the suction.

7.9.7 Fuel tank vent pipes are to be equipped with a non-return check valve.

7.10 Fuel Tank

7.10.1 The vessel must be fitted with one (1) fuel tank with baffles as necessary.

7.10.2 The tank must be aluminum and fitted below the deck.

7.10.3 The total capacity must be a minimum of two hundred liters (303) liters.

7.10.4 Fuel Tank must be hydrostatically tested, or air tested to 3.0 p.s.i. and be labelled per the requirements of TP1332.

7.10.5 Fuel tank(s) must be fitted with fuel level/capacity sender unit and a gauge on the dash of the console for the operator.

7.10.6 The fuel tank(s) is(are) to be equipped with anti-siphon valve(s) installed on motor inlet if flow rate meet the manufacturer's requirement.

7.10.7 In the event that the boat is fitted with two (2) fuel tanks, the vessel must be equipped with cross-over valves to allow the engines to procure fuel from any tank. These valves are to be clearly identified and easily accessible.

7.11 ELECTRICAL SYSTEM

The electrical system design, component selection and installation must be in accordance with Canadian Standards Association C22.2 NO. 183.2-M1983 (R1999) "Standards for D.C. Electrical Installations on Boats", and TP1332 and/or ABYC 'E' as referenced by TP1332. All electrical equipment and hardware must be installed in accordance with the manufacturer's specifications

7.11.1 Twelve Volt (12V) DC distribution system must be provided to power the engine starting and boat service loads including:

- 7.11.2 Navigation lights;
- 7.11.3 Exterior Lighting;
- 7.11.4 Navigational equipment;
- 7.11.5 Instrumentation;
- 7.11.6 Bilge Pumps;
- 7.11.7 Electronics; and
- 7.11.8 Communications
- 7.11.9 Ancillary Items
- 7.11.10 All electrical equipment must be readily accessible for performing maintenance.
- 7.11.11 Three (3) marine quality 12V power outlets one must be must be installed in the main cabin. There must be two USB charging ports on the helm.

7.12 BATTERIES, CABLES AND CHARGING SYSTEMS

- 7.12.1 Two (2) dedicated starting batteries, type M30MF for the outboards. Dual-battery system, minimum 1000 cranking amps with dual-battery selector switch mounted in a recessed position that conforms to engine manufacturer's specifications.
- 7.12.2 Twelve (12) volt DC distribution system must be provided to power the engine starting and boat service loads including:
 - 7.12.2.1 Navigation, interior, and exterior lighting;
 - 7.12.2.2 Electrical equipment;
 - 7.12.2.3 Instrumentation; and
 - 7.12.2.4 Bilge pumps and alarms.
- 7.12.3 Batteries must be marine grade, 12 V, deep cycle maintenance free glass mat or gel type (no custom batteries), and with the ability to cross connect for inboard or outboard start-up of either engine from either battery where the system has a house battery in addition to the start batteries, the house battery shall be able to be joined to the start batteries if necessary.
- 7.12.4 Battery switches must be Certification Agency, (CE, CSA, USCG, etc.) approved and must be mounted to prevent snagging or accidental switching.
- 7.12.5 Battery compartment must be weather tight and fitted with a suitable means of gas venting including for 'sealed' batteries.
- 7.12.6 Cables for all electrical distribution must be ample in size for the particular service, of marine grade tinned boat cable.
- 7.12.7 The electrical system design, component selection and installation must be in accordance with TP1332 and/or ABYC 'E' as referenced by TP1332. All electrical equipment and hardware must be installed in accordance with the manufacturer's specifications.
- 7.12.8 Breaker panels to be appropriately sized for the equipment detailed in this TSOR with a minimum of two (2) spares.
- 7.12.9 One (1) remote 12V marine grade accessory plug must be supplied and installed near the operators.
- 7.12.10 All fitted electrical equipment must be capable of operating simultaneously with any other fitted electronics equipment without causing interference to any electronic equipment or to the magnetic compass.
- 7.12.11 All operation switches for equipment must be labelled.

- 7.12.12 One (1) shore power connection must be fitted as identified in section 5.4.7, complete with a marine grade service rated 30-ft shore power cable, capable of supplying 120V AC, 30 ampere, single-phase service on each boat.

7.13 CABLING INSTALLATION

PROTECTION OF CONTROLS - All control cables, electrical wiring for the motor and the steering hydraulic hoses are to be installed in UV resistant plastic pipes (LOOM) or equal. These pipes are to be installed in such a manner as to ensure that no cable is immersed in water.

- 7.13.1 Cables for all electrical distribution must be ample in size for the particular service, of marine grade tinned boat cable.
- 7.13.2 Cables must be grouped into wiring harnesses wherever possible. All wiring harnesses must be routed through protective conduit pipe. Where impractical cables and conductors must be supported with clamps or straps at least every 18 inches on horizontal runs and every 14 inches on vertical runs.
- 7.13.3 Cabling / conductors passing through watertight boundaries, decks, bulkheads or other exposed surfaces must be installed to maintain watertight integrity of the structure. Cable entry into watertight enclosures must be through watertight marine glands of suitable size.
- 7.13.4 Cabling / conductors passing through structures without watertight glands, must be protected against chafing by the use of abrasive resistant grommets.
- 7.13.5 Routing cables through foamed spaces must be avoided wherever possible. Cables that must be routed through foamed spaces must be run in PVC conduit pipe. The pipe must be arranged in a manner that prevents water from becoming entrapped in the pipe.

7.14 NAVIGATION LIGHTING

LED lighting must be used where available

- 7.14.1 Navigation lights must be permanently fitted to boat with protected wiring and must be waterproof. All around mast /anchor light ratchet mast mounting is acceptable.
- 7.14.2 The fixtures must be of such a design as to resist the effects of vibration and must be provided with adequate protection from damage that may occur when lying alongside a vessel or a pier. (The Hella NaviLED Series of lights, including the NaviLED 360 all-round light , and NaviLED side lights meet this requirement.)
- 7.14.3 Non-white lighting must be wired together on a separate breaker of the 12 volt DC electrical system. All around Mast /Anchor light showing clear above the radar scanner as per TP 1332. One three way rocker switch, labelled "NAV" which turns on all Nav lights. When switched to the "ANC" side, only the anchor light is on.

7.15 ELECTRONIC AND NAVIGATION EQUIPMENT

- 7.15.1 All antennas must be mounted on cabin top with fold down connections for road travel. All cable penetrations must pass through watertight glands. The following Electronic equipment will be supplied as GSM and must be installed by the Contractor:

- 7.15.1.1 Raymarine C127 Multifunction Navigation Display with 12.1" Sunlight Viewable Color display, model E02022 or equivalent. Plotter mounted on vessel dash, and minimizes interference with operator's vision;
- 7.15.1.2 RD24-24"High Performance 4KW Raydome Antenna E-52067 with 15m cable;
- 7.15.1.3 Raymarine Raystar 125 GPS Sensor E32042 Navionics Chart for appropriate areas;
- 7.15.1.4 Raymarine E66008 in Hull Depth Adjustable Angled in Hull Transducer;
- 7.15.1.5 Raymarine DSM300 Digital Sounder Module, model E63069;
- 7.15.1.6 Raymarine Smart Heading System for Pathfinder model E12102 Gyro Stabilized Fluxgate Compass System;
- 7.15.1.7 ICOM IC M604 VHF DSC radio. Complete with loud hailer/intercom function plumbed to Radio;
- 7.15.1.8 Antenna, specification is Comrod AV60P 8 and Shakespeare 4187 HD ratchet mount;
- 7.15.1.9 Whelan Loud Hailer / Siren; and
- 7.15.1.10 Clarion 435 CD AM/FM stereo.
- 7.15.2 The Contractor must supply and install an electric horn that meets the requirements of the Canadian Standards Association (CSA) Collision Regulations. The horn must be operated by a spring-loaded switch located on the operator's console;
- 7.15.3 The Contractor must supply and install a direct read compass with light on each boat. The magnetic compass must be mounted on the centreline of the operator stations, in easy view of the operator when facing forward. Deviation card development is an Owner responsibility. (The Ritchie Explorer meets this requirement.); and
- 7.15.4 One (1) externally mounted EPIRB RLS 406MZ beacon.

7.16 DRAINAGE & BILGE SYSTEMS

- 7.16.1 An electric bilge pump with 2000 gph capacity must be fitted in the main hull or largest watertight division as well as a fixed manual operated bilge pump of the diaphragm type. The bilge pump(s) must be located so that they take suction from the lowest point of the hull. Piping must be installed which will allow the bilge pump(s) to discharge directly overboard. Any additional watertight division of the hull will be serviced by a bilge pump of 1500 GPH capacity. The wire gauge for all bilge pumps must be a minimum of 10 gauge.
- 7.16.2 An automatic level sensor control must be fitted that turns on the electric bilge pump (Non-Pedal type) when water is present in the bilge. The electric bilge pump control switch must be located on the operator's console, with settings for 'momentary on', 'off', and 'automatic' operation. An indicator light must be provided at the control that lights when the bilge pump is operating.
- 7.16.3 High water alarm for the engine installation space and every other space serviced by a bilge pump.
- 7.16.4 Hull drainage - a brass or stainless steel threaded plug must be provided in the lowest point to drain the hull when out of the water.

- 7.16.5 Valves and handles must be made of non-corroding materials and must be located where they are readily accessible for operation, maintenance or removal.
- 7.16.6 GENERAL - Any forward water retaining compartment without pump must have a piped drain to the aft bilge with a stainless steel ball valve. The valve must be readily accessible for testing or draining the forward bilge to the aft pump.

7.17 PAINTING AND CORROSION PROTECTION

Aluminium components not identified for paint must have a clear coat painted finish on all specified exterior and interior surfaces, comprised of suitable etch, primers, and topcoat. Contractor must follow the preparation and application requirements defined by the paint supplier. Typical single coat paint systems can be applied in the 5 to 7-mil thickness range per coating set. Typical system components would be: a) etch-primer; b) two coats of primer; and c) minimum two topcoats.

- 7.17.1 The standard color of the console of each boat must be international F000, Mist grey. All upholstery must be grey.
- 7.17.2 Hull above the water line and cabin: DFO Slate Grey (RAL7042).
- 7.17.3 Exterior Decks and top of bulwarks (around the perimeter of the boat): Anti-slip, Sure-Foot grey.
- 7.17.4 Underwater hull antifouling for Aluminum Trilux II color: Black
- 7.17.5 Prior to delivery, the Contractor must ensure that all non-painted interior or exposed surfaces are free of cosmetic blemishes, including all construction marks, scratches, gouges and stains.

8.0 TESTS & TRIALS

The Contractor must conduct their own inspections, tests and trials to verify successful completion of the Work in accordance with this TSOR and the proper operation of the vessel and all associated equipment. The requirements for inspections, tests and trials and associated deliverable documentation are defined in the Contract and Annexes to the contract including any test, trials or sample reports attached thereto. All discrepancies identified through the inspection, test and trials processes must be corrected prior to delivery.

8.1 TESTS - GENERAL

- 8.1.1 The Contractor must inspect and test the following items, as a minimum, for adherence to the contract requirements and proper operation (proper operation means that the equipment can be started, operated, connected together and demonstrated to function in a normal fashion, as applicable). All discrepancies must be corrected prior to delivery. The required inspections and tests are minimums and are not intended to supplant any controls, examinations, inspections or tests normally employed by the Contractor to assure the quality of the boats:

- 8.1.1.1 Weight;
- 8.1.1.2 Construction Quality;
- 8.1.1.3 Lifting Gear;
- 8.1.1.4 Propulsion Engines, including starting;
- 8.1.1.5 Steering System;

- 8.1.1.6 Fuel System;
- 8.1.1.7 Electrical System; and
- 8.1.1.8 Electronics.

8.2 SEA TRIALS - GENERAL

- 8.2.1 Sea trials must be conducted by the Contractor to demonstrate the boats and their equipment conform to the requirements as stated in the contract. All expenses incident to the trials must be borne by the Contractor, including fuel unless otherwise specified. A crew provided by the Contractor must operate the boats during sea trials. The minimum acceptable sea trial is identified in Appendix A.
- 8.2.2 All Sea Trial instrumentation and equipment must be furnished and operated by the Contractor. Trial instrumentation, where applicable, must not replace the boat's instruments.
- 8.2.3 The Contractor must submit a Test & Trials Plan, including a description of all of the acceptance trials to be performed for each boat. The boats must operate in the Normal Loaded Condition. As a minimum, the following trials must be conducted for each boat:
 - 8.2.3.1 Speed Trials - The speed trials must be done over a course at least one (1) nautical mile in length. Two (2) runs must be made over the course, one (1) in each direction with the speeds for the two (2) runs averaged. The use of GPS data (averaged) is acceptable;
 - 8.2.3.2 Endurance Trial -The boats must operate in the Normal Loaded Condition, at maximum speed for no more than the maximum time allowed if it has not operated for the minimum break-in period (typically five (5) hours);
 - 8.2.3.3 Astern Propulsion - The boats must be operated and manoeuvred using astern propulsion to establish the astern performance. During the backing performance tests the throttles must be set to provide 1/3 of the rated engine horsepower; and
 - 8.2.3.4 Steering Gear - Tests must be conducted on the steering gear to demonstrate the adequacy of the steering system under all operations. Manoeuvring tests must be performed to ensure that each boat meets the stated requirements. Manoeuvring trials must be conducted in the Normal Load Condition and repeated in the Full Load Condition.
- 8.2.4 The Contractor must provide a Tests & Trials Sheet, (Appendix A) for each boat and include this sheet in the technical publications (see section 9.4).
- 8.2.5 The Contractor must notify the Contracting Authority and the Technical Authority Canada no less than two (2) weeks prior to sea trials. At a minimum, the Technical Authority will witness and attend the sea trials. Sea trial results must be forwarded to the Technical Authority prior to the delivery of the boats.
- 8.2.6 At the conclusion of sea trials, each boat must be thoroughly cleaned and inspected. Engine cooling systems must be flushed through with fresh water. The Contractor must repair any damage to the boats or ancillary equipment resulting from sea trials to the satisfaction of Canada.
- 8.2.7 For the purpose of the trials, Normal Loaded Condition must be considered to be the basic boat, fitted with all normal equipment, full fuel, with complement and loads per Boat Particulars, section 4.1.

- 8.2.8 Final Inspection must not be performed until all tests have been satisfactorily completed with data available for review. The boats must be ready for delivery in all respects, except for final preparation for shipment. The Contractor must provide personnel, as required, to resolve questions and to demonstrate equipment operation maintenance accessibility, removal and installation.
- 8.2.9 Stability examination per TP1332, with ISO Design Category “C” further will require the Contractor to record all stability calculations and assessment utilizing ISO 12217-1, ISO 11812 and ISO 12216 with all detailed calculation worksheets, providing a copy for each boat produced as per Section 9.4.1.
- 8.2.10 Final Inspection - Upon delivery, the Technical Authority, or a representative of the Technical Authority will conduct the final delivery inspection. The Contractor must document the results of the delivery and provide these results to the Technical Authority and the Contracting Authority for Acceptance as per the Contract. The Contractor must repair any damage to the boats/equipment resulting from shipping to the satisfaction of Canada.

9.0 DOCUMENTATION

9.1 GENERAL

All documentation to be included in the Technical Publications must be provided in both official languages (French and English).

9.2 NATIONAL ASSET CODE

- 9.2.1 The National asset code for this vessel is **VXC02**. The Contractor must add this five (5) character code to the builder’s plate of the boat with the prefix “National Asset Code”.

9.3 BUILDER’S PLATE

- 9.3.1 A Builder’s plate must be affixed to the vessel and trailer in a readily visible location, e.g. for a boat, in way of the operator position, for a trailer on the left side of the tongue.
- 9.3.2 The plate must be made of a weather resistant material compatible with that to which it is affixed.
- 9.3.3 The dimensions of the plate must be not less than 200mm x 125mm
- 9.3.4 The plate must contain the following information, permanently etched:
- 9.3.4.1 National Asset Code;
 - 9.3.4.2 Builder;
 - 9.3.4.3 Hull Number;
 - 9.3.4.4 Year of Construction; and
 - 9.3.4.5 Lightship Weight in kilograms.

9.4 TECHNICAL PUBLICATIONS

- 9.4.1 The Contractor must provide, upon delivery of the boats, complete set of technical publications of a comprehensive owner/operator manual that provides a physical and functional description of the boat, it’s machinery and equipment, AC and DC electrical system schematics as well as delivery testing and sea trial results (Appendix A) including stability calculation documentation.
- 9.4.2 The Contractor is to provide copies of the technical publications as follows:

9.4.2.1 One (1) complete hard copy and one (1) electronic copy of technical publications to be delivered with the boat.

9.4.2.2 One (1) complete hard copy and one (1) electronic copy of technical publications to be delivered to the Technical Authority.

9.5 GENERAL INFORMATION SECTION

9.5.1 The General Information Section must include a description of the arrangement and function of all structures, systems, fittings and accessories that comprise each boat, with illustrations as appropriate:

9.5.1.1 Operating procedures;

9.5.1.2 Basic operating characteristics (such as temperatures, pressures, flow rates);

9.5.1.3 Installation criteria and drawings, assembly and disassembly instructions with comprehensive illustrations showing each step;

9.5.1.4 Recommended planned maintenance; and

9.5.1.5 Complete troubleshooting procedures.

9.6 ADDITIONAL DELIVERABLE DOCUMENTATION

9.6.1 The following additional documentation must be supplied in the manuals delivered (defined in 9.4.2) for the boat:

9.6.1.1 Tonnage Registration Certificate in accordance with TP 13430 -

<http://www.tc.gc.ca/eng/marinesafety/svcp-gt-3948.htm> ;

9.6.1.2 Registration to the Small Vessel Compliance Program (SVCP) Website:

<http://www.tc.gc.ca/eng/marinesafety/svcp-menu-3633.htm> ;

9.6.1.3 Two (2) Bill of Sales, one (1) for the vessel and one (1) for the trailer;

9.6.1.4 Test & Trial results as required by Appendix A;

9.6.1.5 Acceptance Certificates, i.e. life saving appliances, lifting appliances, engine test reports, calibration certificates, extinguishers, etc;

9.6.1.6 A valid Motor Vehicle Registration Certificate for the relevant Province, for the trailer; and

9.6.1.7 Testing Check Sheets.

10.0 SHIPPING AND DELIVERY

Prior to shipping, the boat is to be cleaned, appropriately protected and covered in accordance with the instructions specified in this section.

10.1 Prior to shipping, the boat must be secured on their respective trailers, cleaned, preserved and covered in accordance with this section. All areas of the boat are to be cleaned prior to covering for shipping. Bilges are to be dry and free of oil and debris and the fuel tanks must be full with fuel stabilizer added.

10.2 The propulsion systems must be preserved in accordance with the manufacturer's recommendations for storage of up to one year in an environment that will be subjected to freezing temperatures.

10.3 The batteries are to be disconnected. A warning plate is to be tied to the steering wheel with a wire indicating that the boat has been protected for shipping and storage and must not be started until the propulsion machinery has been reactivated.

10.4 All contact points with the boat are to be padded. A shrink wrap cover is to be provided to protect the boat during shipping and storage.

10.5 Means of Delivery: The Contractor must deliver the vessel/trailer combination, the trailer supplied for the boat must not be utilized as means of delivery.

11.0 WARRANTY AND SERVICE PROVISIONS

11.1 COMPONENTS AND EQUIPMENT SUPPORT

All components and all mechanical, auxiliary, electronic and electrical equipment installed on the boat must be supportable by parts and service in Canada within 30 days.

11.2 SPARE PARTS

To facilitate replacement and inter-changeability of parts, as well as maintenance procedures and operator training wherever practicable the Contractor must standardize on selection of equipment, fittings and fabrication methods within all boats supplied.

12.0 TRAILER

12.1 The Contractor must supply a tandem axle trailer to fit the boat, aluminum I beam construction and be rated at least 20% over the anticipated 'Normal Load Condition' weight of the boat. The trailer must be certified commercial requirements in accordance with Department of Transport regulations for towing the vessel, and be constructed and equipped with the following:

- 12.1.1 Tandem axle trailer, aluminum I beam construction with spare tire on rim (mounted to front of trailer), safety chains and positive pressure air tight bearing protection with grease nipples and an access ladder to the bow of the boat.
- 12.1.2 Brake and turn signal submersible style LED lighting, with 7-prong flat wiring connector. (Note requirement for other connector if required for the equipment listed for trailer).
- 12.1.3 Stainless steel calipers, mounting brackets and rotors with the appropriate brake pads.
- 12.1.4 Electric/Hydraulic, jurisdiction compliant braking system.
- 12.1.5 Manual two speed bow winch assembly with winch strap and non-corroding snap hook, bow chock, and swivel tongue jack, with wheel. The winch must be of adequate size to launch and recover the vessel and fitted with anti-reverse mechanism;
- 12.1.6 Heavy-duty 'stand-on' diamond plate step fenders with mud flaps and hitch to accommodate a 2 5/16 inch ball;
- 12.1.7 Bunks and wheel mounted spare tire and carrier, with lug wrench; and six removable attachment points. Bunks must be lined with a protector.
- 12.1.8 Trailer to be supplied with four (4) ratchet tie down straps with hooks securing boat to trailer aft. Turnbuckle to be provided for securing boat to trailer forward.
- 12.1.9 The trailer must be fitted with a drop leg, side wind jack with caster wheel with anti-reversing mechanism sized to meet the normal load condition of the vessel.
- 12.1.10 Class III weight distributing hitch compliant.
- 12.1.11 Radial tires approved for trailers on solid galvanized rims, with an equivalent sized spare on a high mount bracket. The tires must have a capacity equal or superior to the load capacity of the trailers.

12.2 The contractor must record the trailer sales and registration information and provide the information in each vessel manual.

APPENDIX A

SMALL BOAT / VESSEL TESTS & TRIALS SHEET

CONTRACT # F7044-170014

Small Boat / Vessel Builder:			
Small Boat / Vessel Description:			
Hull Identification Number:			
National Asset Code:			
Date of Trials:			
Personnel in Attendance:			
Builder			
PWGSC			
DFO			
DFO			
Time: _____ hrs Departing from _____			
Small Boat / Vessel Weights:	Dry Weight of Hull with cabin:		_____ lbs/ _____ kg
	Furnishings & Fittings:		_____ lbs/ _____ kg
	Engines & Equipment:		_____ lbs/ _____ kg
	Fuel: _____ Imp gal	Fuel: _____ Litres	_____ lbs/ _____ kg

	Total Weight of Small Boat/Vessel:	_____ lbs/ _____ kg
	Number of Crew_____and operating equipment:	_____ lbs/ _____ kg
	Test Total Laden Weight:	_____ lbs/ _____ kg
	Trailer weight:	_____ lbs/ _____ kg
	Boat & Trailer weight:	_____ lbs/ _____ kg
Motors: Starting - Operation "IDENTIFY INBOARD/OUTBOARDS"	Port	<input type="radio"/> Immediate, Yes / No
	Starboard	<input type="radio"/> Immediate, Yes / No
Propellers/Impellers	Pitch	_____
	Diameter	_____
	No. of Blades	_____
	Stainless Steel or Aluminum	<input type="radio"/> S/S ____ AL
Static Attitude & Trim:		
Weather Conditions: Refer to attached Beaufort Wind Scale. BWS No. _____		
Speed Trials	Speed Required _____ - _____ knots	
	Cruising Speed: measured mile 1 way	_____ kts @ _____ rpm
	Cruising Speed: measured mile return	_____ kts @ _____ rpm

	Averaged Cruising Speed:		_____ kts @ _____ rpm
	Maximum Speed: measured mile 1 way		_____ kts @ _____ rpm
	Maximum Speed: measured mile return		_____ kts @ _____ rpm
	Average Maximum Speed		_____ kts @ _____ rpm
Full Throttle	From dead stop to plane	_____ seconds	
	From dead stop to 30 knots	_____ seconds	
Astern Propulsion:	Straight line to 2000 rpm	<input type="radio"/> Issues, Yes / No	
	Hard a-port	<input type="radio"/> Issues, Yes / No	
	Hard a-starboard	<input type="radio"/> Issues, Yes / No	
	Emergency stop	_____ seconds	
Tubes (if applicable)	No. of Chambers	_____	
	Semi-auto fill system	<input type="radio"/> Yes / No	
	Time to fill all chambers	_____ seconds	
Endurance Trials: X = gallons or Litres	Fuel consumption		
	Port & Starboard Motor: at cruise:	_____ X/hr @ _____ rpm	
	Port & Starboard Motor: at full throttle:	_____ X/hr @ _____ rpm	
Steering: Acceptable Y /N	Straight line	<input type="radio"/> Yes / No	
	Hard-Port radius of turn. Full Throttle	_____ feet	
	Hard-Stbd radius of turn. Full Throttle	_____ feet	

	Lock to lock = 35 degrees pt. & stbd	<input type="radio"/> Yes / No
	Effective steering 0-5 knots	<input type="radio"/> Yes / No
	5-10 knots	<input type="radio"/> Yes / No
	20-30 knots	<input type="radio"/> Yes / No
	Full speed	<input type="radio"/> Yes / No
Outboard/Inboard Leg Trim Control:	From fully raised to fully lowered.	<input type="radio"/> Acceptable Yes / No
Trim Tab Operation:	Fully raised, fully lowered.	<input type="radio"/> Acceptable Yes / No
Engine Controls:	Start	<input type="radio"/> Issues, Yes / No
	Shift	<input type="radio"/> Issues, Yes / No
	Throttle	<input type="radio"/> Acceptable Yes / No
Engine Gauges:	Tachometer	<input type="radio"/> Acceptable Yes / No
	Fuel gauges	<input type="radio"/> Acceptable Yes / No
	Trim gauges	<input type="radio"/> Acceptable Yes / No
	Oil pressure	<input type="radio"/> Acceptable Yes / No
Engine Gauges:	Voltmeter	_____ volts
Cabin Sound Levels:	Cruising speed- door & windows closed	_____ dbA @ _____ rpm
	Cruising speed- door & windows open	_____ dbA @ _____ rpm
	Full speed- door & windows closed	_____ dbA @ _____ rpm
	Full speed- door and windows open	_____ dbA @ _____ rpm
Outboard/Inboard	Starting	<input type="radio"/> Acceptable Yes / No

engine operation:	Shifting	<input type="radio"/> Acceptable Yes / No
	Throttle	<input type="radio"/> Acceptable Yes / No
	Raise	<input type="radio"/> Acceptable Yes / No
	Lower	<input type="radio"/> Acceptable Yes / No
Loaded Vessel Drop Test:	If applicable	<input type="radio"/> Acceptable Yes / No
Lifting Bridle Certified:	If applicable	<input type="radio"/> Acceptable Yes / No
Rollover test	If applicable	<input type="radio"/> Acceptable Yes / No

<u>NOTES</u>

Beaufort Wind Scale Identifier

Force	Wind Speed		Descriptive Term	Effects Observed at Sea	Effects Observed on Land
	Km/h	Knots			
0	Less than 1	Less than 1	Calm	Sea surface like a mirror, but not necessarily flat.	Smoke rises vertically.
1	1 - 5	1 - 3	Light air	Ripples with the appearance of scales are formed, but without foam crests.	Direction of wind shown by smoke drift, but not wind vanes.
2	6 - 11	4 - 6	Light breeze	Small wavelets, still short but more pronounced. Crests do not break. When visibility good, horizon line always very clear.	Wind felt on face. Leaves rustle. Ordinary vane moved by wind.
3	12 - 19	7 - 10	Gentle breeze	Large wavelets. Crests begin to break. Foam of glassy appearance. Perhaps scattered whitecaps.	Leaves and small twigs in constant motion. Wind extends light flag.
4	20 - 28	11 - 16	Moderate breeze	Small waves, becoming longer. Fairly frequent whitecaps.	Raises dust and loose paper. Small branches are moved.
5	29 - 38	17 - 21	Fresh breeze	Moderate waves, taking a more pronounced long form. Many whitecaps are formed. Chance of some spray.	Small trees with leaves begin to sway. Crested wavelets form on inland waters.
6	39 - 49	22 - 27	Strong breeze	Large waves begin to form. The white foam crests are more extensive everywhere. Probably some spray.	Large branches in motion. Whistling heard in telephone wires. Umbrellas used with difficulty.
7	50 - 61	28 - 33	Near gale	Sea heaps up and white foam from breaking waves begins to be blown in streaks along the direction of the wind.	Whole trees in motion. Inconvenience felt in walking against wind.
8	62 - 74	34 - 40	Gale	Moderately high waves of greater length. Edges of crests begin to break into the spindrift. The foam is blown in well-marked streaks along the direction of the wind.	Breaks twigs off trees. Generally impedes progress. Walking into wind almost impossible.
9	75 - 88	41 - 47	Strong gale	High waves. Dense streaks of foam along the direction of the wind. Crests of waves begin to topple, tumble and roll over. Spray may affect visibility.	Slight structural damage occurs, e.g. roofing shingles may become loose or blow off.
10	89 - 102	48 - 55	Storm	Very high waves with long overhanging crests. Dense white streaks of foam. Surface of the sea takes a white appearance. The tumbling of the sea becomes heavy and shock-like. Visibility affected.	Trees uprooted. Considerable structural damage occurs.
11	103 - 117	56 - 63	Violent storm	Exceptionally high waves. Sea completely covered with long white patches of foam. Visibility affected.	Widespread damage.
12	118 - 133	64 - 71	Hurricane	Air filled with foam and spray. Sea entirely white with foam. Visibility seriously impaired.	Rare. Severe widespread damage to vegetation and significant structural damage possible.



BEAUFORT FORCE 0
WIND SPEED: LESS THAN 1 KNOT
SEA: SEA LIKE A MIRROR



BEAUFORT FORCE 1
WIND SPEED: 1-3 KNOTS
SEA: WAVE HEIGHT 1M (25FT), RIPPLES WITH THE APPEARANCE OF SCALES, BUT WITHOUT FOAM CRESTS



BEAUFORT FORCE 2
WIND SPEED: 4-6 KNOTS
SEA: WAVE HEIGHT 2-3M (5-10FT), SMALL WAVELETS, CRESTS HAVE A GLASSY APPEARANCE AND DO NOT BREAK




BEAUFORT FORCE 4
WIND SPEED: 11-16 KNOTS
SEA: WAVE HEIGHT 1-1.5M (3.5-5FT), SMALL WAVES BECOMING LONGER, FAIRLY FREQUENT WHITE HORSES



BEAUFORT FORCE 5
WIND SPEED: 17-21 KNOTS
SEA: WAVE HEIGHT 2-2.5M (6-8FT), MODERATE WAVES TAKING MORE PRONOUNCED LONG FORM, MANY WHITE HORSES, CHANCE OF SOME SPRAY



BEAUFORT FORCE 6
WIND SPEED: 22-27 KNOTS
SEA: WAVE HEIGHT 3-4M (9.5-13 FT), LARGER WAVES BEGIN TO FORM, SPRAY IS PRESENT, WHITE FOAM CRESTS ARE EVERYWHERE



BEAUFORT FORCE 7
WIND SPEED: 28-33 KNOTS
SEA: WAVE HEIGHT 4-5.5M (13.5-19 FT), SEA HEAPS UP, WHITE FOAM FROM BREAKING WAVES BEGINS TO BE BLOWN IN STREAKS ALONG THE WIND DIRECTION



BEAUFORT FORCE 8
WIND SPEED: 34-40 KNOTS
SEA: WAVE HEIGHT 5.5-7.5M (18-25FT), MODERATELY HIGH WAVES OF GREATER LENGTH, EDGES OF CREST BEGIN TO BREAK INTO THE SPINDRIFT, FOAM BLOWN IN WELL MARKED STREAKS ALONG WIND DIRECTION.



BEAUFORT FORCE 9
WIND SPEED: 41-47 KNOTS
SEA: WAVE HEIGHT 7-10M (23-32FT), HIGH WAVES, DENSE STREAKS OF FOAM ALONG DIRECTION OF THE WIND, WAVE CRESTS BEGIN TO TOPPLE, TUMBLE, AND ROLL OVER, SPRAY MAY AFFECT VISIBILITY.



BEAUFORT FORCE 10
WIND SPEED: 48-55 KNOTS
SEA: WAVE HEIGHT 9-12.5M (29-41FT), VERY HIGH WAVES WITH LONG OVERHANGING CRESTS, THE RESULTING FOAM, IN GREAT PATCHES, IS BLOWN IN DENSE WHITE STREAKS ALONG WIND DIRECTION, ON THE WHOLE, SEA SURFACE TAKES A WHITE APPEARANCE, TUMBLING OF THE SEA IS HEAVY AND SHOCK-LIKE, VISIBILITY AFFECTED.



BEAUFORT FORCE 11
WIND SPEED: 56-63 KNOTS
SEA: WAVE HEIGHT 11.5-16M (37-52FT), EXCEPTIONALLY HIGH WAVES, SMALL-MEDIUM SIZED SHIPS MAY BE LOST TO VIEW BEHIND THE WAVES, SEA COMPLETELY COVERED WITH LONG WHITE PATCHES OF FOAM LYING ALONG WIND DIRECTION, EVERYWHERE, THE EDGES OF WAVE CRESTS ARE BLOWN INTO FROTH.



BEAUFORT FORCE 12
WIND SPEED: 64 KNOTS
SEA: SEA COMPLETELY WHITE WITH DRIVING SPRAY, VISIBILITY VERY SERIOUSLY AFFECTED, THE AIR IS FILLED WITH FOAM AND SPRAY