


3 Greenleaf Dr., Charlottetown
Prince Edward Island C1A 8E7
Phone: (902) 566-5456, Fax: (902) 566-3598
email: lakeshgarg201@gmail.com






LOCATION MAP
SCALE/ÉCHELLE: NTS

DEMOLITION NOTES:

- EXISTING WHARF DECK AND OTHER MATERIAL INCLUDING PILE CUT-OFF, WALLS, SHEATHING ETC. TO BE REMOVED AND DISPOSED OFF SITE.
- ALL OTHER MATERIAL, DEBRIS, ETC. TO BE REMOVED AND DISPOSED OFF SITE.
- ALL OTHER MATERIAL, DEBRIS, ETC. TO BE MOVED OFF THE SITE.

DEMOLITION PROCEDURE:

- REMOVE CONCRETE AND DEBRIS, ETC. FROM WHARF SECTION 408 FOR ACCESS TO NEW CONSTRUCTION. ALL REMOVED MATERIALS TO BE DISPOSED OFF SITE IN THIS CONTRACT.
- REMOVE EXISTING WHARF TIMBER DECK AND ANY OTHER DEBRIS, ETC., INCLUDING CUTTING OFF THE EXISTING CREOSOTE DECK.
- SEE NOTES ON DRAWING M-1 ALSO.
- ALL MATERIALS TO BE DISPOSED OFF SITE SHALL BE DISPOSED IN ACCORDANCE WITH ALL APPLICABLE ENVIRONMENTAL LEGISLATION OR OTHER REQUIREMENTS.
- REMOVE CONCRETE AND TIMBER DECK, DEBRIS, ETC. FROM WHARF SECTION 408 AND DISPOSE OFF SITE (FUTURE CONTRACT).



revisions	date
4	REVISÉ - ISSUÉ POUR TENDRE Jun. 08 2017
3	REVISÉ - ISSUÉ POUR TENDRE Nov. 24 2016
2	ISSUÉ POUR TENDRE Aug. 19 2016
1	99% SUBMISSION July 04 2016

project
**WHARF RECONSTRUCTION
408
MONTAGUE
KINGS COUNTY, PEI**

drawing
**EXISTING SITE PLAN,
SECTIONS &
DEMOLITION
REQUIREMENTS**

designed L.G. coripu
date JUNE, 2017
drawn M.G.M. dessin
date JUNE, 2017
approved
date
Tender Soumission
Lokesh Garg
PWGSC/Project Manager Administrateur de projets TPSGC
project number no. du projet
R.084160.001
drawing no. no. du dessin
M2 OF 5