

CONTRACT ITEM LISTING SHEET

Job Description: CRC Shirleys Bay – Roadway
Modifications

Date: April 19, 2017

Item No.	Description	Extra Specification Numbers	Estimated Quantity *
General			
A-1	Traffic Control Plan		L.S.
A-2	Construction Site Pedestrian Control Plan		L.S.
A-3	Erosion and sediment control plan and monitoring		L.S.
Culverts			
B-1	150mm Non-perforated pipe subdrain		60 m
B-2	600mm x 600mm PCC catchbasin per OPSD-705.010		2 ea (P)
B-3	200 mm dia. PVC catchbasin lead - class SDR 35		19 m (P)
B-4	Connection into maintenance holes, catch basins, ditch inlets, culverts and sewers		2 ea
Road			
C-1	Removal of asphalt sidewalk		111 m ² (P)
C-2	Removal of Catchbasin		3 ea (P)
C-3	Removal of concrete curb		580 m (P)
C-4	Removal of concrete sidewalk		253 m ² (P)
C-5	Saw-cutting of asphalt		270 m
C-6	Removal of asphalt pavement by dry grinding		1,523 m ²
C-7	Remove Asphalt Pavement - Full Depth (Stripping)		2,659 m ²
C-8	Earth excavation - grading		3,425 m ³ (P)
C-9	Geotextile Fabric - Woven Class II		66 m ²
C-10	Rip Rap for sewer or culvert outlet per OPSD 810.010		54 m ² (P)
C-11	Granular 'A'		2,155 t
C-12	Granular 'B' Type II		4,384 t
C-13	Asphalt Sidewalks, medians, boulevards and islands		239 m ² (P)
C-14	Monolithic Concrete Sidewalks, Boulevards and Islands		746 m ² (P)
C-15	Concrete barrier curb as per SC1.1		212 m (P)
C-16	Adjusting or Rebuilding Maintenance Holes		2 ea (P)

	and Valve Chambers, any size, any type		
C-17	Adjusting or Rebuilding Catch Basins, any size, any type including twin		2 ea (P)
C-18	Performance Graded Superpave 12.5mm		553 t
C-19	Performance Graded Superpave 19.0mm		955 t
C-20	Adjust or rebuild electrical hand hole or maintenance hole		2 ea
C-21	Removal of sign		11 ea
C-22	Remove, salvage, and return sign to owner		1 ea
C-23	Removal of Tree		6 ea
C-24	Concrete Curb and Gutter per OPSD 600.040		136 m
C-25	Mountable Curb per OPSD 600.030		50 m
Landscaping			
D-1	Topsoil, imported (100mm thick)		146 m ³
D-2	Sodding, including watering		1,467 m ²
Rigid Ducts and Associated Wiring			
E-1	2 x 75mm Polymeric PVC rigid duct concrete encased		23 m
E-2	3 x 75mm Polymeric PVC rigid duct concrete encased		11 m