

Part 1 General

1.1 WORK COVERED BY CONTRACT DOCUMENTS

- .1 Work of this Contract comprises the replacement of make-up air unit serving Laundry area at the Saskatchewan Penitentiary located outside Prince Albert.

1.2 CONTRACT METHOD

- .1 Construct Work under stipulated price contract.

1.3 WORK SEQUENCE

- .1 Construct Work in stages to accommodate Owner's continued use of premises during construction.
- .2 Co-ordinate Progress Schedule and co-ordinate with Owner Occupancy during construction.
- .3 Maintain fire access/control.

1.4 CONTRACTOR USE OF PREMISES

- .1 Limit use of premises for Work, for storage, for access, to allow:
 - .1 Owner occupancy.
- .2 Co-ordinate use of premises under direction of Departmental Representative.
- .3 Remove or alter existing work to prevent injury or damage to portions of existing work which remain.
- .4 Repair or replace portions of existing work which have been altered during construction operations to match existing or adjoining work, as directed by Departmental Representative.
- .5 At completion of operations condition of existing work: equal to or better than that which existed before new work started.

1.5 OWNER OCCUPANCY

- .1 Owner will occupy premises during entire construction period for execution of normal operations.
- .2 Co-operate with Departmental Representative in scheduling operations to minimize conflict and to facilitate Owner usage.

1.6 ALTERATIONS, ADDITIONS OR REPAIRS TO EXISTING BUILDING

- .1 Execute work with least possible interference or disturbance to building operations, occupants, and normal use of premises. Arrange with Departmental Representative to facilitate execution of work.

1.7 EXISTING SERVICES

- .1 Notify, Departmental Representative and utility companies of intended interruption of services and obtain required permission.
- .2 Where Work involves breaking into or connecting to existing services, give Departmental Representative 48 hours notice for necessary interruption of mechanical or electrical service throughout course of work. Minimize duration of interruptions. Carry out work at times as directed by governing authorities with minimum disturbance to vehicular traffic.
- .3 Provide alternative routes for personnel and vehicular traffic.
- .4 Establish location and extent of service lines in area of work before starting Work. Notify Departmental Representative of findings.
- .5 Submit schedule to and obtain approval from Departmental Representative for any shut-down or closure of active service or facility including power and communications services. Adhere to approved schedule and provide notice to affected parties.
- .6 Provide temporary services when directed by Departmental Representative to maintain critical building and tenant systems.
- .7 Provide adequate bridging over trenches which cross sidewalks or roads to permit normal traffic.
- .8 Where unknown services are encountered, immediately advise Departmental Representative and confirm findings in writing.
- .9 Protect, relocate or maintain existing active services. When inactive services are encountered, cap off in manner approved by authorities having jurisdiction.
- .10 Record locations of maintained, re-routed and abandoned service lines.
- .11 Construct barriers in accordance with Section 01 56 00 - Temporary Barriers and Enclosures.

1.8 DOCUMENTS REQUIRED

- .1 Maintain at job site, one copy each document as follows:
 - .1 Contract Drawings.
 - .2 Specifications.
 - .3 Addenda.
 - .4 Reviewed Shop Drawings.
 - .5 List of Outstanding Shop Drawings.
 - .6 Change Orders.
 - .7 Other Modifications to Contract.
 - .8 Field Test Reports.
 - .9 Copy of Approved Work Schedule.
 - .10 Health and Safety Plan and Other Safety Related Documents.
 - .11 Other documents as specified.

Part 2 Products

2.1 NOT USED

.1 Not used.

Part 3 Execution

3.1 NOT USED

.1 Not used.

END OF SECTION

Part 1 General

1.1 ACCESS AND EGRESS

- .1 Design, construct and maintain temporary "access to" and "egress from" work areas, including stairs, runways, ramps or ladders and scaffolding, independent of finished surfaces and in accordance with relevant municipal, provincial and other regulations.

1.2 USE OF SITE AND FACILITIES

- .1 Execute work with least possible interference or disturbance to normal use of premises. Make arrangements with Departmental Representative to facilitate work as stated.
- .2 Maintain existing services to building and provide for personnel and vehicle access.
- .3 Where security is reduced by work provide temporary means to maintain security.
- .4 Departmental Representative will assign sanitary facilities for use by Contractor's personnel. Keep facilities clean.
- .5 Use only elevators, existing in building for moving workers and material.
 - .1 Protect walls of passenger elevators, to approval of Departmental Representative prior to use.
 - .2 Accept liability for damage, safety of equipment and overloading of existing equipment.
- .6 Closures: Protect work temporarily until permanent enclosures are completed.

1.3 EXISTING SERVICES

- .1 Notify, Departmental Representative and utility companies of intended interruption of services and obtain required permission.
- .2 Where Work involves breaking into or connecting to existing services, give Departmental Representative 48 hours of notice for necessary interruption of mechanical or electrical service throughout course of work. Keep duration of interruptions minimum. Carry out interruptions after normal working hours of occupants, preferably on weekends.
- .3 Provide for personnel and vehicular traffic.
- .4 Construct barriers in accordance with Section 01 56 00 - Temporary Barriers and Enclosures.

1.4 INSTITUTIONAL REQUIREMENTS FOR PWGSC CONTRACTORS

- .1 Establishment of Requirements:
 - .1 Carry out an efficient operation of a penitentiary, it is absolutely necessary for civilian personnel, who are employed on the penitentiary property, to observe established rules and procedures.
 - .2 Prior to commencing work, the contractor shall meet with the Warden or his designate to discuss the nature and extent of all activities involved, and to establish mutually acceptable requirements to ensure that both the project and institution operation may proceed without undue disruption or hindrance except where unavoidable. Such requirements shall include the matters specified in this instruction as well as others peculiar to the immediate locality.

- .2 Working Conditions:
 - .1 Subject to Institutional Security requirements, the warden or his designate shall permit the contractor as much freedom of action and movement as is reasonably possible, and the contractor in turn shall be expected to cooperate with institutional personnel in ensuring that security requirements are observed by construction workers.
- .3 Observation and Inspection:
 - .1 Construction activity and all related movement of personnel & vehicles shall be subject to observation & inspection by institutional staff to ensure that security requirements are met, and understanding of the need for this action is established and maintained throughout.
- .4 Personnel Security:
 - .1 The names of all construction personnel to be employed on the site shall be submitted in writing via SMI form #85 (Security Clearance Request) which may be obtained from Security Intelligence Officer (SIO), Correctional Supervisor In Charge of Construction and/or Public Works Supervisor. All contractors and their employees, including subcontractors and their employees, involved in the contract, must report to the SIO or CS I/C of Construction prior to the first day of employment for the purpose of obtaining a "pass" (photo identification card) and receiving a security briefing. This will only be done after a Security Clearance Request form is completed and approved by the Warden. The Warden or his designate may require close-up facial photographs to be taken of construction personnel, and may have such photographs displayed at appropriate locations in the institution for identification purposes. When the contractors and employees are required to work on the prison property, they will enter and exit the premises via the Service Entrance (Sally Port) if authorized by the CS I/C Construction or designated due to job requirements. The Warden or his designate has the right to refuse permission to enter institutional property to any person whom he has reason to believe may be a security risk.
- .5 Parking:
 - .1 The Warden or his designate shall assign the parking area or areas to be used by the construction personnel and indiscriminate parking in other locations shall not be permitted.
 - .2 All unattended vehicles must have windows closed, doors and trunks locked, and keys removed. Vehicles must not contain any type of weapons, ammunition or spirits (empty, partial or full).
- .6 Shipping and Access to the Site:
 - .1 The contractor shall verify with the Warden or his designate the hours during which vehicles will be allowed to enter or leave the institution. Vehicles or personnel will not be admitted to the institution after normal working hours or on weekends/holidays without prior arrangement with the Warden or his designate. Normal construction work hours are 07:30 hours to 16:30 hours Monday thru Friday.
 - .2 Note: Service Entrance is closed between 11:00 to 13:00 hours unless arrangements are made in advance. The contractor shall have all project material and equipment addressed in his name to avoid confusion with the institutions own shipments. The contractor shall, when overtime work is necessary, inform the Warden or his designate at least 24 hours in advance so that extra staff may

be arranged to maintain the institution's observation inspection of construction activity. The Warden or his designate may prohibit or restrict access to any part of the institution. He may require that, in certain areas or at certain times, no civilian is allowed unless accompanied by an officer of the Correctional Service of Canada. Private vehicles will not be allowed within the institution's security wall or fence without special permission of the Warden or his designate. All vehicles entering the institution's security wall or fence must comply with institution's security requirements (ie. lockable gas caps or wheel covers, no wheel hub caps, lockable doors and windows, tools in a lockable container and locked when not in use). Trucks delivering materials, equipment and tools to the job will be allowed access when the contents are certified by the contractor or his representative as being strictly necessary for the execution of the work. Security requirements such as wheel covers, lockable fuel caps, lockable doors and windows are still required unless special provisions are made thru the CS I/C Construction. Trucks or vehicles, after being unloaded, are to be parked in the designated area outside the security wall or fence. All vehicles are subject to search and will be refused access if, in the opinion of the Warden or his designate, they contain any article that may jeopardize the security of the institution. Examples: weapons, alcohol, cell phones, drugs or narcotics.

.3 Tools and Equipment:

- .1 Commissioner's Directive 573 Control of Items Critical to the Security & Safety of the Institution under section 10 and Institutional Standing Order 573: The contractor shall maintain an inventory of all tools and equipment, including the number of cartridges for power-driven tools brought on site, and a record of every shot fired. (Empty cartridges to taken out after completion of work and counted with live cartridges. Total cartridges taken in must add up to those taken out, counting those that have been fired.) A copy of these tool lists shall be kept in the Security Construction Trailer when manned or with the officer in charge of the service entrance. The contractor shall keep all tools and equipment under constant supervision and not leave them unattended, paying particular attention to power-driven tools, files, saw blades, rod saw, wire, rope, extension cords and ladders. The contractor shall store all tools and equipment in places and under conditions approved by the Warden or his designate and locks all toolboxes when not in use. He shall report immediately all missing or lost tools or equipment to the Warden or his designate and complete Missing Tool Report form. This form is available to the General Contractor. The contractor shall provide permanent identification (engraving) to all tools indicating that they are the personal property of the employee/tradesperson or employing company. Negligence in this regard may result in confiscation of tools.

.4 Telephones and Installations:

- .1 The contractor shall obtain approval from the Warden or his designate for the installation of telephones that shall be located so that they are not accessible to inmates. Cell phones are NOT allowed inside the security wall or fence.

.5 Two-Way Radio Communications:

- .1 The Warden or his designate must approve all two-way radio communication devices. All radio devices requested for use on job site must be checked with institutional ADGA technicians to ensure no

interference with institution equipment. All radio devices brought into SMI are not to be accessible to inmates.

- .6 Alcohol and Narcotics:
 - .1 There is a Zero tolerance policy for alcohol beverages and narcotics on site. These items are not permitted on institutional property. Discovery of such items on site, and identification of the person or persons responsible for them, shall be reported immediately to the Warden or his designate. Any persons employed in the project that appear to be intoxicated or under the influence of any drug or narcotic, or who behaves in an unusual manner, shall be subject to immediate removal from institutional property.
- .7 Control of Contraband – General:
 - .1 The contractor is responsible for ensuring that all persons employed by him directly or indirectly upon the project are familiar with Correctional and Conditional Release Act section 45 Summary Convictions.
 - .2 CCRA Summary Conviction Offences:
 - .1 Every person commits a summary conviction offence who:
 - .1 is in possession of contraband beyond the visitor control point in a penitentiary;
 - .2 is in possession of anything referred to in paragraph (b) or (c) of the definition "contraband" in section 2 before the visitor control point at a penitentiary;
 - .3 delivers contraband to, or receives contraband from, an inmate;
 - .4 without prior authorization, delivers jewellery to, or receives jewellery from, an inmate; or
 - .2 Search: Where the Warden or his designate suspects, on reasonable grounds, that an employee of the contractor is in possession of contraband, he may order that person to be searched, under, Correctional Conditional Release Regulations Section 42.1 Contraband, Sections 43-46, 54.1-2, 55.1 Search and Seizure and Section 57 Seizure, Commissioner's Directives 566-8 section 9-16.
- .8 Key Control:
 - .1 Commissioner's Directive 573 Control of Items Critical to the Security & Safety of the Institution under section 3 C & E and Institutional Standing Order 573 The general contractor shall maintain control of all new keys as follows:
 - .1 Upon receipt of keys from the security hardware supplier / installer; provide a receipt to the security hardware supplier, listing all keys and quantity of each, by key code.
 - .1 Provide a copy of the receipt to the appropriate Correctional Service of Canada representative at the site.
 - .2 Locks are to be handed over to SMO Officer for the purpose of repining of lock to CSC standards. Once locks have been repined, locks will be returned to General Contractor for installation.

- .3 Keys for locks will be made available to the Security Construction Gate to maintain CSC regulation control.
- .2 Upon putting operational keys to use:
 - .1 Keys will be issued thru the Security personnel as per CSC standards and to ensure that keys are issued to responsible personnel only and the keys are turned in at the end of the days work. No keys are to be retained by an employee for any period longer than that for which the key is required.
 - .2 The issue and receipt of all keys is recorded, showing the date, time, key code number, issued to, including the name of the recipient and employer. The time of return should be signed in by the key control officer (Gate Security) and witnessed by CSC site representative at the end of each working day.
 - .3 Report, in writing, any untoward circumstances, such as loss, disfigurement, misuse, or mishandling, etc., to the security hardware supplier or CSC/SMO, identifying keys by code and/or number, so that appropriate action may be taken to effect replacement or abandonment of that particular code as circumstances may warrant. Send a copy of these reports to the CSC site representative.
 - .4 Misuse or improper control of CSC keys can result in that employee being denied access to keys or removal from CSC property.
 - .5 No inmates are allowed to handle or be given access to CSC keys.
- .3 Upon completion of the contract and takeover of the buildings:
 - .1 Provide a list of all keys, by number and/or key code, with space for the signature of recipients (both Public Works & Government Services Canada representative and CSC representative) and the date of receipt.
 - .2 Provide certification to Public Works & Government Services Canada that all reasonable caution and care has been exercised in accordance with these instructions, and include a copy for CSC.
- .4 Once locks have been installed on new installation, all keys pertaining to that lock and code shall immediately be turned over to the CSC/SMO. All locks removed during demolition must immediately be turned over to CSC/SMO.
- .9 Work Areas:
 - .1 The contractors and their employees shall be confined to their work area. All other buildings and grounds shall be considered "Out of Bounds". The contractors and their employees shall not contact or attempt to contact or deal in any way with inmates.
- .10 Confined Space Entry:
 - .1 Confined Space Entry Regulations are now in effect. Personnel entering confined space areas must have passed the required Confined Space Training Course to enter Class "A" or "B" areas.

- .2 Institution:
 - .1 Confined Spaces Area "A" are typically areas below grade within the duct areas of the Institution. Confined Space Area "A" requires the issue of a permit from the SMI Works Department prior to entry of area or issue of keys. This includes all necessary equipment and safety personnel.
 - .2 Confined Spaces Area "B" are all areas above grade within a confined space area such as attics, mechanical rooms and ducts. This does not require a permit from Works Department, but does require that you sign a waiver form. This form is for you to indicate that you have had the Confined Space Training. To enter Confined Spaces you are required to have all necessary equipment. The waiver form must be completed prior to entry or before the issuance of any keys.

1.5 BUILDING SMOKING ENVIRONMENT

- .1 Comply with smoking restrictions. Smoking is not allowed.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 ADMINISTRATIVE

- .1 Schedule and administer project meetings throughout the progress of the work at the call of Departmental Representative.
- .2 Prepare agenda for meetings.
- .3 Distribute written notice of each meeting four days in advance of meeting date to Departmental Representative.
- .4 Provide physical space and make arrangements for meetings.
- .5 Preside at meetings.
- .6 Record the meeting minutes. Include significant proceedings and decisions. Identify actions by parties.
- .7 Reproduce and distribute copies of minutes within three days after meetings and transmit to meeting participants, Departmental Representative and affected parties not in attendance.
- .8 Representative of Contractor, Subcontractor and suppliers attending meetings will be qualified and authorized to act on behalf of party each represents.

1.2 PRECONSTRUCTION MEETING

- .1 Within 15 days after award of Contract, request a meeting of parties in contract to discuss and resolve administrative procedures and responsibilities.
- .2 Departmental Representative, Contractor and major Subcontractors will be in attendance.
- .3 Establish time and location of meeting and notify parties concerned minimum 5 days before meeting.
- .4 Incorporate mutually agreed variations to Contract Documents into Agreement, prior to signing.
- .5 Agenda to include:
 - .1 Appointment of official representative of participants in the Work.
 - .2 Schedule of Work: in accordance with Section 01 32 16 - Construction Progress Schedules - Bar (GANTT) Chart.
 - .3 Schedule of submission of shop drawings, samples, colour chips. Submit submittals in accordance with Section 01 33 00 - Submittal Procedures.
 - .4 Delivery schedule of specified equipment.
 - .5 Site security in accordance with Section 01 56 00 - Temporary Barriers and Enclosures.
 - .6 Proposed changes, change orders, procedures, approvals required, mark-up percentages permitted, time extensions, overtime, administrative requirements.
 - .7 Record drawings in accordance with Section 01 33 00 - Submittal Procedures.
 - .8 Maintenance manuals in accordance with Section 01 78 00 - Closeout Submittals.

- .9 Take-over procedures, acceptance, warranties in accordance with Section 01 78 00 - Closeout Submittals.
- .10 Monthly progress claims, administrative procedures, photographs, hold backs.
- .11 Appointment of inspection and testing agencies or firms.
- .12 Insurances, transcript of policies.

1.3 PROGRESS MEETINGS

- .1 During course of Work and monthly
- .2 Contractor, major Subcontractors involved in Work, and Departmental Representative are to be in attendance.
- .3 Notify parties minimum five (5) days before meeting.
- .4 Record minutes of meetings and circulate to attending parties and affected parties not in attendance within three (3).
- .5 Agenda to include the following:
 - .1 Review, approval of minutes of previous meeting.
 - .2 Review of Work progress since previous meeting.
 - .3 Field observations, problems, conflicts.
 - .4 Problems which impede construction schedule.
 - .5 Review of off-site fabrication delivery schedules.
 - .6 Corrective measures and procedures to regain projected schedule.
 - .7 Revision to construction schedule.
 - .8 Progress schedule, during succeeding work period.
 - .9 Review submittal schedules: expedite as required.
 - .10 Maintenance of quality standards.
 - .11 Review proposed changes for affect on construction schedule and on completion date.
 - .12 Other business.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 DEFINITIONS

- .1 Activity: element of Work performed during course of Project. Activity normally has expected duration, and expected cost and expected resource requirements. Activities can be subdivided into tasks.
- .2 Bar Chart (GANTT Chart): graphic display of schedule-related information. In typical bar chart, activities or other Project elements are listed down left side of chart, dates are shown across top, and activity durations are shown as date-placed horizontal bars. Generally, Bar Chart should be derived from commercially available computerized project management system.
- .3 Baseline: original approved plan (for project, work package, or activity), plus or minus approved scope changes.
- .4 Construction Work Week: Monday to Friday, inclusive, will provide five-day work week and define schedule calendar working days as part of Bar (GANTT) Chart submission.
- .5 Duration: number of work periods (not including holidays or other nonworking periods) required to complete activity or other project element. Usually expressed as workdays or workweeks.
- .6 Master Plan: summary-level schedule that identifies major activities and key milestones.
- .7 Milestone: significant event in project, usually completion of major deliverable.
- .8 Project Schedule: planned dates for performing activities and the planned dates for meeting milestones. Dynamic, detailed record of tasks or activities that must be accomplished to satisfy Project objectives. Monitoring and control process involves using Project Schedule in executing and controlling activities and is used as basis for decision making throughout project life cycle.
- .9 Project Planning, Monitoring and Control System: overall system operated by Departmental Representative to enable monitoring of project work in relation to established milestones.

1.2 REQUIREMENTS

- .1 Ensure Master Plan and Detail Schedules are practical and remain within specified Contract duration.
- .2 Plan to complete Work in accordance with prescribed milestones and time frame.
- .3 Limit activity durations to maximum of approximately 10 working days, to allow for progress reporting.
- .4 Ensure that it is understood that Award of Contract or time of beginning, rate of progress, Interim Certificate and Final Certificate as defined times of completion are of essence of this contract.

1.3 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit Project Schedule to Departmental Representative within 5 working days of receipt of acceptance of Master Plan.

1.4 MASTER PLAN

- .1 Structure schedule to allow orderly planning, organizing and execution of Work as Bar Chart (GANTT).
- .2 Departmental Representative will review and return revised schedules within 5 working days.
- .3 Revise impractical schedule and resubmit within 5 working days.
- .4 Accepted revised schedule will become Master Plan and be used as baseline for updates.

1.5 PROJECT SCHEDULE

- .1 Develop detailed Project Schedule derived from Master Plan.
- .2 Ensure detailed Project Schedule includes as minimum milestone and activity types as follows:
 - .1 Award.
 - .2 Shop Drawings, Samples.
 - .3 Permits.
 - .4 Mobilization.
 - .5 Excavation.
 - .6 Backfill.
 - .7 Plumbing.
 - .8 Piping.
 - .9 Testing and Commissioning.

1.6 PROJECT SCHEDULE REPORTING

- .1 Update Project Schedule on weekly basis reflecting activity changes and completions, as well as activities in progress.
- .2 Include as part of Project Schedule, narrative report identifying Work status to date, comparing current progress to baseline, presenting current forecasts, defining problem areas, anticipated delays and impact with possible mitigation.

1.7 PROJECT MEETINGS

- .1 Discuss Project Schedule at regular site meetings, identify activities that are behind schedule and provide measures to regain slippage. Activities considered behind schedule are those with projected start or completion dates later than current approved dates shown on baseline schedule.
- .2 Weather related delays with their remedial measures will be discussed and negotiated.

Part 2 Products

2.1 NOT USED

.1 Not used.

Part 3 Execution

3.1 NOT USED

.1 Not used.

END OF SECTION

Part 1 General

1.1 ADMINISTRATIVE

- .1 Submit to Departmental Representative submittals listed for review. Submit promptly and in orderly sequence to not cause delay in Work. Failure to submit in ample time is not considered sufficient reason for extension of Contract Time and no claim for extension by reason of such default will be allowed.
- .2 Do not proceed with Work affected by submittal until review is complete.
- .3 Present shop drawings, product data, samples and mock-ups in SI Metric units.
- .4 Where items or information is not produced in SI Metric units converted values are acceptable.
- .5 Review submittals prior to submission to Departmental Representative. This review represents that necessary requirements have been determined and verified, or will be, and that each submittal has been checked and co-ordinated with requirements of Work and Contract Documents. Submittals not stamped, signed, dated and identified as to specific project will be returned without being examined and considered rejected.
- .6 Notify Departmental Representative, in writing at time of submission, identifying deviations from requirements of Contract Documents stating reasons for deviations.
- .7 Verify field measurements and affected adjacent Work are co-ordinated.
- .8 Contractor's responsibility for errors and omissions in submission is not relieved by Departmental Representative's review of submittals.
- .9 Contractor's responsibility for deviations in submission from requirements of Contract Documents is not relieved by Departmental Representative review.
- .10 Keep one reviewed copy of each submission on site.

1.2 SHOP DRAWINGS AND PRODUCT DATA

- .1 The term "shop drawings" means drawings, diagrams, illustrations, schedules, performance charts, brochures and other data which are to be provided by Contractor to illustrate details of a portion of Work.
- .2 Indicate materials, methods of construction and attachment or anchorage, erection diagrams, connections, explanatory notes and other information necessary for completion of Work. Where articles or equipment attach or connect to other articles or equipment, indicate that such items have been co-ordinated, regardless of Section under which adjacent items will be supplied and installed. Indicate cross references to design drawings and specifications.
- .3 Allow ten days for Departmental Representative's review of each submission.
- .4 Adjustments made on shop drawings by Departmental Representative are not intended to change Contract Price. If adjustments affect value of Work, state such in writing to Departmental Representative prior to proceeding with Work.

- .5 Make changes in shop drawings as Departmental Representative may require, consistent with Contract Documents. When resubmitting, notify Departmental Representative in writing of revisions other than those requested.
- .6 Accompany submissions with transmittal letter, in duplicate, containing:
 - .1 Date.
 - .2 Project title and number.
 - .3 Contractor's name and address.
 - .4 Identification and quantity of each shop drawing, product data and sample.
 - .5 Other pertinent data.
- .7 Submissions include:
 - .1 Date and revision dates.
 - .2 Project title and number.
 - .3 Name and address of:
 - .1 Subcontractor.
 - .2 Supplier.
 - .3 Manufacturer.
 - .4 Contractor's stamp, signed by Contractor's authorized representative certifying approval of submissions, verification of field measurements and compliance with Contract Documents.
 - .5 Details of appropriate portions of Work as applicable:
 - .1 Fabrication.
 - .2 Layout, showing dimensions, including identified field dimensions, and clearances.
 - .3 Setting or erection details.
 - .4 Capacities.
 - .5 Performance characteristics.
 - .6 Standards.
 - .7 Operating weight.
 - .8 Wiring diagrams.
 - .9 Single line and schematic diagrams.
 - .10 Relationship to adjacent work.
- .8 After Departmental Representative's review, distribute copies.
- .9 Submit one transparency on plastic film electronic copy of shop drawings for each requirement requested in specification Sections and as Departmental Representative may reasonably request.
- .10 Submit electronic copies of product data sheets or brochures for requirements requested in specification Sections and as requested by Departmental Representative where shop drawings will not be prepared due to standardized manufacture of product.
- .11 Submit electronic copies of test reports for requirements requested in specification Sections and as requested by Departmental Representative.

- .1 Report signed by authorized official of testing laboratory that material, product or system identical to material, product or system to be provided has been tested in accord with specified requirements.
 - .2 Testing must have been within 3 years of date of contract award for project.
- .12 Submit electronic copy of certificates for requirements requested in specification Sections and as requested by Departmental Representative.
 - .1 Statements printed on manufacturer's letterhead and signed by responsible officials of manufacturer of product, system or material attesting that product, system or material meets specification requirements.
 - .2 Certificates must be dated after award of project contract complete with project name.
- .13 Submit electronic copy of manufacturer's instructions for requirements requested in specification Sections and as requested by Departmental Representative.
 - .1 Pre-printed material describing installation of product, system or material, including special notices and Material Safety Data Sheets concerning impedances, hazards and safety precautions.
- .14 Submit electronic copy of Manufacturer's Field Reports for requirements requested in specification Sections and as requested by Departmental Representative.
- .15 Documentation of the testing and verification actions taken by manufacturer's representative to confirm compliance with manufacturer's standards or instructions.
- .16 Submit 4 electronic copies of Operation and Maintenance Data for requirements requested in specification Sections and as requested by Departmental Representative.
- .17 Delete information not applicable to project.
- .18 Supplement standard information to provide details applicable to project.
- .19 If upon review by Departmental Representative, no errors or omissions are discovered or if only minor corrections are made, copies will be returned and fabrication and installation of Work may proceed. If shop drawings are rejected, noted copy will be returned and resubmission of corrected shop drawings, through same procedure indicated above, must be performed before fabrication and installation of Work may proceed.
- .20 The review of shop drawings by Departmental Representative is for sole purpose of ascertaining conformance with general concept.
 - .1 This review shall not mean that Departmental Representative approves detail design inherent in shop drawings, responsibility for which shall remain with Contractor submitting same, and such review shall not relieve Contractor of responsibility for errors or omissions in shop drawings or of responsibility for meeting requirements of construction and Contract Documents.
 - .2 Without restricting generality of foregoing, Contractor is responsible for dimensions to be confirmed and correlated at job site, for information that pertains solely to fabrication processes or to techniques of construction and installation and for co-ordination of Work of sub-trades.

1.3 SAMPLES

- .1 Submit for review samples as requested in respective specification Sections. Label samples with origin and intended use.
- .2 Deliver samples prepaid to Departmental Representative's business address.
- .3 Notify Departmental Representative in writing, at time of submission of deviations in samples from requirements of Contract Documents.
- .4 Where colour, pattern or texture is criterion, submit full range of samples.
- .5 Adjustments made on samples by Departmental Representative are not intended to change Contract Price. If adjustments affect value of Work, state such in writing to Departmental Representative prior to proceeding with Work.
- .6 Make changes in samples which Departmental Representative may require, consistent with Contract Documents.
- .7 Reviewed and accepted samples will become standard of workmanship and material against which installed Work will be verified.

1.4 CERTIFICATES AND TRANSCRIPTS

- .1 Immediately after award of Contract, submit Workers' Compensation Board status.
- .2 Submit transcription of insurance immediately after award of Contract.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 PRECEDENCE

- .1 For Federal Government projects, Division 1 Sections take precedence over technical specification sections in other Divisions of this Project Manual.

1.2 REFERENCES

- .1 Canada Labour Code, Part 2, Canada Occupational Safety and Health Regulations.
- .2 Health Canada/Workplace Hazardous Materials Information System (WHMIS).
 - .1 Material Safety Data Sheets (MSDS).
- .3 Province of Saskatchewan
 - .1 Occupational Health and Safety Act, 1996.

1.3 SUBMITTALS

- .1 Make submittals in accordance with Section 01 33 00 - Submittal Procedures
- .2 Submit site-specific Health and Safety Plan: Within 14 days after date of Notice to Proceed and prior to commencement of Work. Health and Safety Plan must include:
 - .1 Results of site specific safety hazard assessment.
 - .2 Results of safety and health risk or hazard analysis for site tasks and operation.
- .3 Submit copies of Contractor's authorized representative's work site health and safety inspection reports to Departmental Representative and authority having jurisdiction, monthly.
- .4 Submit copies of reports or directions issued by Federal, Provincial and Territorial health and safety inspectors.
- .5 Submit copies of incident and accident reports.
- .6 Departmental Representative will review Contractor's site-specific Health and Safety Plan and provide comments to Contractor within 14 days after receipt of plan. Revise plan as appropriate and resubmit plan to Departmental Representative within 5 days after receipt of comments from Departmental Representative.
- .7 Departmental Representative's review of Contractor's final Health and Safety plan should not be construed as approval and does not reduce the Contractor's overall responsibility for construction Health and Safety.
- .8 Medical Surveillance: where prescribed by legislation, regulation or safety program, submit certification of medical surveillance for site personnel prior to commencement of Work, and submit additional certifications for any new site personnel to Departmental Representative.

- .9 On-site Contingency and Emergency Response Plan: address standard operating procedures to be implemented during emergency situations.

1.4 FILING OF NOTICE

- .1 File Notice of Project with Provincial authorities prior to beginning of Work.

1.5 SAFETY ASSESSMENT

- .1 Perform site specific safety hazard assessment related to project.

1.6 MEETINGS

- .1 Schedule and administer Health and Safety meeting with Departmental Representative prior to commencement of Work.

1.7 REGULATORY REQUIREMENTS

- .1 Do Work in accordance with Section 01 14 00 – Work Restrictions.

1.8 GENERAL REQUIREMENTS

- .1 Develop written site-specific Health and Safety Plan based on hazard assessment prior to beginning site Work and continue to implement, maintain, and enforce plan until final demobilization from site. Health and Safety Plan must address project specifications.
- .2 Departmental Representative may respond in writing, where deficiencies or concerns are noted and may request re-submission with correction of deficiencies or concerns.

1.9 RESPONSIBILITY

- .1 Be responsible for health and safety of persons on site, safety of property on site and for protection of persons adjacent to site and environment to extent that they may be affected by conduct of Work.
- .2 Comply with and enforce compliance by employees with safety requirements of Contract Documents, applicable federal, provincial, territorial and local statutes, regulations, and ordinances, and with site-specific Health and Safety Plan.

1.10 UNFORSEEN HAZARDS

- .1 When unforeseen or peculiar safety-related factor, hazard, or condition occur during performance of Work, follow procedures in place for Employee's Right to Refuse Work in accordance with Acts and Regulations of Province having jurisdiction and advise Departmental Representative verbally and in writing.

1.11 HEALTH AND SAFETY CO-ORDINATOR

- .1 Employ and assign to Work, competent and authorized representative as Health and Safety Co-ordinator. Health and Safety Co-ordinator must:
 - .1 Have working knowledge of occupational safety and health regulations.

- .2 Be responsible for completing Contractor's Health and Safety Training Sessions and ensuring that personnel not successfully completing required training are not permitted to enter site to perform Work.
- .3 Be responsible for implementing, enforcing daily and monitoring site-specific Contractor's Health and Safety Plan.
- .4 Be on site during execution of Work and report directly to and be under direction of site supervisor.

1.12 POSTING OF DOCUMENTS

- .1 Ensure applicable items, articles, notices and orders are posted in conspicuous location on site in accordance with Acts and Regulations of Province having jurisdiction, and in consultation with Departmental Representative.

1.13 CORRECTION OF NON-COMPLIANCE

- .1 Immediately address health and safety non-compliance issues identified by authority having jurisdiction or by Departmental Representative.
- .2 Provide Departmental Representative with written report of action taken to correct non-compliance of health and safety issues identified.
- .3 Departmental Representative may stop Work if non-compliance of health and safety regulations is not corrected.

1.14 WORK STOPPAGE

- .1 Give precedence to safety and health of public and site personnel and protection of environment over cost and schedule considerations for Work.

Part 2 Products

2.1 NOT USED

- .1 Not used.

Part 3 Execution

3.1 NOT USED

- .1 Not used.

END OF SECTION

Part 1 General

1.1 INSPECTION

- .1 Allow Departmental Representative access to Work. If part of Work is in preparation at locations other than Place of Work, allow access to such Work whenever it is in progress.
- .2 Give timely notice requesting inspection if Work is designated for special tests, inspections or approvals by Departmental Representative instructions, or law of Place of Work.
- .3 If Contractor covers or permits to be covered Work that has been designated for special tests, inspections or approvals before such is made, uncover such Work, have inspections or tests satisfactorily completed and make good such Work.
- .4 Departmental Representative will order part of Work to be examined if Work is suspected to be not in accordance with Contract Documents. If, upon examination such work is found not in accordance with Contract Documents, correct such Work and pay cost of examination and correction. If such Work is found in accordance with Contract Documents, Departmental Representative shall pay cost of examination and replacement.

1.2 INDEPENDENT INSPECTION AGENCIES

- .1 Independent Inspection/Testing Agencies will be engaged by Departmental Representative for purpose of inspecting and/or testing portions of Work. Cost of such services will be borne by Departmental Representative.
- .2 Provide equipment required for executing inspection and testing by appointed agencies.
- .3 Employment of inspection/testing agencies does not relax responsibility to perform Work in accordance with Contract Documents.
- .4 If defects are revealed during inspection and/or testing, appointed agency will request additional inspection and/or testing to ascertain full degree of defect. Correct defect and irregularities as advised by Departmental Representative at no cost to Departmental Representative. Pay costs for retesting and re-inspection.

1.3 ACCESS TO WORK

- .1 Allow inspection/testing agencies access to Work, off site manufacturing and fabrication plants.
- .2 Co-operate to provide reasonable facilities for such access.

1.4 PROCEDURES

- .1 Notify appropriate agency and Departmental Representative in advance of requirement for tests, in order that attendance arrangements can be made.
- .2 Submit samples and/or materials required for testing, as specifically requested in specifications. Submit with reasonable promptness and in orderly sequence to not cause delays in Work.
- .3 Provide labour and facilities to obtain and handle samples and materials on site. Provide sufficient space to store and cure test samples.

1.5 REJECTED WORK

- .1 Remove defective Work, whether result of poor workmanship, use of defective products or damage and whether incorporated in Work or not, which has been rejected by Departmental Representative as failing to conform to Contract Documents. Replace or re-execute in accordance with Contract Documents.
- .2 Make good other Contractor's work damaged by such removals or replacements promptly.
- .3 If in opinion of Departmental Representative, it is not expedient to correct defective Work or Work not performed in accordance with Contract Documents, Owner will deduct from Contract Price difference in value between Work performed and that called for by Contract Documents, amount of which will be determined by.

1.6 REPORTS

- .1 Submit 4 copies of inspection and test reports to Departmental Representative.
- .2 Provide copies to subcontractor of work being inspected or tested.

1.7 TESTS AND MIX DESIGNS

- .1 Furnish test results and mix designs as requested.
- .2 Cost of tests and mix designs beyond those called for in Contract Documents or beyond those required by law of Place of Work will be appraised by Departmental Representative and may be authorized as recoverable.

1.8 MILL TESTS

- .1 Submit mill test certificates as required of specification Sections.

1.9 EQUIPMENT AND SYSTEMS

- .1 Submit adjustment and balancing reports for mechanical systems.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 INSTALLATION AND REMOVAL

- .1 Provide temporary controls in order to execute Work expeditiously.
- .2 Remove from site all such work after use.

1.2 HOARDING

- .1 Erect temporary site enclosures using 38 x 89 mm construction grade lumber framing at 600 mm centres and 1200 x 2400 x 13 mm exterior grade fir plywood to CSA O121.
- .2 Apply plywood panels vertically flush and butt jointed.
- .3 Provide one lockable pedestrian door. Equip doors with locks and keys.
- .4 Erect and maintain pedestrian walkways including roof and side covers, complete with signs and electrical lighting as required by law.
- .5 Provide barriers around trees and plants designated to remain. Protect from damage by equipment and construction procedures.

1.3 GUARD RAILS AND BARRICADES

- .1 Provide secure, rigid guard rails and barricades around deep excavations, open shafts, open stair wells, open edges of floors and roofs.
- .2 Provide as required by governing authorities.

1.4 WEATHER ENCLOSURES

- .1 Provide weather tight closures to unfinished door and window openings, tops of shafts and other openings in floors and roofs.
- .2 Close off floor areas where walls are not finished; seal off other openings; enclose building interior work for temporary heat.
- .3 Design enclosures to withstand wind pressure and snow loading.

1.5 DUST TIGHT SCREENS

- .1 Provide dust tight screens or insulated partitions to localize dust generating activities, and for protection of workers, finished areas of Work and public.
- .2 Maintain and relocate protection until such work is complete.

1.6 ACCESS TO SITE

- .1 Provide and maintain access roads, sidewalk crossings, ramps and construction runways as may be required for access to Work.

1.7 FIRE ROUTES

- .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

1.8 PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY

- .1 Protect surrounding private and public property from damage during performance of Work.
- .2 Be responsible for damage incurred.

1.9 PROTECTION OF BUILDING FINISHES

- .1 Provide protection for finished and partially finished building finishes and equipment during performance of Work.
- .2 Provide necessary screens, covers, and hoardings.
- .3 Be responsible for damage incurred due to lack of or improper protection.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 Within text of each specifications section, reference may be made to reference standards.
- .2 Conform to these reference standards, in whole or in part as specifically requested in specifications.
- .3 If there is question as to whether products or systems are in conformance with applicable standards, Departmental Representative reserves right to have such products or systems tested to prove or disprove conformance.
- .4 Cost for such testing will be borne by Departmental Representative in event of conformance with Contract Documents or by Contractor in event of non-conformance.

1.2 QUALITY

- .1 Products, materials, equipment and articles incorporated in Work shall be new, not damaged or defective, and of best quality for purpose intended. If requested, furnish evidence as to type, source and quality of products provided.
- .2 Procurement policy is to acquire, in cost effective manner, items containing highest percentage of recycled and recovered materials practicable consistent with maintaining satisfactory levels of competition. Make reasonable efforts to use recycled and recovered materials and in otherwise utilizing recycled and recovered materials in execution of work.
- .3 Defective products, whenever identified prior to completion of Work, will be rejected, regardless of previous inspections. Inspection does not relieve responsibility, but is precaution against oversight or error. Remove and replace defective products at own expense and be responsible for delays and expenses caused by rejection.
- .4 Should disputes arise as to quality or fitness of products, decision rests strictly with Departmental Representative based upon requirements of Contract Documents.
- .5 Unless otherwise indicated in specifications, maintain uniformity of manufacture for any particular or like item throughout building.
- .6 Permanent labels, trademarks and nameplates on products are not acceptable in prominent locations, except where required for operating instructions, or when located in mechanical or electrical rooms.

1.3 AVAILABILITY

- .1 Immediately upon signing Contract, review product delivery requirements and anticipate foreseeable supply delays for items. If delays in supply of products are foreseeable, notify Departmental Representative of such, in order that substitutions or other remedial action may be authorized in ample time to prevent delay in performance of Work.
- .2 In event of failure to notify Departmental Representative at commencement of Work and should it subsequently appear that Work may be delayed for such reason, Departmental Representative reserves right to substitute more readily available products of similar character, at no increase in Contract Price or Contract Time.

1.4 STORAGE, HANDLING AND PROTECTION

- .1 Handle and store products in manner to prevent damage, adulteration, deterioration and soiling and in accordance with manufacturer's instructions when applicable.
- .2 Store packaged or bundled products in original and undamaged condition with manufacturer's seal and labels intact. Do not remove from packaging or bundling until required in Work.
- .3 Store products subject to damage from weather in weatherproof enclosures.
- .4 Store cementitious products clear of earth or concrete floors, and away from walls.
- .5 Keep sand, when used for grout or mortar materials, clean and dry. Store sand on wooden platforms and cover with waterproof tarpaulins during inclement weather.
- .6 Store sheet materials, lumber on flat, solid supports and keep clear of ground. Slope to shed moisture.
- .7 Store and mix paints in heated and ventilated room. Remove oily rags and other combustible debris from site daily. Take every precaution necessary to prevent spontaneous combustion.
- .8 Remove and replace damaged products at own expense and to satisfaction of Departmental Representative.
- .9 Touch-up damaged factory finished surfaces to Departmental Representative's satisfaction. Use touch-up materials to match original. Do not paint over name plates.

1.5 TRANSPORTATION

- .1 Pay costs of transportation of products required in performance of Work.

1.6 MANUFACTURER'S INSTRUCTIONS

- .1 Unless otherwise indicated in specifications, install or erect products in accordance with manufacturer's instructions. Do not rely on labels or enclosures provided with products. Obtain written instructions directly from manufacturers.
- .2 Notify Departmental Representative in writing, of conflicts between specifications and manufacturer's instructions, so that Departmental Representative will establish course of action.
- .3 Improper installation or erection of products, due to failure in complying with these requirements, authorizes Departmental Representative to require removal and re-installation at no increase in Contract Price or Contract Time.

1.7 QUALITY OF WORK

- .1 Ensure Quality of Work is of highest standard, executed by workers experienced and skilled in respective duties for which they are employed. Immediately notify Departmental Representative if required Work is such as to make it impractical to produce required results.
- .2 Do not employ anyone unskilled in their required duties. Departmental Representative reserves right to require dismissal from site, workers deemed incompetent or careless.

- .3 Decisions as to standard or fitness of Quality of Work in cases of dispute rest solely with Departmental Representative, whose decision is final.

1.8 CO-ORDINATION

- .1 Ensure co-operation of workers in laying out Work. Maintain efficient and continuous supervision.
- .2 Be responsible for coordination and placement of openings, sleeves and accessories.

1.9 CONCEALMENT

- .1 In finished areas conceal pipes, ducts and wiring in floors, walls and ceilings, except where indicated otherwise.
- .2 Before installation inform Departmental Representative if there is interference. Install as directed by Departmental Representative.

1.10 REMEDIAL WORK

- .1 Refer to Section 01 73 00 - Execution Requirements.
- .2 Perform remedial work required to repair or replace parts or portions of Work identified as defective or unacceptable. Co-ordinate adjacent affected Work as required.
- .3 Perform remedial work by specialists familiar with materials affected. Perform in a manner to neither damage nor put at risk any portion of Work.

1.11 LOCATION OF FIXTURES

- .1 Consider location of fixtures, outlets, and mechanical and electrical items indicated as approximate.
- .2 Inform Departmental Representative of conflicting installation. Install as directed.

1.12 FASTENINGS

- .1 Provide metal fastenings and accessories in same texture, colour and finish as adjacent materials, unless indicated otherwise.
- .2 Prevent electrolytic action between dissimilar metals and materials.
- .3 Use non-corrosive hot dip galvanized steel fasteners and anchors for securing exterior work, unless stainless steel or other material is specifically requested in affected specification Section.
- .4 Space anchors within individual load limit or shear capacity and ensure they provide positive permanent anchorage. Wood, or any other organic material plugs are not acceptable.
- .5 Keep exposed fastenings to a minimum, space evenly and install neatly.
- .6 Fastenings which cause spalling or cracking of material to which anchorage is made are not acceptable.

1.13 FASTENINGS - EQUIPMENT

- .1 Use fastenings of standard commercial sizes and patterns with material and finish suitable for service.
- .2 Use heavy hexagon heads, semi-finished unless otherwise specified. Use No. 304 stainless steel for exterior areas.
- .3 Bolts may not project more than one diameter beyond nuts.
- .4 Use plain type washers on equipment, sheet metal and soft gasket lock type washers where vibrations occur. Use resilient washers with stainless steel.

1.14 PROTECTION OF WORK IN PROGRESS

- .1 Prevent overloading of parts of building. Do not cut, drill or sleeve load bearing structural member, unless specifically indicated without written approval of Departmental Representative.

1.15 EXISTING UTILITIES

- .1 When breaking into or connecting to existing services or utilities, execute Work at times directed by local governing authorities, with minimum of disturbance to Work, and/or building occupants and pedestrian and vehicular traffic.
- .2 Protect, relocate or maintain existing active services. When services are encountered, cap off in manner approved by authority having jurisdiction. Stake and record location of capped service.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 EXISTING SERVICES

- .1 Before commencing work, establish location and extent of service lines in area of Work and notify Departmental Representative of findings.
- .2 Remove abandoned service lines within 2m of structures. Cap or otherwise seal lines at cut-off points as directed by Departmental Representative.

1.2 LOCATION OF EQUIPMENT AND FIXTURES

- .1 Location of equipment, fixtures and outlets indicated or specified are to be considered as approximate.
- .2 Locate equipment, fixtures and distribution systems to provide minimum interference and maximum usable space and in accordance with manufacturer's recommendations for safety, access and maintenance.
- .3 Inform Departmental Representative of impending installation and obtain approval for actual location.
- .4 Submit field drawings to indicate relative position of various services and equipment when required by Departmental Representative.

1.3 RECORDS

- .1 Maintain a complete, accurate log of control and survey work as it progresses.
- .2 On completion of foundations and major site improvements, prepare a certified survey showing dimensions, locations, angles and elevations of Work.
- .3 Record locations of maintained, re-routed and abandoned service lines.

1.4 ACTION AND INFORMATIONAL SUBMITTALS

- .1 On request of Departmental Representative, submit documentation to verify accuracy of field engineering work.
- .2 Submit certificate signed by surveyor certifying and noting those elevations and locations of completed Work that conform and do not conform with Contract Documents.

1.5 SUBSURFACE CONDITIONS

- .1 Promptly notify Departmental Representative in writing if subsurface conditions at Place of Work differ materially from those indicated in Contract Documents, or a reasonable assumption of probable conditions based thereon.
- .2 After prompt investigation, should Departmental Representative determine that conditions do differ materially, instructions will be issued for changes in Work as provided in Changes and Change Orders.

Part 2 Products

2.1 NOT USED

.1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

END OF SECTION

Part 1 General

1.1 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit written request in advance of cutting or alteration which affects:
 - .1 Structural integrity of elements of project.
 - .2 Integrity of weather-exposed or moisture-resistant elements.
 - .3 Efficiency, maintenance, or safety of operational elements.
 - .4 Visual qualities of sight-exposed elements.
- .3 Include in request:
 - .1 Identification of project.
 - .2 Location and description of affected Work.
 - .3 Statement on necessity for cutting or alteration.
 - .4 Description of proposed Work, and products to be used.
 - .5 Alternatives to cutting and patching.
 - .6 Date and time work will be executed.

1.2 MATERIALS

- .1 Required for original installation.
- .2 Change in Materials: Submit request for substitution in accordance with Section 01 33 00 - Submittal Procedures.

1.3 PREPARATION

- .1 Inspect existing conditions, including elements subject to damage or movement during cutting and patching.
- .2 After uncovering, inspect conditions affecting performance of Work.
- .3 Beginning of cutting or patching means acceptance of existing conditions.
- .4 Provide supports to assure structural integrity of surroundings; provide devices and methods to protect other portions of project from damage.
- .5 Provide protection from elements for areas which are to be exposed by uncovering work; maintain excavations free of water.

1.4 EXECUTION

- .1 Execute cutting, fitting, and patching including excavation and fill, to complete Work.
- .2 Fit several parts together, to integrate with other Work.
- .3 Uncover Work to install ill-timed Work.
- .4 Remove and replace defective and non-conforming Work.
- .5 Remove samples of installed Work for testing.

- .6 Provide openings in non-structural elements of Work for penetrations of mechanical and electrical Work.
- .7 Execute Work by methods to avoid damage to other Work, and which will provide proper surfaces to receive patching and finishing.
- .8 Employ original installer to perform cutting and patching for weather-exposed and moisture-resistant elements, and sight-exposed surfaces.
- .9 Cut rigid materials using masonry saw or core drill. Pneumatic or impact tools not allowed on masonry work without prior approval.
- .10 Restore work with new products in accordance with requirements of Contract Documents.
- .11 Fit Work airtight to pipes, sleeves, ducts, conduit, and other penetrations through surfaces.
- .12 At penetration of fire rated wall, ceiling, or floor construction, completely seal voids with firestopping material.
- .13 Refinish surfaces to match adjacent finishes: Refinish continuous surfaces to nearest intersection. Refinish assemblies by refinishing entire unit.
- .14 Conceal pipes, ducts and wiring in floor, wall and ceiling construction of finished areas except where indicated otherwise.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 REFERENCES

- .1 Public Works Government Services Canada (PWGSC) Standard Acquisition Clauses and Conditions (SACC)-ID: R0202D, Title: General Conditions "C", In Effect as of: May 14, 2004.

1.2 PROJECT CLEANLINESS

- .1 Maintain Work in tidy condition, free from accumulation of waste products and debris, other than that caused by Owner or other Contractors.
- .2 Remove waste materials from site at daily regularly scheduled times or dispose of as directed by Departmental Representative. Do not burn waste materials on site, unless approved by Departmental Representative.
- .3 Clear snow and ice from access to building, bank/pile snow in designated areas only.
- .4 Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .5 Provide on-site containers for collection of waste materials and debris.
- .6 Dispose of waste materials and debris off site.
- .7 Clean interior areas prior to start of finishing work, and maintain areas free of dust and other contaminants during finishing operations.
- .8 Store volatile waste in covered metal containers, and remove from premises at end of each working day.
- .9 Provide adequate ventilation during use of volatile or noxious substances. Use of building ventilation systems is not permitted for this purpose.
- .10 Use only cleaning materials recommended by manufacturer of surface to be cleaned, and as recommended by cleaning material manufacturer.
- .11 Schedule cleaning operations so that resulting dust, debris and other contaminants will not fall on wet, newly painted surfaces nor contaminate building systems.

1.3 FINAL CLEANING

- .1 When Work is Substantially Performed remove surplus products, tools, construction machinery and equipment not required for performance of remaining Work.
- .2 Remove waste products and debris other than that caused by others, and leave Work clean and suitable for occupancy.
- .3 Prior to final review remove surplus products, tools, construction machinery and equipment.
- .4 Remove waste products and debris other than that caused by Owner or other Contractors.
- .5 Remove waste materials from site at regularly scheduled times or dispose of as directed by Departmental Representative. Do not burn waste materials on site, unless approved by Departmental Representative.

- .6 Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .7 Clean and polish glass, mirrors, hardware, wall tile, stainless steel, chrome, porcelain enamel, baked enamel, plastic laminate, and mechanical and electrical fixtures. Replace broken, scratched or disfigured glass.
- .8 Remove stains, spots, marks and dirt from decorative work, electrical and mechanical fixtures, furniture fitments, walls, floors.
- .9 Clean lighting reflectors, lenses, and other lighting surfaces.
- .10 Vacuum clean and dust building interiors, behind grilles, louvres and screens.
- .11 Inspect finishes, fitments and equipment and ensure specified workmanship and operation.
- .12 Broom clean and wash exterior walks, steps and surfaces; rake clean other surfaces of grounds.
- .13 Remove dirt and other disfiguration from exterior surfaces.
- .14 Clean and sweep roofs, gutters, areaways, and sunken wells.
- .15 Sweep and wash clean paved areas.
- .16 Clean equipment and fixtures to sanitary condition; clean or replace filters of mechanical equipment.
- .17 Clean roofs, downspouts, and drainage systems.
- .18 Remove debris and surplus materials from crawl areas and other accessible concealed spaces.
- .19 Remove snow and ice from access to building.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 ADMINISTRATIVE REQUIREMENTS

- .1 Acceptance of Work Procedures:
 - .1 Contractor's Inspection: Contractor: conduct inspection of Work, identify deficiencies and defects, and repair as required to conform to Contract Documents.
 - .1 Notify Departmental Representative in writing of satisfactory completion of Contractor's inspection and submit verification that corrections have been made.
 - .2 Request Departmental Representative inspection.
 - .2 Departmental Representative Inspection:
 - .1 Departmental Representative and Contractor to inspect Work and identify defects and deficiencies.
 - .2 Contractor to correct Work as directed.
 - .3 Completion Tasks: submit written certificates in English that tasks have been performed as follows:
 - .1 Work: completed and inspected for compliance with Contract Documents.
 - .2 Defects: corrected and deficiencies completed.
 - .3 Equipment and systems: tested, adjusted, balanced and fully operational.
 - .4 Certificates required by Fire Commissioner, Utility companies: submitted.
 - .5 Operation of systems: demonstrated to Owner's personnel.
 - .6 Commissioning of mechanical systems: completed in accordance with 01 91 13 - General Commissioning (Cx) Requirements and 4 copies of final Commissioning Report submitted to Departmental Representative.
 - .7 Work: complete and ready for final inspection.
 - .4 Final Inspection:
 - .1 When completion tasks are done, request final inspection of Work by Departmental Representative, and Contractor.
 - .2 When Work incomplete according to Departmental Representative, complete outstanding items and request re-inspection.
 - .5 Declaration of Substantial Performance: when Departmental Representative considers deficiencies and defects corrected and requirements of Contract substantially performed, make application for Certificate of Substantial Performance.
 - .6 Commencement of Lien and Warranty Periods: date of Owner's acceptance of submitted declaration of Substantial Performance to be date for commencement for warranty period and commencement of lien period unless required otherwise by lien statute of Place of Work.
 - .7 Final Payment:

- .1 When Departmental Representative considers final deficiencies and defects corrected and requirements of Contract met, make application for final payment.
- .2 When Work deemed incomplete by Departmental Representative, complete outstanding items and request re-inspection.
- .8 Payment of Holdback: after issuance of Certificate of Substantial Performance of Work, submit application for payment of holdback amount in accordance with contractual agreement.

1.2 FINAL CLEANING

- .1 Clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 ADMINISTRATIVE REQUIREMENTS

- .1 Pre-warranty Meeting:
 - .1 Convene meeting one week prior to contract completion with contractor's representative and Departmental Representative, in accordance with Section 01 31 19 - Project Meetings to:
 - .1 Verify Project requirements.
 - .2 Review warranty requirements.
 - .2 Departmental Representative to establish communication procedures for:
 - .1 Notifying construction warranty defects.
 - .2 Determine priorities for type of defects.
 - .3 Determine reasonable response time.
 - .3 Contact information for bonded and licensed company for warranty work action: provide name, telephone number and address of company authorized for construction warranty work action.
 - .4 Ensure contact is located within local service area of warranted construction, is continuously available, and is responsive to inquiries for warranty work action.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Prior to Substantial Performance of the Work, submit to the Departmental Representative, four final copies of operating and maintenance manuals in English.
- .3 Provide spare parts, maintenance materials and special tools of same quality and manufacture as products provided in Work.
- .4 Provide evidence, if requested, for type, source and quality of products supplied.

1.3 FORMAT

- .1 Organize data as instructional manual.
- .2 Binders: vinyl, hard covered, 3 'D' ring, loose leaf 219 x 279 mm with spine and face pockets.
- .3 When multiple binders are used correlate data into related consistent groupings.
 - .1 Identify contents of each binder on spine.
- .4 Cover: identify each binder with type or printed title 'Project Record Documents'; list title of project and identify subject matter of contents.
- .5 Arrange content by systems, under Section numbers and sequence of Table of Contents.
- .6 Provide tabbed fly leaf for each separate product and system, with typed description of product and major component parts of equipment.
- .7 Text: manufacturer's printed data, or typewritten data.

- .8 Drawings: provide with reinforced punched binder tab.
 - .1 Bind in with text; fold larger drawings to size of text pages.
- .9 Provide 1:1 scaled CAD files in dwg format on CD.

1.4 CONTENTS - PROJECT RECORD DOCUMENTS

- .1 Table of Contents for Each Volume: provide title of project;
 - .1 Date of submission; names.
 - .2 Addresses, and telephone numbers of Consultant and Contractor with name of responsible parties.
 - .3 Schedule of products and systems, indexed to content of volume.
- .2 For each product or system:
 - .1 List names, addresses and telephone numbers of subcontractors and suppliers, including local source of supplies and replacement parts.
- .3 Product Data: mark each sheet to identify specific products and component parts, and data applicable to installation; delete inapplicable information.
- .4 Drawings: supplement product data to illustrate relations of component parts of equipment and systems, to show control and flow diagrams.
- .5 Typewritten Text: as required to supplement product data.
 - .1 Provide logical sequence of instructions for each procedure, incorporating manufacturer's instructions specified in Section 01 45 00 - Quality Control.
- .6 Training: refer to Section 01 79 00 - Demonstration and Training.

1.5 AS -BUILT DOCUMENTS AND SAMPLES

- .1 Maintain, in addition to requirements in General Conditions, at site for Departmental Representative one record copy of:
 - .1 Contract Drawings.
 - .2 Specifications.
 - .3 Addenda.
 - .4 Change Orders and other modifications to Contract.
 - .5 Reviewed shop drawings, product data, and samples.
 - .6 Field test records.
 - .7 Inspection certificates.
 - .8 Manufacturer's certificates.
- .2 Store record documents and samples in field office apart from documents used for construction.
 - .1 Provide files, racks, and secure storage.
- .3 Label record documents and file in accordance with Section number listings in List of Contents of this Project Manual.
 - .1 Label each document "PROJECT RECORD" in neat, large, printed letters.

- .4 Maintain record documents in clean, dry and legible condition.
 - .1 Do not use record documents for construction purposes.
- .5 Keep record documents and samples available for inspection by Departmental Representative.

1.6 RECORDING INFORMATION ON PROJECT RECORD DOCUMENTS

- .1 Record information on set of black line opaque drawings, provided by Departmental Representative.
- .2 Use felt tip marking pens, maintaining separate colours for each major system, for recording information.
- .3 Record information concurrently with construction progress.
 - .1 Do not conceal Work until required information is recorded.
- .4 Contract Drawings and shop drawings: mark each item to record actual construction, including:
 - .1 Measured depths of elements of foundation in relation to finish first floor datum.
 - .2 Measured horizontal and vertical locations of underground utilities and appurtenances, referenced to permanent surface improvements.
 - .3 Measured locations of internal utilities and appurtenances, referenced to visible and accessible features of construction.
 - .4 Field changes of dimension and detail.
 - .5 Changes made by change orders.
 - .6 Details not on original Contract Drawings.
 - .7 References to related shop drawings and modifications.
- .5 Specifications: mark each item to record actual construction, including:
 - .1 Manufacturer, trade name, and catalogue number of each product actually installed, particularly optional items and substitute items.
 - .2 Changes made by Addenda and change orders.
- .6 Other Documents: maintain manufacturer's certifications, inspection certifications, field test records, required by individual specifications sections.

1.7 EQUIPMENT AND SYSTEMS

- .1 For each item of equipment and each system include description of unit or system, and component parts.
 - .1 Give function, normal operation characteristics and limiting conditions.
 - .2 Include performance curves, with engineering data and tests, and complete nomenclature and commercial number of replaceable parts.
- .2 Panel board circuit directories: provide electrical service characteristics, controls, and communications.
- .3 Include installed colour coded wiring diagrams.

- .4 Operating Procedures: include start-up, break-in, and routine normal operating instructions and sequences.
 - .1 Include regulation, control, stopping, shut-down, and emergency instructions.
 - .2 Include summer, winter, and any special operating instructions.
- .5 Maintenance Requirements: include routine procedures and guide for trouble-shooting; disassembly, repair, and reassembly instructions; and alignment, adjusting, balancing, and checking instructions.
- .6 Provide servicing and lubrication schedule, and list of lubricants required.
- .7 Include manufacturer's printed operation and maintenance instructions.
- .8 Include sequence of operation by controls manufacturer.
- .9 Provide original manufacturer's parts list, illustrations, assembly drawings, and diagrams required for maintenance.
- .10 Provide installed control diagrams by controls manufacturer.
- .11 Provide Contractor's co-ordination drawings, with installed colour coded piping diagrams.
- .12 Provide charts of valve tag numbers, with location and function of each valve, keyed to flow and control diagrams.
- .13 Provide list of original manufacturer's spare parts, current prices, and recommended quantities to be maintained in storage.
- .14 Include test and balancing reports as specified in Section 01 45 00 - Quality Control and 01 91 13 - General Commissioning (Cx) Requirements.
- .15 Additional requirements: as specified in individual specification sections.

1.8 MATERIALS AND FINISHES

- .1 Building products, applied materials, and finishes: include product data, with catalogue number, size, composition, and colour and texture designations.
 - .1 Provide information for re-ordering custom manufactured products.
- .2 Instructions for cleaning agents and methods, precautions against detrimental agents and methods, and recommended schedule for cleaning and maintenance.
- .3 Moisture-protection and weather-exposed products: include manufacturer's recommendations for cleaning agents and methods, precautions against detrimental agents and methods, and recommended schedule for cleaning and maintenance.
- .4 Additional requirements: as specified in individual specifications sections.

1.9 MAINTENANCE MATERIALS

- .1 Spare Parts:
 - .1 Provide spare parts, in quantities specified in individual specification sections.
 - .2 Provide items of same manufacture and quality as items in Work.
 - .3 Deliver to site; place and store.
 - .4 Receive and catalogue items.

- .1 Submit inventory listing to Departmental Representative.
 - .2 Include approved listings in Maintenance Manual.
 - .5 Obtain receipt for delivered products and submit prior to final payment.
- .2 Extra Stock Materials:
 - .1 Provide maintenance and extra materials, in quantities specified in individual specification sections.
 - .2 Provide items of same manufacture and quality as items in Work.
 - .3 Deliver to site; place and store.
 - .4 Receive and catalogue items.
 - .1 Submit inventory listing to Departmental Representative.
 - .2 Include approved listings in Maintenance Manual.
 - .5 Obtain receipt for delivered products and submit prior to final payment.
- .3 Special Tools:
 - .1 Provide special tools, in quantities specified in individual specification section.
 - .2 Provide items with tags identifying their associated function and equipment.
 - .3 Deliver to site; place and store.
 - .4 Receive and catalogue items.
 - .1 Submit inventory listing to Departmental Representative.
 - .2 Include approved listings in Maintenance Manual.

1.10 DELIVERY, STORAGE AND HANDLING

- .1 Store spare parts, maintenance materials, and special tools in manner to prevent damage or deterioration.
- .2 Store in original and undamaged condition with manufacturer's seal and labels intact.
- .3 Store components subject to damage from weather in weatherproof enclosures.
- .4 Store paints and freezable materials in a heated and ventilated room.
- .5 Remove and replace damaged products at own expense and for review by Departmental Representative.

1.11 WARRANTIES AND BONDS

- .1 Develop warranty management plan to contain information relevant to Warranties.
- .2 Submit warranty management plan, 30 days before planned pre-warranty conference, to Departmental Representative approval.
- .3 Warranty management plan to include required actions and documents to assure that Departmental Representative receives warranties to which it is entitled.
- .4 Provide plan in narrative form and contain sufficient detail to make it suitable for use by future maintenance and repair personnel.
- .5 Submit, warranty information made available during construction phase, to Departmental Representative for approval prior to each monthly pay estimate.

- .6 Assemble approved information in binder, submit upon acceptance of work and organize binder as follows:
 - .1 Separate each warranty or bond with index tab sheets keyed to Table of Contents listing.
 - .2 List subcontractor, supplier, and manufacturer, with name, address, and telephone number of responsible principal.
 - .3 Obtain warranties and bonds, executed in duplicate by subcontractors, suppliers, and manufacturers, within ten days after completion of applicable item of work.
 - .4 Verify that documents are in proper form, contain full information, and are notarized.
 - .5 Co-execute submittals when required.
 - .6 Retain warranties and bonds until time specified for submittal.
- .7 Except for items put into use with Owner's permission, leave date of beginning of time of warranty until Date of Substantial Performance is determined.
- .8 Include information contained in warranty management plan as follows:
 - .1 Roles and responsibilities of personnel associated with warranty process, including points of contact and telephone numbers within the organizations of Contractors, subcontractors, manufacturers or suppliers involved.
 - .2 Listing and status of delivery of Certificates of Warranty for extended warranty items, to make-up air unit.
 - .3 Provide list for each warranted equipment, item, feature of construction or system indicating:
 - .1 Name of item.
 - .2 Model and serial numbers.
 - .3 Location where installed.
 - .4 Name and phone numbers of manufacturers or suppliers.
 - .5 Names, addresses and telephone numbers of sources of spare parts.
 - .6 Warranties and terms of warranty: include one-year overall warranty of construction. Indicate items that have extended warranties and show separate warranty expiration dates.
 - .7 Cross-reference to warranty certificates as applicable.
 - .8 Starting point and duration of warranty period.
 - .9 Summary of maintenance procedures required to continue warranty in force.
 - .10 Cross-Reference to specific, pertinent Operation and Maintenance manuals.
 - .11 Organization, names and phone numbers of persons to call for warranty service.
 - .12 Typical response time and repair time expected for various warranted equipment.
 - .4 Procedure and status of tagging of equipment covered by extended warranties.
 - .5 Post copies of instructions near selected pieces of equipment where operation is critical for warranty and/or safety reasons.

- .9 Respond in timely manner to oral or written notification of required construction warranty repair work.
- .10 Written verification to follow oral instructions.
 - .1 Failure to respond will be cause for the Departmental Representative to proceed with action against Contractor.

1.12 WARRANTY TAGS

- .1 Tag, at time of installation, each warranted item. Provide durable, oil and water resistant tag approved by Departmental Representative.
- .2 Attach tags with copper wire and spray with waterproof silicone coating.
- .3 Leave date of acceptance until project is accepted for occupancy.
- .4 Indicate following information on tag:
 - .1 Type of product/material.
 - .2 Model number.
 - .3 Serial number.
 - .4 Contract number.
 - .5 Warranty period.
 - .6 Inspector's signature.
 - .7 Construction Contractor.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 ADMINISTRATIVE REQUIREMENTS

- .1 Demonstrate scheduled operation and maintenance of equipment and systems to Owner's personnel two weeks prior to date of substantial performance.
- .2 Owner: provide list of personnel to receive instructions, and co-ordinate their attendance at agreed-upon times.
- .3 Preparation:
 - .1 Verify conditions for demonstration and instructions comply with requirements.
 - .2 Verify designated personnel are present.
 - .3 Ensure equipment has been inspected and put into operation.
 - .4 Ensure testing, adjusting, and balancing has been performed in accordance with Section 01 91 13 - General Commissioning (Cx) Requirements and equipment and systems are fully operational.
- .4 Demonstration and Instructions:
 - .1 Demonstrate start-up, operation, control, adjustment, trouble-shooting, servicing, and maintenance of each item of equipment at scheduled times, at the equipment location.
 - .2 Instruct personnel in phases of operation and maintenance using operation and maintenance manuals as basis of instruction.
 - .3 Review contents of manual in detail to explain aspects of operation and maintenance.
 - .4 Prepare and insert additional data in operations and maintenance manuals when needed during instructions.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit schedule of time and date for demonstration of each item of equipment and each system two weeks prior to designated dates, for Departmental Representative's approval.
- .3 Submit reports within one week after completion of demonstration, that demonstration and instructions have been satisfactorily completed.
- .4 Give time and date of each demonstration, with list of persons present.
- .5 Provide copies of completed operation and maintenance manuals for use in demonstrations and instructions.

1.3 QUALITY ASSURANCE

- .1 When specified in individual Sections requiring manufacturer to provide authorized representative to demonstrate operation of equipment and systems:
 - .1 Instruct Owner's personnel.
 - .2 Provide written report that demonstration and instructions have been completed.

Part 2 Products

2.1 NOT USED

.1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

END OF SECTION

Part 1 General

1.1 GENERAL

- .1 Cx is a planned program of tests, procedures and checks carried out systematically on systems and integrated systems of the finished Project. Cx is performed after systems and integrated systems are completely installed, functional and Contractor's Performance Verification responsibilities have been completed and approved. Objectives:
 - .1 Verify installed equipment, systems and integrated systems operate in accordance with contract documents and design criteria and intent.
 - .2 Ensure appropriate documentation is compiled into the BMM.
 - .3 Effectively train O M staff.
- .2 Contractor assists in Cx process, operating equipment and systems, troubleshooting and making adjustments as required.
 - .1 Systems to be operated at full capacity under various modes to determine if they function correctly and consistently at peak efficiency. Systems to be interactively with each other as intended in accordance with Contract Documents and design criteria.
 - .2 During these checks, adjustments to be made to enhance performance to meet environmental or user requirements.
- .3 Design Criteria: as per client's requirements or determined by designer. To meet Project functional and operational requirements.

1.2 COMMISSIONING OVERVIEW

- .1 Section 01 91 31 - Commissioning (Cx) Plan.
- .2 For Cx responsibilities refer to Section 01 91 31 - Commissioning (Cx) Plan.
- .3 Cx to be a line item of Contractor's cost breakdown.
- .4 Cx activities supplement field quality and testing procedures described in relevant technical sections.
- .5 Cx is conducted in concert with activities performed during stage of project delivery. Cx identifies issues in Planning and Design stages which are addressed during Construction and Cx stages to ensure the built facility is constructed and proven to operate satisfactorily under weather, environmental and occupancy conditions to meet functional and operational requirements. Cx activities includes transfer of critical knowledge to facility operational personnel.
- .6 Departmental Representative will issue Interim Acceptance Certificate when:
 - .1 Completed Cx documentation has been received, reviewed for suitability and approved by Departmental Representative.
 - .2 Equipment, components, systems and in integrated systems have been fully commissioned and functional as per design intent within the context of the Owner Project Requirement.

- .3 Final O&M and Training Manual has been received, reviewed, and approved by the Departmental Representative for suitability.
- .4 Completion of training session to all Operational and Maintenance staff.

1.3 NON-CONFORMANCE TO PERFORMANCE VERIFICATION REQUIREMENTS

- .1 Should equipment, system components, and associated controls be incorrectly installed or malfunction during Cx, correct deficiencies, re-verify equipment and components within the unfunctional system, including related systems as deemed required by Departmental Representative, to ensure effective performance.
- .2 Costs for corrective work, additional tests, inspections, to determine acceptability and proper performance of such items to be borne by Contractor. Above costs to be in form of progress payment reductions or hold-back assessments.

1.4 PRE-CX REVIEW

- .1 Before Construction:
 - .1 Review contract documents, confirm by writing to Departmental Representative.
 - .1 Adequacy of provisions for Cx.
 - .2 Aspects of design and installation pertinent to success of Cx.
- .2 During Construction:
 - .1 Co-ordinate provision, location and installation of provisions for Cx.
- .3 Before start of Cx:
 - .1 Have completed Cx Plan up-to-date.
 - .2 Ensure installation of related components, equipment, sub-systems, systems is complete.
 - .3 Fully understand Cx requirements and procedures.
 - .4 Have Cx documentation shelf-ready.
 - .5 Understand completely design criteria and intent and special features.
 - .6 Submit complete start-up documentation to Departmental Representative.
 - .7 Have Cx schedules up-to-date.
 - .8 Ensure systems have been cleaned thoroughly.
 - .9 Complete TAB procedures on systems, submit TAB reports to Departmental Representative for review and approval.
 - .10 Ensure "As-Built" system schematics are available.
- .4 Inform Departmental Representative in writing of discrepancies and deficiencies on finished works.

1.5 CONFLICTS

- .1 Report conflicts between requirements of this section and other sections to Departmental Representative before start-up and obtain clarification.
- .2 Failure to report conflict and obtain clarification will result in application of most stringent requirement.

1.6 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
 - .1 Submit no later than 8 weeks after award of Contract:
 - .1 Name of Contractor's Cx agent.
 - .2 Draft Cx documentation.
 - .3 Preliminary Cx schedule.
 - .4 Approved Shop Drawings.
 - .5 Proposed schedule for manufacturer startup and operation instruction to Departmental Representative for review and approval.
 - .2 Request in writing to Departmental Representative for changes to submittals and obtain written approval at least 8 weeks prior to start of Cx.
 - .3 Submit proposed Cx procedures to Departmental Representative where not specified and obtain written approval at least 8 weeks prior to start of Cx.
 - .4 Provide additional documentation relating to Cx process required by Departmental Representative.

1.7 COMMISSIONING DOCUMENTATION

- .1 Refer to Section 01 91 33 - Commissioning (Cx) Forms: Installation Check Lists and Product Information (PI) / Performance Verification (PV) Forms for requirements and instructions for use.
- .2 Departmental Representative to review and approve Cx documentation.
- .3 Provide completed and approved Cx documentation to Departmental Representative.

1.8 COMMISSIONING SCHEDULE

- .1 Provide detailed Cx schedule as part of construction schedule.
- .2 Provide adequate time for Cx activities prescribed in technical sections and commissioning sections including:
 - .1 Approval of Cx reports.
 - .2 Verification of reported results.
 - .3 Repairs, retesting, re-commissioning, re-verification.
 - .4 Training.

1.9 COMMISSIONING MEETINGS

- .1 Convene Cx meetings following project meetings.
- .2 Purpose: to resolve issues, monitor progress, identify deficiencies, relating to Cx.
- .3 Continue Cx meetings on regular basis until commissioning deliverables have been addressed.
- .4 At 60% construction completion stage. to call a separate Cx scope meeting to review progress, discuss schedule of equipment start-up activities and prepare for Cx. Issues at meeting to include:

- .1 Review duties and responsibilities of Contractor and subcontractors, addressing delays and potential problems.
- .2 Determine the degree of involvement of trades and manufacturer's representatives in the commissioning process.
- .5 Thereafter Cx meetings to be held until project completion and as required during equipment start-up and functional testing period.
- .6 Meeting will be chaired by Departmental Representative, who will record and distribute minutes.
- .7 Ensure subcontractors and relevant manufacturer representatives are present at 60% and subsequent Cx meetings and as required.

1.10 STARTING AND TESTING

- .1 Contractor assumes liabilities and costs for inspections. Including disassembly and re-assembly after approval, starting, testing and adjusting, including supply of testing equipment.

1.11 WITNESSING OF STARTING AND TESTING

- .1 Provide 14 days notice prior to commencement.
- .2 Departmental Representative to witness of start-up and testing.
- .3 .3 Contractor's Cx Agent to be present at tests performed and documented by sub-trades, suppliers and equipment manufacturers.

1.12 MANUFACTURER'S INVOLVEMENT

- .1 Factory testing: manufacturer to:
 - .1 Coordinate time and location of testing.
 - .2 Provide testing documentation for approval by Departmental Representative.
 - .3 Arrange for Departmental Representative to witness tests.
 - .4 Obtain written approval of test results and documentation from Departmental Representative before delivery to site.
- .2 Obtain manufacturers installation, start-up and operations instructions prior to start-up of components, equipment and systems and review with Departmental Representative.
 - .1 Compare completed installation with manufacturer's published data, record discrepancies, and review with manufacturer.
 - .2 Modify procedures detrimental to equipment performance and review same with manufacturer before start-up.
- .3 Integrity of warranties:
 - .1 Use manufacturer's trained start-up personnel where specified elsewhere in other divisions or required to maintain integrity of warranty.
 - .2 Verify with manufacturer that testing as specified will not void warranties.
- .4 Qualifications of manufacturer's personnel:
 - .1 Experienced in design, installation and operation of equipment and systems.

- .2 Ability to interpret test results accurately.
- .3 To report results in clear, concise, logical manner.

1.13 PROCEDURES

- .1 Verify that equipment and systems are complete, clean, and operating in normal and safe manner prior to conducting start-up, testing and Cx.
- .2 Conduct start-up and testing in following distinct phases:
 - .1 Included in delivery and installation:
 - .1 Verification of conformity to specification, approved shop drawings and completion of PI report forms.
 - .2 Visual inspection of quality of installation.
 - .2 Start-up: follow accepted start-up procedures.
 - .3 Operational testing: document equipment performance.
 - .4 System PV: include repetition of tests after correcting deficiencies.
 - .5 Post-substantial performance verification: to include fine-tuning.
- .3 Correct deficiencies and obtain approval from Departmental Representative after distinct phases have been completed and before commencing next phase.
- .4 Document require tests on approved PV forms.
- .5 Failure to follow accepted start-up procedures will result in re-evaluation of equipment by an independent testing agency selected by Departmental Representative. If results reveal that equipment start-up was not in accordance with requirements, and resulted in damage to equipment, implement following:
 - .1 Minor equipment/systems: implement corrective measures approved by Departmental Representative.
 - .2 Major equipment/systems: if evaluation report concludes that damage is minor, implement corrective measures approved by Departmental Representative.
 - .3 If evaluation report concludes that major damage has occurred, Departmental Representative shall reject equipment.
 - .1 Rejected equipment to be remove from site and replace with new.
 - .2 Subject new equipment/systems to specified start-up procedures.

1.14 START-UP DOCUMENTATION

- .1 Assemble start-up documentation and submit to Departmental Representative for approval before commencement of commissioning.
- .2 Start-up documentation to include:
 - .1 Factory and on-site test certificates for specified equipment.
 - .2 Pre-start-up inspection reports.
 - .3 Signed installation/start-up check lists.
 - .4 Start-up reports,
 - .5 Step-by-step description of complete start-up procedures, to permit Departmental Representative to repeat start-up at any time.

1.15 OPERATION AND MAINTENANCE OF EQUIPMENT AND SYSTEMS

- .1 After start-up, operate and maintain equipment and systems as directed by equipment/system manufacturer.
- .2 With assistance of manufacturer develop written maintenance program and submit Departmental Representative for approval before implementation.
- .3 Operate and maintain systems for length of time required for commissioning to be completed.
- .4 After completion of commissioning, operate and maintain systems until issuance of certificate of interim acceptance.

1.16 TEST RESULTS

- .1 If start-up, testing and/or PV produce unacceptable results, repair, replace or repeat specified starting and/or PV procedures until acceptable results are achieved.
- .2 Provide manpower and materials, assume costs for re-commissioning.

1.17 START OF COMMISSIONING

- .1 Notify Departmental Representative at least 21 days prior to start of Cx.
- .2 Start Cx after elements of building affecting start-up and performance verification of systems have been completed.

1.18 INSTRUMENTS / EQUIPMENT

- .1 Submit to Departmental Representative for review and approval:
 - .1 Complete list of instruments proposed to be used.
 - .2 Listed data including, serial number, current calibration certificate, calibration date, calibration expiry date and calibration accuracy.
- .2 Provide the following equipment as required:
 - .1 2-way radios.
 - .2 Ladders.
 - .3 Equipment as required to complete work.

1.19 COMMISSIONING PERFORMANCE VERIFICATION

- .1 Carry out Cx:
 - .1 Under accepted simulated operating conditions, over entire operating range, in all modes.
 - .2 On independent systems and interacting systems.
- .2 Cx procedures to be repeatable and reported results are to be verifiable.
- .3 Follow equipment manufacturer's operating instructions.

1.20 WITNESSING COMMISSIONING

- .1 Departmental Representative to witness activities and verify results.

1.21 AUTHORITIES HAVING JURISDICTION

- .1 Where specified start-up, testing or commissioning procedures duplicate verification requirements of authority having jurisdiction, arrange for authority to witness procedures so as to avoid duplication of tests and to facilitate expedient acceptance of facility.
- .2 Obtain certificates of approval, acceptance and compliance with rules and regulation of authority having jurisdiction.
- .3 Provide copies to Departmental Representative within 5 days of test and with Cx report.

1.22 COMMISSIONING CONSTRAINTS

- .1 Since access into secure or sensitive areas will be very difficult after occupancy it is necessary to complete Cx of occupancy, weather, and seasonal sensitive equipment and systems in these areas before issuance of the Interim Certificate, using, if necessary, simulated thermal loads.

1.23 EXTRAPOLATION OF RESULTS

- .1 Where Cx of weather, occupancy, or seasonal-sensitive equipment or systems cannot be conducted under near-rated or near-design conditions, extrapolate part-load results to design conditions when approved by Departmental Representative in accordance with equipment manufacturer's instructions, using manufacturer's data, with manufacturer's assistance and using approved formulae.

1.24 EXTENT OF VERIFICATION

- .1 Provide manpower and instrumentation to verify up to 30 % of reported results, unless specified otherwise in other sections.
- .2 Number and location to be at discretion of Departmental Representative.
- .3 Conduct tests repeated during verification under same conditions as original tests, using same test equipment, instrumentation.
- .4 Review and repeat commissioning of systems if inconsistencies found in more than 20% of reported results.
- .5 Perform additional commissioning until results are acceptable to Departmental Representative.

1.25 REPEAT VERIFICATIONS

- .1 Assume costs incurred by Departmental Representative for third and subsequent verifications where:
 - .1 Verification of reported results fail to receive Departmental Representative's approval.
 - .2 Repetition of second verification again fails to receive approval.
 - .3 Departmental Representative deems Contractor's request for second verification was premature.

1.26 SUNDRY CHECKS AND ADJUSTMENTS

- .1 Make adjustments and changes which become apparent as Cx proceeds.

- .2 Perform static and operational checks as applicable and as required.

1.27 DEFICIENCIES, FAULTS, DEFECTS

- .1 Correct deficiencies found during start-up and Cx to satisfaction of Departmental Representative.
- .2 Report problems, faults or defects affecting Cx to Departmental Representative in writing. Stop Cx until problems are rectified. Proceed with written approval from Departmental Representative.

1.28 COMPLETION OF COMMISSIONING

- .1 Upon completion of Cx leave systems in normal operating mode.
- .2 Except for warranty and seasonal verification activities specified in Cx specifications, complete Cx prior to issuance of Interim Certificate of Completion.
- .3 Cx to be considered complete when contract Cx deliverables have been submitted and accepted by Departmental Representative.

1.29 ACTIVITIES UPON COMPLETION OF COMMISSIONING

- .1 When changes are made to baseline components or system settings established during Cx process, provide updated Cx form for affected item.

1.30 TRAINING

- .1 In accordance with Section 01 91 41 - Commissioning (Cx) - Training.

1.31 MAINTENANCE MATERIALS, SPARE PARTS, SPECIAL TOOLS

- .1 Supply, deliver, and document maintenance materials, spare parts, and special tools as specified in contract.

1.32 OCCUPANCY

- .1 Cooperate fully with Departmental Representative during stages of acceptance and occupancy of facility.

1.33 INSTALLED INSTRUMENTATION

- .1 Use instruments installed under Contract for TAB and PV if:
 - .1 Accuracy complies with these specifications.
 - .2 Calibration certificates have been deposited with Departmental Representative.

1.34 PERFORMANCE VERIFICATION TOLERANCES

- .1 Application tolerances:
 - .1 Specified range of acceptable deviations of measured values from specified values or specified design criteria. Except for special areas, to be within +/- 10% of specified values.
- .2 Instrument accuracy tolerances:
 - .1 To be of higher order of magnitude than equipment or system being tested.

- .3 Measurement tolerances during verification:
 - .1 Unless otherwise specified actual values to be within +/- 2 % of recorded values.

1.35 OWNER'S PERFORMANCE TESTING

- .1 Performance testing of equipment or system by Departmental Representative will not relieve Contractor from compliance with specified start-up and testing procedures.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes: Description of overall structure of Cx Plan and roles and responsibilities of Cx team.

1.2 REFERENCE STANDARDS

- .1 American Water Works Association (AWWA)
- .2 National Fire Protection Association (NFPA)
 - .1 NFPA-13-07, Installation of Sprinkler Systems Handbook.
- .3 Public Works and Government Services Canada (PSPC)
 - .1 PSPC - Commissioning Guidelines-3rd edition-03.
- .4 Underwriters' Laboratories of Canada (ULC)
- .5 CSA-Z320-11 – Building Commissioning Standard.
- .6 ASHRAE 202-2013 – Commissioning Process for Building and System.

1.3 GENERAL

- .1 Provide a fully functional makeup air system.
 - .1 Systems, equipment, and components meet user's functional requirements before date of acceptance, and operate consistently at peak efficiencies.
 - .2 O M personnel have been fully trained in aspects of installed systems.
 - .3 Complete documentation relating to installed equipment and systems.
- .2 Term "Cx" in this section means "Commissioning".
- .3 Use this Cx Plan as master planning document for Cx:
 - .1 Outlines organization, scheduling, allocation of resources, documentation, pertaining to implementation of Cx.
 - .2 Communicates responsibilities of team members involved in Cx Scheduling, documentation requirements, and verification procedures.
 - .3 Sets out deliverables relating to O M, process and administration of Cx.
 - .4 Describes process of verification of how built works meet design requirements.
 - .5 Produces a complete functional system prior to issuance of Certificate of Occupancy.
 - .6 Management tool that sets out scope, standards, roles and responsibilities, expectations, deliverables, and provides:
 - .1 Overview of Cx.
 - .2 General description of elements that make up Cx Plan.
 - .3 Process and methodology for successful Cx.
- .4 Acronyms:

- .1 Cx - Commissioning.
- .2 BMM - Building Management Manual.
- .3 EMCS - Energy Monitoring and Control Systems.
- .4 MSDS - Material Safety Data Sheets.
- .5 PI - Product Information.
- .6 PV - Performance Verification.
- .7 TAB - Testing, Adjusting and Balancing.
- .8 WHMIS - Workplace Hazardous Materials Information System.
- .5 Commissioning terms used in this Section:
 - .1 Bumping: short term start-up to prove ability to start and prove correct rotation.
 - .2 Deferred Cx - Cx activities delayed for reasons beyond Contractor's control due to lack of occupancy, weather conditions, need for heating/cooling loads.

1.4 DEVELOPMENT OF 100% CX PLAN

- .1 Cx Plan to be 100% completed within 8 weeks of award of contract to take into account:
 - .1 Approved shop drawings and product data.
 - .2 Approved changes to contract.
 - .3 Contractor's project schedule.
 - .4 Cx schedule.
 - .5 Contractor's, sub-contractor's, suppliers' requirements.
 - .6 Project construction team's and Cx team's requirements.
- .2 Submit completed Cx Plan to Departmental Representative and obtain written approval.

1.5 COMPOSITION, ROLES AND RESPONSIBILITIES OF CX TEAM

- .1 Departmental Representative to maintain overall responsibility for project and is sole point of contact between members of commissioning team.
- .2 Project Manager will select Cx Team consisting of following members:
 - .1 PSPC Design Quality Review Team: during construction, will conduct periodic site reviews to observe general progress.
 - .2 PSPC Quality Assurance Commissioning Manager: confirm Cx processes, forms and procedures are developed in the Cx Plan by the Departmental Representative to deliver a fully operational project.
 - .3 Departmental Representative is responsible for:
 - .1 Organizing Cx.
 - .2 Monitoring operations Cx activities.
 - .3 Ensuring implementation of final Cx Plan.
 - .4 Performing verification of performance of installed systems and equipment.
 - .5 Implementation of Training Plan.
 - .6 Review of Cx documentation from operational perspective.

- .7 Review for performance, reliability, durability of operation, accessibility, maintainability, operational efficiency under conditions of operation.
- .8 Protection of health, safety and comfort of occupants and O M personnel.
- .9 Monitoring of Cx activities, training, development of Cx documentation.
- .10 Work closely with members of Cx Team.
- .4 Construction Team: contractor, sub-contractors, suppliers and support disciplines, is responsible for construction/installation in accordance with Contract Documents, including:
 - .1 Testing.
 - .2 TAB.
 - .3 Performance of Cx activities.
 - .4 Delivery of training and Cx documentation.
 - .5 Assigning one person as point of contact with the Departmental Representative and PSPC Cx Manager for administrative and coordination purposes.
- .5 Contractor's Cx agent implements specified Cx activities including:
 - .1 Demonstrations.
 - .2 Training.
 - .3 Testing.
 - .4 Preparation, submission of test reports.
- .6 Property Manager: represents lead role in Operation Phase and onwards and is responsible for:
 - .1 Receiving facility.
 - .2 Day-To-Day operation and maintenance of facility.

1.6 CX PARTICIPANTS

- .1 Employ the following Cx participants to verify performance of equipment and systems:
 - .1 Installation contractor/subcontractor:
 - .1 Equipment and systems except as noted.
 - .2 Equipment manufacturer: equipment specified to be installed and started by manufacturer.
 - .1 To include performance verification.
- .3 Ensure that Cx participant:
 - .1 Could complete work within scheduled timeframe.
 - .2 Available for emergency and troubleshooting service during first year of occupancy by user for adjustments and modifications outside responsibility of O M personnel, including:
 - .1 Modify ventilation rates to meet changes in off-gassing.
 - .2 Changes to heating or cooling loads beyond scope of EMCS.
 - .3 Changes to EMCS control strategies beyond level of training provided to O M personnel.

- .4 Redistribution of electrical services.
- .5 Modifications of fire alarm systems.
- .6 Modifications to voice communications systems.

1.7 EXTENT OF CX

- .1 Commission mechanical systems and associated equipment:
 - .1 HVAC and exhaust systems:
 - .1 Makeup Air Unit
 - .2 Grilles and Diffusers
 - .3 Air Balancing
 - .4 Electrical

1.8 DELIVERABLES RELATING TO O M PERSPECTIVES

- .1 General requirements:
 - .1 Compile English documentation.
 - .2 Documentation to be computer-compatible format ready for inputting for data management.
- .2 Provide deliverables:
 - .1 Warranties.
 - .2 Project record documentation.
 - .3 Inventory of spare parts, special tools, and maintenance materials.
 - .4 Maintenance Management System (MMS) identification system used.
 - .5 WHMIS information.
 - .6 MSDS data sheets.
 - .7 Preventative Maintenance Program
 - .8 Contractor's and Subcontractor's As-Built Drawings.

1.9 DELIVERABLES RELATING TO THE CX PROCESS

- .1 General:
 - .1 Start-up, testing and Cx requirements, conditions for acceptance and specifications form part of relevant technical sections of these specifications.
- .2 Definitions:
 - .1 Cx as used in this section includes:
 - .1 Cx of components, equipment, systems, subsystems, and integrated systems.
 - .2 Factory inspections and performance verification tests.
- .3 Deliverables: provide:
 - .1 Startup, pre-Cx activities and documentation for systems, and equipment.
 - .2 Completed installation checklists (ICL).
 - .3 Completed product information (PI) report forms.

- .4 Completed performance verification (PV) report forms.
- .5 Results of Performance Verification Tests and Inspections.
- .6 Description of Cx activities and documentation.
- .7 Description of Cx of integrated systems and documentation.
- .8 Training Plans.
- .9 Cx Reports.
- .10 Prescribed activities during warranty period.
- .4 Departmental Representative to participate.

1.10 PRE-CX ACTIVITIES AND RELATED DOCUMENTATION

- .1 Items listed in this Cx Plan include the following:
 - .1 Pre-Start-Up inspections: by Departmental Representative prior to permission to start up and rectification of deficiencies to Departmental Representative's satisfaction.
 - .2 Include completed documentation with Cx report.
 - .3 Conduct pre-start-up tests: conduct pressure, static, flushing, cleaning, and "bumping" during construction as specified in technical sections.
 - .4 Departmental Representative will monitor some of these inspections and tests.
 - .5 Include completed documentation in Cx report.
- .2 Pre-Cx Activities - MECHANICAL:
 - .1 HVAC equipment and systems:
 - .1 "Bump" each item of equipment in its "stand-alone" mode.
 - .2 At this time, complete pre-start-up checks and complete relevant documentation.
 - .3 After equipment has been started, test related systems in conjunction with control systems on a system-by-system basis.
 - .4 Perform TAB on systems. TAB reports to be approved by Departmental Representative.

1.11 START-UP

- .1 Start up components, equipment and systems.
- .2 Equipment manufacturer, supplier, installing specialist sub-contractor, as appropriate, to startup, under Contractor's direction, following equipment, systems:
 - .1 Makeup Air Unit.
- .3 Departmental Representative to monitor some of these start-up activities.
 - .1 Rectify start-up deficiencies to satisfaction of Departmental Representative.
- .4 Performance Verification (PV):
 - .1 Approved Cx Agent to perform.
 - .1 Repeat when necessary until results are acceptable to Departmental Representative.

- .2 Use procedures modified generic procedures to suit project requirements.
- .3 Departmental Representative to approve completed PV reports.
- .4 Departmental Representative reserves right to verify up to 30% of reported results at random.
- .5 Failure of randomly selected item shall result in rejection of PV report or report of system startup and testing.

1.12 CX ACTIVITIES AND RELATED DOCUMENTATION

- .1 Perform Cx by specified Cx agency using procedures developed by the Departmental Representative.
- .2 Departmental Representative to monitor Cx activities.
- .3 Upon satisfactory completion, Cx agency performing tests to prepare Cx Report using approved PV forms.
- .4 Departmental Representative reserves right to verify a percentage of reported results at no cost to contract.

1.13 INSTALLATION CHECK LISTS (ICL)

- .1 Refer to Section 01 91 33 - Commissioning (Cx) Forms: Installation Check Lists and Product Information (PI) / Performance Verification (PV)Forms.

1.14 PRODUCT INFORMATION (PI) REPORT FORMS

- .1 Refer to Section 01 91 33 - Commissioning (Cx) Forms: Installation Check Lists and Product Information (PI) / Performance Verification (PV)Forms.

1.15 PERFORMANCE VERIFICATION (PV) REPORT

- .1 Refer to Section 01 91 33 - Commissioning (Cx) Forms: Installation Check Lists and Product Information (PI) / Performance Verification (PV)Forms.

1.16 DELIVERABLES RELATING TO ADMINISTRATION OF CX

- .1 General: Because of risk assessment, complete Cx of occupancy, weather and seasonal-sensitive equipment and systems in these areas before building is occupied.

1.17 CX SCHEDULES

- .1 Prepare detailed Cx Schedule and submit to Departmental Representative for review and approval same time as project Construction Schedule. Include:
 - .1 Milestones, testing, documentation, training and Cx activities of components, equipment, subsystems, systems and integrated systems, including:
 - .1 Design criteria, design intents.
 - .2 Cx agents' credentials: 14 days before start of Cx.
 - .3 Cx procedures: 1 month after award of contract.
 - .4 Cx Report format: 1 month after contract award.
 - .5 Submission of list of instrumentation with relevant certificates: 21 days before start of Cx.

- .6 Notification of intention to start TAB: 21 days before start of TAB.
- .7 TAB: after successful start-up, correction of deficiencies and verification of normal and safe operation.
- .8 Notification of intention to start Cx: 14 days before start of Cx.
- .9 Identification of deferred Cx.
- .10 Implementation of training plans.
- .11 Cx reports: immediately upon successful completion of Cx.
- .2 Detailed training schedule to demonstrate no conflicts with testing, completion of project and hand-over to Property Manager.
- .2 After approval, incorporate Cx Schedule into Construction Schedule.

1.18 CX REPORTS

- .1 Submit reports of tests to Departmental Representative who will verify reported results.
- .2 Include completed and certified PV reports in properly formatted Cx Reports.
- .3 Before reports are accepted, reported results to be subject to verification by Departmental Representative.

1.19 ACTIVITIES DURING WARRANTY PERIOD

- .1 Cx activities must be completed before issuance of Interim Certificate, it is anticipated that certain Cx activities may be necessary during Warranty Period, including:
 - .1 Fine tuning of HVAC systems.

1.20 TRAINING PLANS

- .1 Refer to Section 01 91 41 - Commissioning (Cx) - Training.

1.21 FINAL SETTINGS

- .1 Upon completion of Cx to satisfaction of Departmental Representative lock control devices in their final positions, indelibly mark settings marked and include in Cx Reports.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 INSTALLATION/START-UP CHECK LISTS

- .1 Include the following data:
 - .1 Product manufacturer's installation instructions and recommended checks.
 - .2 Special procedures as specified in relevant technical sections.
 - .3 Items considered good installation and engineering industry practices deemed appropriate for proper and efficient operation.
- .2 Equipment manufacturer's installation/start-up check lists are acceptable for use. As deemed necessary by Departmental Representative supplemental additional data lists will be required for specific project conditions.
- .3 Use check lists for equipment installation. Document check list verifying checks have been made, indicate deficiencies and corrective action taken.
- .4 Installer to sign check lists upon completion, certifying stated checks and inspections have been performed. Return completed check lists to Departmental Representative. Check lists will be required during Commissioning and will be included in Building Maintenance Manual (BMM) at completion of project.
- .5 Use of check lists will not be considered part of commissioning process but will be stringently used for equipment pre-start and start-up procedures.
- .6 Sample check sheets are provided at the end of this section.

1.2 PRODUCT INFORMATION (PI) REPORT FORMS

- .1 Product Information (PI) forms compiles gathered data on items of equipment produced by equipment manufacturer, includes nameplate information, parts list, operating instructions, maintenance guidelines and pertinent technical data and recommended checks that is necessary to prepare for start-up and functional testing and used during operation and maintenance of equipment. This documentation is included in the BMM at completion of work.
- .2 Prior to Performance Verification (PV) of systems complete items on PI forms related to systems and obtain Departmental Representative's approval.

1.3 PERFORMANCE VERIFICATION (PV) FORMS

- .1 PV forms to be used for checks, running dynamic tests and adjustments carried out on equipment and systems to ensure correct operation, efficiently and function independently and interactively with other systems as intended with project requirements.
- .2 PV report forms include those developed by Contractor records measured data and readings taken during functional testing and Performance Verification procedures.
- .3 Prior to PV of integrated system, complete PV forms of related systems and obtain Departmental Representative's approval.

1.4 SAMPLES OF COMMISSIONING FORMS

- .1 Departmental Representative will develop and provide to Contractor required project-specific Commissioning forms for components, equipment, systems, and integrated systems to be commissioned for pre-functional and functional performance verification.
- .2 Departmental Representative will provide commissioning issues/resolution log template and system components index checklist; project specific.

1.5 CHANGES AND DEVELOPMENT OF NEW REPORT FORMS

- .1 When additional forms are required, but are not available from Departmental Representative develop appropriate verification forms and submit to Departmental Representative for approval prior to use.
 - .1 Additional commissioning forms to be in same format as provided by Departmental Representative.

1.6 COMMISSIONING FORMS

- .1 Use Commissioning forms to verify installation and record performance when starting equipment and systems.
- .2 Strategy for Use:
 - .1 Departmental Representative provides Contractor project-specific Commissioning forms with Specification data included.
 - .2 Contractor will provide required shop drawings information and verify correct installation and operation of items indicated on these forms.
 - .3 Confirm operation as per design criteria and intent.
 - .4 Identify variances between design and operation and reasons for variances.
 - .5 Verify operation in specified normal and emergency modes and under specified load conditions.
 - .6 Record analytical and substantiating data.
 - .7 Verify reported results.
 - .8 Form to bear signatures of recording technician and reviewed and signed off by Departmental Representative.
 - .9 Submit immediately after tests are performed.
 - .10 Reported results in true measured SI unit values.
 - .11 Provide Departmental Representative with originals of completed forms.
 - .12 Maintain copy on site during start-up, testing and commissioning period.

1.7 LANGUAGE

- .1 To suit the language profile of the awarded contract.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

Component Verification (CV)

Project: Laundry C29 Ventilation Upgrade
Location: Prince Albert, Saskatchewan
Project Number: R.076925.001

Asset:

New Make-Up Air Unit

Technical Data:	Yes	No	Notes
Note manufacturer?			
Correct manufacturer installed?			
Note model number?			
Correct model number installed?			
Does the O/A intake louver match shop drawings information provided?			
Does the MUA installed match the shop drawing information provided?			
Local factory non fused disconnect installed?			
Confirm supply fan airflow 8307 L/s (17,600 cfm) at 125 Pa (1.0 in wc)			
Static Checks:	Yes	No	Notes
Is the cabinet in good condition?			
Are the filters in good condition?			
Are the duct connections in good condition?			
Are the access doors in good condition?			
O/A damper installed and in good condition?			
Static pressure taps installed?			
Filter gauge installed?			
Correct filter type installed?			
Flue and cap installed correctly?			
24 Volt control transformer installed?			
Operation Checks	Yes	No	Notes
Any air leakage?			
Any excess sound/vibration?			
Dampers close properly?			
Dampers fail to their appropriate fail safe positions?			
Vendor start-up complete and report received?			

*Good Condition is defined as equipment showing a high level of workmanship in its construction and installation and it is performing its intended service as required

Component Verification (CV)

Project:

Laundry C29 Ventilation Upgrade

Location:

Prince Albert, Saskatchewan

Project Number:

R.076925.001

Asset:

Fan

Static Checks:	Yes	No	Notes
Is the fan housing sealed and free of damage?			
Note the bearing type.			
Is amperage correct? 14.1 FLA			
Is voltage correct? 575V			
3 Phase for fan motor?			
Phase legs of equal amperage? (Witness test by electrician)			
Fan alignment correct?			
Local factory non fused disconnect installed?			
Vibration isolation installed?			
Flex connections installed?			
11.19 kW (15 BHP) motor?			
Sufficient service access?			
Unit complete with 120 V transformer			
Operation Checks	Yes	No	Notes
Rotation is correct?			
Fan set at 840 RMP (adjustable)			
Note the fan static inlet/outlet pressure.			
Are noise and vibration levels acceptable?			
Verify that switch on O/A damper will not allow fan to start until O/A damper is opened.			

Component Verification (CV)

Project:
Location:
Project Number:

Laundry C29 Ventilation Upgrade
Prince Albert, Saskatchewan
R.076925.001

Asset:

Heat Exchanger

Static Checks:	Yes	No	Notes
Proper support installed?			
Drain installed?			
Sufficient service space?			
Pressure regulating valve installed and set at appropriate. Note setpoint.			
1/2 HP motor with 24.6 unit amps?			
Operation Checks:	Yes	No	Notes
Is the remote surface mount installed and functioning as per design?			

Performance Verification Tests (PVT's)

Project: Laundry C29 Ventilation Upgrade
Location: Prince Albert, Saskatchewan
Project Number: R.076925.001

Performance Checks:	Check Pass	Check Fail
1) Manually adjust time schedule of MUA to turn on/off to an acceptable time (i.e. 30 minutes) to witness both on/off conditions. Set discharge temp to 21° C		
2) Once timer prompts MUA to start, visually confirm O/A damper opens in an appropriate manner		
3) Confirm the fan starts up after a time delay		
4) Test accuracy of ambient air temperature sensor by testing air temperature in O/A and compare readings		
5) SEASONAL: If ambient air temperature sensor reads < 18° C (+65° F) - confirm natural gas valve modulates to an open position and burners fire up		
6) SEASONAL: If ambient air temperature sensor reads => 18° C (+65° F) - confirm natural gas valve remains closed		
7) Manually adjust discharge temperature to 23° C (73° F), and verify discharge air temperature sensor reaches this setpoint		
8) Test accuracy of discharge air temperature sensor by testing air temperature in supply air duct and compare readings		
9) Manually set discharge air temperature to a high unachievable set point to verify supply air fan temporarily shuts off to allow heat exchanger to warm		
10) Manually adjust controls to minimize set time period for reset of fans after this situation to a reasonable waiting time to verify fan restart		
11) Await time schedule of MUA to turn off and witness O/A damper to close		
12) Verify fan shuts off before O/A damper closes		
13) Reset overridden controls to default/owners setpoints		

Component Verification (CV)

Project:

Laundry C29 Ventilation Upgrade

Location:

Prince Albert, Saskatchewan

Project Number:

R.076925.001

General Commissioning Checks	Yes	No	Notes
Do single line drawings match what was installed?			
Are all valves installed and in correct locations?			
Does new duct work display good workmanship?			
New duct work supported appropriately?			
Do new diffusers installed match design type?			
Do new diffusers installed match design location?			
Do airflows at diffusers match design drawings?			
Has sufficient owner training been completed?			
Have shop drawings been reviewed?			
Start up reports attained?			

Part 1 General

1.1 TRAINEES

- .1 Trainees: personnel selected for operating and maintaining this facility. Includes building operators, maintenance staff, security staff, and technical specialists as required.
- .2 Trainees will be available for training during later stages of construction for purposes of familiarization with systems.

1.2 INSTRUCTORS

- .1 Departmental Representative will provide:
 - .1 Descriptions of systems.
 - .2 Instruction on design philosophy, design criteria, and design intent.
- .2 Contractor and certified factory-trained manufacturers' personnel: to provide instruction on the following:
 - .1 Start-Up, operation, shut-down of equipment, components and systems.
 - .2 Control features, reasons for, results of, implications on associated systems of, adjustment of set points of control and safety devices.
 - .3 Instructions on servicing, maintenance and adjustment of systems, equipment and components.
- .3 Contractor and equipment manufacturer to provide instruction on:
 - .1 Start-up, operation, maintenance and shut-down of equipment they have certified installation, started up and carried out PV tests.

1.3 TRAINING OBJECTIVES

- .1 Training to be detailed and duration to ensure:
 - .1 Safe, reliable, cost-effective, energy-efficient operation of systems in normal and emergency modes under all conditions.
 - .2 Effective on-going inspection, measurements of system performance.
 - .3 Proper preventive maintenance, diagnosis and trouble-shooting.
 - .4 Ability to update documentation.
 - .5 Ability to operate equipment and systems under emergency conditions until appropriate qualified assistance arrives.

1.4 TRAINING MATERIALS

- .1 Instructors to be responsible for content and quality.
- .2 Training materials to include:
 - .1 "As-Built" Contract Documents.
 - .2 Operating Manual.
 - .3 Maintenance Manual.

- .4 Management Manual.
- .5 TAB and PV Reports.
- .3 Project Manager, Commissioning Manager and Facility Manager will review training manuals.
- .4 Training materials to be in a format that permits future training procedures to same degree of detail.
- .5 Supplement training materials:
 - .1 Transparencies for overhead projectors.
 - .2 Multimedia presentations.
 - .3 Manufacturer's training videos.
 - .4 Equipment models.

1.5 SCHEDULING

- .1 Include in Commissioning Schedule time for training.
- .2 Deliver training during regular working hours, training sessions to be 3 hours in length.
- .3 Training to be completed prior to acceptance of facility.

1.6 RESPONSIBILITIES

- .1 Be responsible for:
 - .1 Implementation of training activities,
 - .2 Coordination among instructors,
 - .3 Quality of training, training materials,
- .2 Departmental Representative will evaluate training and materials.
- .3 Upon completion of training, provide written report, signed by Instructors, witnessed by Departmental Representative.

1.7 TRAINING CONTENT

- .1 Training to include demonstrations by Instructors using the installed equipment and systems.
- .2 Content includes:
 - .1 Review of facility and occupancy profile.
 - .2 Functional requirements.
 - .3 System philosophy, limitations of systems and emergency procedures.
 - .4 Review of system layout, equipment, components and controls.
 - .5 Equipment and system start-up, operation, monitoring, servicing, maintenance and shut-down procedures.
 - .6 System operating sequences, including step-by-step directions for starting up, shut-down, operation of valves, dampers, switches, adjustment of control settings and emergency procedures.
 - .7 Maintenance and servicing.

- .8 Trouble-shooting diagnosis.
- .9 Inter-Action among systems during integrated operation.
- .10 Review of O M documentation.
- .3 Provide specialized training as specified in relevant Technical Sections of the construction specifications.

1.8 VIDEO-BASED TRAINING

- .1 Manufacturer's videotapes to be used as training tool with Departmental Representative's review and written approval 3 months prior to commencement of scheduled training.
- .2 On-Site training videos:
 - .1 Videotape training sessions for use during future training.
 - .2 To be performed after systems are fully commissioned.
 - .3 Organize into several short modules to permit incorporation of changes.
- .3 Production methods to be high quality.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

