



1 AD2 LEVEL 1 – DEMOLITION RCP 1 : 125

- GENERAL NOTES:**
- A. PRIOR TO COMMENCEMENT OF WORK, NOTIFY DEPARTMENTAL REPRESENTATIVE OF ANY DISCREPANCIES NOTED IN THE CONTRACT.
 - B. ALL GRID TO GRID DIMENSIONS ARE PLUS/MINUS. PRIOR TO COMMENCEMENT OF WORK, REVIEW SITE CONDITIONS AND VERIFY ALL DIMENSIONS. NOTIFY DEPARTMENTAL REPRESENTATIVE OF ANY DISCREPANCIES.
 - C. DO NOT SCALE DRAWINGS.
 - D. ALL DIMENSIONS ARE INDICATED IN MILLIMETERS UNLESS OTHERWISE SPECIFIED.
- DRAWING NOTES – SHEET AD2:**
THESE NOTES APPLY TO DRAWING SHEET AD2 ONLY
- 1. EXISTING ACT CEILING TO BE REMOVED AND GRID TO REMAIN. PROVIDE NEW ACOUSTIC CEILING TILE PANELS IN EXISTING GRID.
 - 2. EXISTING ACT GRID AND TILES TO BE REMOVED. REFER TO NEW CONSTRUCTION DRAWINGS.
 - 3. EXISTING COFFERED CEILING TILES AND GRID TO REMAIN.
 - 4. RESERVED.
 - 5. EXISTING LIGHT FIXTURE TO REMAIN.
 - 6. EXISTING LIGHT FIXTURE TO BE DISCONNECTED AND RELOCATED OR REMOVED. REFER TO ELECTRICAL DRAWINGS AND SPECIFICATIONS.
 - 7. LINE INDICATING OFFSET IN FLOOR ASSEMBLY ABOVE.
 - 8. LINE INDICATING EXISTING GYPSUM BULKHEAD TO REMAIN.
 - 9. EXISTING ACT CEILING TILES TO BE REMOVED AND REINSTATED. CUT BACK & MODIFY EXISTING GRID IN RELATION TO NEW WALL LOCATION.
 - 10. EXISTING COFFERED CEILING TILES & GRID TO BE MODIFIED TO FACILITATE INSTALLATION OF NEW MECHANICAL DIFFUSERS.
 - 11. CUT OPENING IN COFFERED LAY-IN TILE CEILING TRACK & MODIFY FRAMING FOR NEW DIFFUSER. COORDINATE WITH MECHANICAL.
 - 12. EXISTING CONCRETE BLOCK EXTERIOR WALL TO BE REMOVED FOR DUCT PENETRATION. COORDINATE WITH MECHANICAL.
 - 13. PROVIDE NEW DUCT OPENING IN EXISTING WALL. MODIFY EXISTING FRAMING & PROVIDE NEW WALL FRAMING FOR NEW OPENING. PATCH AND REPAIR EXISTING GYPSUM. PROVIDE CONTINUOUS SEALANT AROUND OPENING.
 - 14. AREA OF EXISTING ACT CEILING TILES TO BE REMOVED AND REINSTATED AS NEEDED TO FACILITATE DEMOLITION OF EXISTING MECHANICAL DUCTWORK AND INSTALLATION OF NEW MECHANICAL DUCTWORK. ACT CEILING TILES TO BE REINSTATED AS PART OF NEW CONSTRUCTION. REFER TO NEW CONSTRUCTION DRAWINGS.
 - 15. RESERVED.
 - 16. PROVIDE NEW OPENING IN EXISTING CMU FOR DUCT ABOVE CEILING. COORDINATE WITH MECHANICAL AND STRUCTURAL. PROVIDE 1-HR FIRE RATED SEALANT AROUND OPENING.
 - 17. AREA OF CEILING TO BE REMOVED AND REINSTATED TO FACILITATE OVERHEAD DOOR REMOVAL WORK.
 - 18. EXISTING WELL TO REMAIN.

Public Works and
Government Services
Canada

Travaux publics et
services gouvernementaux
Canada

383 Parkdale Avenue, Suite 201
Ottawa Ontario Canada K1Y 4R4

KWC ARCHITECTS INC.

PHONE (613) 238-2117
FAX (613) 238-6595
E MAIL kwc@kwc-arch.com

ARCHITECTS
MAURIZIO SEBASTIAN MARTIGNAGO
LICENCE 6892

2	ISSUED FOR TENDER	2017 06 30
1	66% CLIENT REVIEW	2017 06 16
revisions	description	date
A	A detail no. no. du detail	A
C	B location drawing no. sur dessin no.	B
	C drawing no. dessin no.	C
project	project	
CRA / MAIL PROCESSING RM. INTERIOR RENOVATION/FITUP		
1050 NOTRE DAME AVE., SUDBURY, ON.		
drawing	dessin	
LEVEL 1 RCP DEMOLITION		
Designed By	M.MARTIGNAGO	Conçu par
Date	2015/11/09	(yyyy/mm/dd)
Drawn By	C. DURKIN/ TRAVIS CURLEY	Dessiné par
Date	2017/06/30	(yyyy/mm/dd)
Reviewed By	M.MARTIGNAGO	Examiné par
Date	2015/11/09	(yyyy/mm/dd)
Approved By	M.MARTIGNAGO	Approuvé par
Date	2015/11/09	(yyyy/mm/dd)
Tender		Soumission
Project Manager	CRISTIAN BORS	Administrateur de projets
Project no.		No. du projet
PWGSC R.087411.001		
Drawing no.		No. du dessin
AD2		