

1 MINIMUM STANDARDS

- .1 Materials shall be new and work shall conform to the minimum applicable standards of the Canadian General Standards Board, the Canadian Standards Association, the National Building Code of Canada 2015 (NBCC) and all applicable Provincial and Municipal codes. In the case of conflict or discrepancy the most stringent requirement shall apply.

2 TAXES

- .1 Pay all taxes properly levied by law (including Federal, Provincial and Municipal).

3 FEES, PERMITS, AND CERTIFICATES

- .1 Pay all fees and obtain all permits. Provide authorities with plans and information for acceptance certificates. Provide inspection certificates as evidence that work conforms to requirements of Authority having jurisdiction.

4 FIRE SAFETY REQUIREMENTS

- .1 Comply with the National Building Code of Canada 2015 (NBCC) for fire safety in construction and the National Fire Code of Canada 2015 (NFCC) for fire prevention, fire fighting and life safety in building in use.
- .2 Comply with PSPC Standard on Construction Occupational Health and Safety, Fire Commissioner of Canada (FCC) standards:
 - .1 No. 301: Standard for Construction Operations
 - .2 No. 302: Standard for Welding and Cutting
 - .3 No. 374: Fire Protection Standard for General Storage (Indoor and Outdoor)
 - .4 available from Fire Protection Engineering Services, Labour Program, HRSDC or following internet site: http://info.load-otea.hrsdc-drhcc.gc.ca/fire_prevention/standards/commissioner.shtml
 - .5 Retain all fire safety documents and standards on site.

5 FIELD QUALITY CONTROL

- .1 Carry out Work using qualified licenced workers or apprentices in accordance with Provincial Act respecting manpower vocational training and qualification.
- .2 Permit employees registered in Provincial apprenticeship program to perform specific tasks only if under direct supervision of qualified licenced workers.
- .3 Determine permitted activities and tasks by apprentices, based on level of training attended and demonstration of ability to perform specific duties.

6 HAZARDOUS MATERIALS

- .1 Comply with the requirements of the Workplace Hazardous Materials Information System (WHMIS) regarding use, handling, storage, and disposal of hazardous materials; and regarding labelling and the provision of Material Safety Data Sheets (MSDS) acceptable to Human Resources Development Canada, Labour Program.

7 REMOVED MATERIALS

- .1 Unless otherwise specified, materials for removal become the Contractor's property and shall be taken from site.

8 PROTECTION

- .1 Protect finished work against damage until take-over.
- .2 Protect adjacent work against the spread of dust and dirt beyond the work areas.

- .3 Protect operatives and other users of site from all hazards.

9 USE OF SITE AND FACILITIES

- .1 Execute work with least possible interference or disturbance to the normal use of premises. Make arrangements with Departmental Representative to facilitate work as stated.
- .2 Maintain existing services to building and provide for personnel and vehicle access.
- .3 Where security is reduced by work provide temporary means to maintain security.
- .4 Where elevators, dumbwaiters, conveyors or escalators exist Contractor may use these at Departmental Representative's discretion. Protect from damage, safety hazards and overloading of existing equipment.
- .5 Sanitary facilities will be assigned for Contractor's personnel. Others shall not be used. Keep facilities clean.
- .6 Closures: Protect work temporarily until permanent enclosures completed.

10 SITE STORAGE

- .1 Do not unreasonably encumber site with materials or equipment.
- .2 Move stored products or equipment which interfere with operations of Departmental Representative or other contractors.
- .3 Obtain and pay for use of additional storage as space for equipment storage on site is minimal.

11 CUT, PATCH AND MAKE GOOD

- .1 Cut existing surfaces as required to accommodate new work.
- .2 Remove all items so shown or specified.
- .3 Patch and make good surfaces cut, damaged or disturbed, to Departmental Representative's approval. Match existing material, colour, finish and texture.
- .4 Install firestops and smoke seals in accordance with ULC-S115-11, around pipe, ductwork, cables, and other objects penetrating fire separations to provide fire resistance not less than the fire resistance rating of surrounding floor, ceiling, and wall assembly.

12 SLEEVES, HANGERS AND INSERTS

- .1 Co-ordinate setting and packing of sleeves and supply and installation of hangers and inserts. Obtain Departmental Representative's approval before cutting into structure.

13 EXAMINATION

- .1 Examine site and conditions likely to affect work and be familiar and conversant with existing conditions.

14 SIGNS

- .1 Provide common-use signs related to traffic control, information, instruction, use of equipment, public safety devices, etc., in both official languages or by the use of commonly-understood graphic symbols to the Departmental Representative's approval.
- .2 No advertising will be permitted on this project.

15 WASTE MANAGEMENT

- .1 Comply with the Environmental Protection Act, Ontario Regulations O.Reg. 102/94 and O. Reg. 103/94 for waste management program on construction and demolition projects.
- .2 Conduct "waste audit" to determine waste generated during demolition or construction operations, prepare written "waste reduction work plan" and implement procedures to reduce, reuse and recycle materials to the extent possible.
- .3 Provide a "source separation program" to disassemble and collect in an orderly fashion the following "materials designated for alternative disposal" from the "general waste" stream.
 - .1 cardboard (corrugated).
 - .2 steel.
 - .3 wood (not including treated or laminated wood).
- .4 Submit complete records of all removals from site for both "materials designated for alternative disposal" and "general waste" including:
 - .1 Time and date of removal
 - .2 Description of material and quantities.
 - .3 Proof that materials have been received at an Approved Waste Processing
 - .4 Site or certified Waste Disposal Site as required.

16 GUARANTEES AND WARRANTIES

- .1 Before completion of work collect all manufacturer's guarantees and warranties and deposit with Departmental Representative.

17 SECURITY ESCORT

- .1 Personnel will be checked daily at start of work shift and given a pass which must be worn at all times. Pass must be returned at end of work shift and personnel checked out.
- .2 All personnel must attend a mandatory 2 hour site specific safety training session. Provide minimum 72 hours notice to Departmental Representative requesting site training.

18 BUILDING SMOKING ENVIRONMENT

- .1 Smoking is not permitted in the Building. Obey smoking restrictions on building property.

19 DUST CONTROL

- .1 Provide dust tight screens or partitions to localize dust generating activities, and for protection of workers, finished areas of work and public.
- .2 Maintain and relocate protection until such work is complete.
- .3 Protect all furnishings within work area with 0.102 mm thick polyethylene film during construction. Remove film during non- construction hours and leave premises in clean, unencumbered and safe manner for normal daytime function.

20 TESTING LABORATORY SERVICES

- .1 Departmental Representative will appoint and pay for costs of inspection and testing services, unless indicated otherwise.
- .2 Provide safe working areas and assist with testing procedures, including provisions for materials or services and co-ordination, as required by testing agency and as authorized by Departmental Representative.

- .3 Where tests indicate non-compliance with specifications, contractor to pay for initial test and all subsequent testing of work to verify acceptability of corrected work.

21 SCHEDULING

- .1 On award of contract submit bar chart construction schedule for work, indicating anticipated progress stages within time of completion. When schedule has been reviewed by the Departmental Representative, take necessary measures to complete work within scheduled time. Do not change schedule without notifying Departmental Representative.
- .2 Carry out work during "off hours" Monday to Friday 18:00 to 06:00 and on Saturdays, Sundays and statutory holidays.
- .3 Give the Departmental Representative 48 hours notice for work to be carried out during "off hours".

22 COST BREAKDOWN

- .1 Before submitting first progress claim submit breakdown of Contract Amount in detail as directed by Departmental Representative and aggregating the Contract Amount. After approval by Departmental Representative cost breakdown will be used as the basis of progress payments.

23 PRECEDENCE

- .1 Division 01 Sections take precedence over technical specification sections in other Divisions of this Project Manual.

24 WORK PERMIT

- .1 Obtain applicable work and hot work permit forms from building operator.

25 STAGING PLAN

- .1 Submit to Departmental Representative for review and approval, a Staging Plan that outlines work stages in compliance with specified implementation restrictions and in accordance with submitted schedule. Once approved by the Departmental Representative, do not make changes to specified stages without prior written approval of Departmental Representative. Any changes to the Phasing Plan will require a minimum of 7 days advanced notice. Do not work in staging areas outside of indicated times.

END OF SECTION

1.0 GENERAL

1.1 REFERENCES

1. *Federal Legislation*
 1. *Canada Labour Code, Part II, section 124 and 125. Canada Occupational Health and Safety Regulations (SOR/86-304).*
 2. *Transportation of Dangerous Goods Act, 1992 (TDGA)*
 3. *Canada Consumer Product Safety Act*
 1. *Surface Coating Materials Regulations (SOR/2005-109).*
 4. *Canadian Environmental Protection Act, 1999 (CEPA)*
 1. *PCB Regulations (SOR/2008-273)*
 2. *Federal Halocarbon Regulations, 2003 (SOR/2003-289)*
2. *Provincial Legislation*
 1. *Ontario Occupational Health and Safety Act, R.S.O. 1990, 2010 edition.*
 1. *Ontario Regulation 490/09 – Designated Substances.*
 2. *Ontario Regulation 278/05 – Designated Substance - Asbestos on Construction Projects and in Buildings and Repair Operations.*
 3. *Ontario Regulation 213/91 for Construction Projects.*
 2. *Ontario Environmental Protection Act, R.R.O. 1990:*
 1. *Ontario Regulation 347/09, General – Waste Management.*
 2. *Ontario Regulations 362/90 – Waste Management, PCBs.*
 3. *Ontario Regulation 463/10, Ozone Depleting Substances and Other Halocarbons.*
3. *Canadian General Standards Board (CGSB).*
4. *Canadian Standards Association (CSA International). CAN/CSA-Z94.4-11 - Respiratory Protection*
5. *Underwriters' Laboratories of Canada (ULC).*

1.2 DEFINITIONS

Asbestos-Containing Materials (ACMs): means material that contains 0.5 per cent or more asbestos by dry weight as per Ontario Regulation 278/05, as amended.

Friable Material: material that when dry can be crumbled, pulverized or powdered by hand pressure and includes such material that is crumbled, pulverized or powdered.

Time-weighted average exposure limit (TWael): the time-weighted average airborne concentration of a biological or chemical agent to which a worker may be exposed in a work day or work week as prescribed by *Ontario Regulation 490/09 Designated Substances*, as amended.

1.3 RELATED SECTIONS

Not used

1.4 DESIGNATED SUBSTANCES

Confirm with the Departmental Representative that no additional designated substances have been brought to the project area prior to beginning work.

Additional designated substances and hazardous materials may exist outside the accessible survey areas but are beyond the scope of this project.

Should any additional material, suspected to be a designated substance, be encountered within the project area, any disturbance of such material must be stopped, precautionary measures taken, and the Departmental Representative must be notified immediately. Do not proceed until written instructions have been received.

1. ACRYLONITRILE: Not Identified
2. ARSENIC: Not Identified
3. ASBESTOS: **Identified**

Bulk sampling and subsequent laboratory analysis, visual observations, or historical reports have determined that the following friable materials contain or are assumed to contain regulated amounts of asbestos:

- Previous reports indicate the presence of asbestos-containing pipe/elbow/fitting insulation in select laboratories and in the Corridor ceiling plenums of the 1950's Wing. Grey cement compound, "aircell", and layered cardboard wrap (anti-sweat) insulation, which is assumed asbestos-containing was observed in the Corridors and some laboratories surveyed. This insulation was generally in good condition and no debris was noted.

Bulk sampling and subsequent laboratory analysis, visual observations, or historical reports have determined that the following non-friable materials contain regulated amounts of asbestos:

- Brown Mastic on Exhaust Manifold Unit in the Mechanical Penthouse (1950), Enclosed Roof Area contains 2.54% Chrysotile Asbestos.
- Black Tar on Concrete Pad beneath Duct Inside Exhaust Manifold Unit in the Mechanical Penthouse (1950), Enclosed Roof Area contains 22.91% Chrysotile Asbestos.

4. BENZENE: Not identified
5. COKE OVEN EMISSIONS: Not identified
6. ETHYLENE OXIDE: Not Identified
7. ISOCYANATES: Not Identified

8. LEAD: **Identified**

The following paints contain detectable concentrations of lead, and concentrations above the limit of 90 ppm of the *Canada Consumer Product Safety Act*:

- White paint on the Booster Exhaust Stack in the Mechanical Penthouse (1950), Enclosed Roof Area contains 1,330 ppm lead

Given the vintage of the building, all paints and surface coatings, throughout the project areas shall be assumed to contain detectable concentrations of lead, unless specific bulk sampling and laboratory analysis confirms otherwise.

9. MERCURY: **Identified**

The presence of mercury is suspected within the following areas:

- Fluorescent light fixtures containing fluorescent light tubes were observed throughout the building. Fluorescent light tubes contain mercury in a vapour form and in the phosphor coating on the lamp tube.

10. SILICA: **Identified**

Free crystalline silica shall be assumed to be present in the following materials:

- Concrete and cement materials;
- Plaster; and,
- Ceiling tiles.

11. VINYL CHLORIDE MONOMER: Not Identified

12. POLYCHLORINATED BIPHENYLS (PCBs): Not Identified

13. MOULD: Not Identified

14. HALOCARBONS: Not Identified

15. OTHER HAZARDOUS MATERIALS: **Identified**

The fumehoods have been used for exhausting acid/base/solvent chemicals. It is reported that the hoods were not used for Perchloric acid.

All surfaces of the fumehood and ducting servicing the fumehood shall be considered impacted by chemical residue.

Some fumehoods may also have been, or are being, used for work with radioactive materials.

A minor accumulation (less than a square metre) of bird droppings were present on the exhaust manifold housing connecting to the booster exhaust in the Mechanical Penthouse (1950), Enclosed Roof Area.

1.5 RECOMMENDATIONS

1.5.1 ASBESTOS

All work must be done in accordance with *O.Reg 278/05* (as amended).

1. The disturbance of ACMs on construction and demolition projects in the province of Ontario is governed by *O.Reg 278/05*, as amended. This regulation classifies all asbestos disturbances as Low Risk (Type 1), Moderate Risk (Type 2), or High Risk (Type 3), each of which has defined precautionary measures. All asbestos materials are subject to specific handling and disposal precautions, and must be removed prior to demolition. The Ontario Ministry of Labour (MoL) must be notified of any project involving removal of more than a minor amount (e.g. typically 1 square metre) of friable asbestos material.
2. Identified friable ACMs (pipe/elbow/fitting insulation if required to accommodate the scope of work for the project) require a minimum of Type 2 abatement procedures under Ontario Regulation 278/05, as amended, when disturbing/removing/repairing one (1) square metre or less of the material. Should demolition, disturbance, or repair be required of more than one (1) square metre of friable ACM, Type 3 abatement procedures are required. It should be noted that the removal of an unlimited quantity of piping insulation can be completed using Type 2 glovebag procedures, provided that the application of the glovebag does not result in the release of asbestos fibres (e.g. from damaged fittings) and that the glovebag seal can be maintained throughout the removal process.
3. Type 1 work procedures can be used for the removal of non-friable materials (caulking/mastic), provided that the material can be wetted and removed using only non-powered hand tools. If these conditions cannot be met, then more stringent (e.g., Type 2 or Type 3) procedures are necessary.
4. Disposal of asbestos waste must be done in accordance with "General – Waste Management" O.Reg 347/90 (as amended) under the Ontario Environmental Protection Act and the federal Transportation of Dangerous Goods Act. The waste must be disposed at a licensed waste disposal site. Proper notification must be issued to the Departmental Representative prior to transportation of waste.

1.5.2 LEAD

1. Follow recommendations provided in the Ontario Ministry of Labour (MoL) Guideline entitled "Guideline: Lead on Construction Projects". This guideline classifies all lead disturbances as Type 1, Type 2a, Type 2b, Type 3a or Type 3b work, and assigns different levels of respiratory protection and work procedures for each classification.
2. Work procedures and personal protective equipment must be used to ensure that workers are not exposed to airborne lead levels that exceed the TWAEEL of 0.05 milligram per cubic metre (mg/m³) prescribed by O.Reg 490/09.
3. Even at low concentrations, there may be a potential for exposure to high concentrations of lead depending on the activities performed that disturb the lead-containing materials. At low lead concentrations, conducting a risk assessment to assess the potential for exposure is required to determine the need to follow precautionary measures.
4. Disposal of construction waste containing lead must be done in accordance with O.Reg 347/90 – General Waste Management, as amended, under the Ontario Environmental Protection Act and the federal Transportation of Dangerous Goods Act. The classification of the waste is dependent upon the result(s) of leachate test(s). The waste can be classified as "hazardous, "non-hazardous" or "registerable solid waste" depending on the results of the leachate test.

1.5.3 MERCURY

1. All work involving disturbance of mercury-containing equipment must be done in accordance with O.Reg 490/09.
2. Follow recommendations provided in the MoL Guideline entitled "The Safe Handling of Mercury: A Guide for the Construction Industry". This document provides advice on how to reduce the risk of mercury exposure, and outlines clean-up methods for spills.
3. When removal of fluorescent light tubes is required, the tubes should be removed intact from the fixtures. Other sources of liquid mercury should be removed intact to prevent worker exposure.
4. Disposal of waste containing mercury must be done in accordance with "General – Waste Management" O.Reg 347/90 (as amended) under the Ontario Environmental Protection Act and the federal Transportation of Dangerous Goods Act.

1.5.4 SILICA

1. Comply with Ontario Regulations O.Reg 490/09 when performing works that may disturb silica-containing materials. The regulation provides requirements for allowable exposure levels.
2. Silica dust can be generated through such processes as blasting, grinding, crushing, and sandblasting silica-containing material. Since silica is present in select materials within the project area, appropriate respiratory protection and ventilation must be donned during the demolition and modifications of these structures.
3. Follow recommendations provided in the MoL Guideline entitled "Guideline: Silica on Construction Projects". This document classifies all silica disturbances as Type 1, Type 2 or Type 3 work, and assigns different levels of respiratory protection and work procedures for each classification. These work procedures should be followed when performing work involving the disturbance of silica-containing materials.

1.5.5 OTHER HAZARDOUS MATERIALS - CHEMICALS (FUMEHOODS)

1. As a precaution, dermal protection such as chemical resistant gloves, coveralls, etc. should be used when working on internal fumehood/exhaust duct components.
2. A fumehood use inventory for the facility should be reviewed to determine if there is/has been any radioactivity material use within fumehoods being disturbed as part of the project.

1.5.6 BIRD DROPPINGS

1. Due to the health concern of mycotic organisms inhabiting avian fecal matter, it is recommended that disturbance avian/animal fecal matter and nesting materials (where present) be performed following the appropriate work procedures given in the document Mould Guidelines for the Canadian Construction Industry CCA 82-2004 published by the Canadian Construction Association (CCA 82-2004).
2. Disturbance shall avoid cross-contamination of unaffected areas. Disposal of waste should be performed in accordance with local, municipal, provincial, and/or federal jurisdictions having authority.

2.0 PRODUCTS

Not used

3.0 EXECUTION

Not used

END OF SECTION

Part 1 General**1.1 ADMINISTRATIVE**

- .1 Submit to Departmental Representative submittals listed for review. Submit promptly and in orderly sequence to not cause delay in Work. Failure to submit in ample time is not considered sufficient reason for extension of Contract Time and no claim for extension by reason of such default will be allowed.
- .2 Do not proceed with Work affected by submittal until review is complete.
- .3 Present shop drawings, product data, samples and mock-ups in SI Metric units.
- .4 Where items or information is not produced in SI Metric units converted values are acceptable.
- .5 Review submittals prior to submission to Departmental Representative. This review represents that necessary requirements have been determined and verified, or will be, and that each submittal has been checked and co-ordinated with requirements of Work and Contract Documents. Submittals not stamped, signed, dated and identified as to specific project will be returned without being examined and considered rejected.
- .6 Notify Departmental Representative, in writing at time of submission, identifying deviations from requirements of Contract Documents stating reasons for deviations.
- .7 Verify field measurements and affected adjacent Work are co-ordinated.
- .8 Contractor's responsibility for errors and omissions in submission is not relieved by Departmental Representative's review of submittals.
- .9 Contractor's responsibility for deviations in submission from requirements of Contract Documents is not relieved by Departmental Representative review.
- .10 Keep one reviewed copy of each submission on site.

1.2 SHOP DRAWINGS AND PRODUCT DATA

- .1 Submissions shall include:
 - .1 Date and revision dates.
 - .2 Project title and number.
 - .3 Name and address of:
 - .1 Subcontractor.
 - .2 Supplier.
 - .3 Manufacturer.
 - .4 Contractor's stamp, signed by Contractor's authorized representative certifying approval of submissions, verification of field measurements and compliance with Contract Documents.
 - .5 Details of appropriate portions of Work as applicable:
 - .1 Fabrication.
 - .2 Layout, showing dimensions, including identified field dimensions, and clearances.
 - .3 Setting or erection details.
 - .4 Capacities.
 - .5 Performance characteristics.
 - .6 Standards.
 - .7 Operating weight.
 - .8 Wiring diagrams.
 - .9 Single line and schematic diagrams.
 - .10 Relationship to adjacent work.
- .2 After Departmental Representative's review, distribute copies.

- .3 Submit electronic copy of shop drawings for each requirement requested in specification Sections and as Departmental Representative may reasonably request.
- .4 Submit electronic copies of Operation and Maintenance Data for requirements requested in specification Sections and as requested by Departmental Representative.
- .5 Delete information not applicable to project.
- .6 Supplement standard information to provide details applicable to project.
- .7 If upon review by Departmental Representative, no errors or omissions are discovered or if only minor corrections are made, copies will be returned and fabrication and installation of Work may proceed. If shop drawings are rejected, noted copy will be returned and resubmission of corrected shop drawings, through same procedure indicated above, must be performed before fabrication and installation of Work may proceed.
- .8 The review of shop drawings is for sole purpose of ascertaining conformance with general concept.
 - .1 This review shall not mean that Departmental Representative approves detail design inherent in shop drawings, responsibility for which shall remain with Contractor submitting same, and such review shall not relieve Contractor of responsibility for errors or omissions in shop drawings or of responsibility for meeting requirements of construction and Contract Documents.
 - .2 Without restricting generality of foregoing, Contractor is responsible for dimensions to be confirmed and correlated at job site, for information that pertains solely to fabrication processes or to techniques of construction and installation and for co-ordination of Work of sub-trades.

Part 2 Products**2.1 NOT USED**

- .1 Not Used.

Part 3 Execution**3.1 NOT USED**

- .1 Not Used.

END OF SECTION

Part 1 General**1.1 REFERENCES**

- .1 Canada Labour Code, Part 2, Canada Occupational Safety and Health Regulations
- .2 Province of Ontario
 - .1 Occupational Health and Safety Act and Regulations for Construction Projects, R.S.O. 1990, c.0.1, as amended and O. Reg. 213/91 as amended - Updated 2005.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit site-specific Health and Safety Plan: Within 7 days after date of Notice to Proceed and prior to commencement of Work. Health and Safety Plan must include:
 - .1 Results of site specific safety hazard assessment.
 - .2 Results of safety and health risk or hazard analysis for site tasks and operation found in work plan.
- .3 Submit one (1) copy of Contractor's authorized representative's work site health and safety inspection reports to Departmental Representative weekly.
- .4 Submit copies of reports or directions issued by Federal and Provincial health and safety inspectors.
- .5 Submit copies of incident and accident reports.
- .6 Submit WHMIS MSDS - Material Safety Data Sheets.
- .7 Departmental Representative will review Contractor's site-specific Health and Safety Plan and provide comments to Contractor within 2 days after receipt of plan. Revise plan as appropriate and resubmit plan to Departmental Representative within 2 days after receipt of comments from Departmental Representative.
- .8 Departmental Representative's review of Contractor's final Health and Safety plan should not be construed as approval and does not reduce the Contractor's overall responsibility for construction Health and Safety.
- .9 Medical Surveillance: where prescribed by legislation, regulation or safety program, submit certification of medical surveillance for site personnel prior to commencement of Work, and submit additional certifications for any new site personnel to Departmental Representative.
- .10 On-site Contingency and Emergency Response Plan: address standard operating procedures to be implemented during emergency situations.

1.3 FILING OF NOTICE

- .1 File Notice of Project with Provincial authorities prior to beginning of Work.
- .2 Contractor shall agree to install proper site separation and identification in order to maintain time and space at all times throughout life of project.

1.4 SAFETY ASSESSMENT

- .1 Perform site specific safety hazard assessment related to project.

1.5 MEETINGS

- .1 Schedule and administer Health and Safety meeting with Departmental Representative prior to commencement of Work.

1.6 GENERAL REQUIREMENTS

- .1 Develop written site-specific Health and Safety Plan based on hazard assessment prior to beginning site Work and continue to implement, maintain, and enforce plan until final demobilization from site. Health and Safety Plan must address project specifications.
- .2 Departmental Representative may respond in writing, where deficiencies or concerns are noted and may request re-submission with correction of deficiencies or concerns.

1.7 RESPONSIBILITY

- .1 Be responsible for health and safety of persons on site, safety of property on site and for protection of persons adjacent to site and environment to extent that they may be affected by conduct of Work.
- .2 Contractor will be responsible and assume the role Constructor as described in the Ontario Occupational Health and Safety Act and Regulations for Construction Projects.
- .3 Comply with and enforce compliance by employees with safety requirements of Contract Documents, applicable federal, provincial, territorial and local statutes, regulations, and ordinances, and with site-specific Health and Safety Plan.

1.8 COMPLIANCE REQUIREMENTS

- .1 Comply with Ontario Occupational Health and Safety Act, R.S.O. 1990, c. 0.1, Ontario Regulations for Construction Projects, O. Reg. 213/91 and PSPC Standard on Construction Occupational Health and Safety.

1.9 UNFORSEEN HAZARDS

- .1 When unforeseen or peculiar safety-related factor, hazard, or condition occur during performance of Work, follow procedures in place for Employee's Right to Refuse Work in accordance with Acts and Regulations of Province having jurisdiction and advise Departmental Representative verbally and in writing.

1.10 POSTING OF DOCUMENTS

- .1 Ensure applicable items, articles, notices and orders are posted in conspicuous location on site in accordance with Acts and Regulations of Province having jurisdiction, and in consultation with Departmental Representative.

1.11 CORRECTION OF NON-COMPLIANCE

- .1 Immediately address health and safety non-compliance issues identified by authority having jurisdiction or by Departmental Representative.
- .2 Provide Departmental Representative with written report of action taken to correct non-compliance of health and safety issues identified.
- .3 Departmental Representative may stop Work if non-compliance of health and safety regulations is not corrected.

1.12 POWDER ACTUATED DEVICES

- .1 Use powder actuated devices only after receipt of written permission from Departmental Representative.

1.13 WORK STOPPAGE

- .1 Give precedence to safety and health of public and site personnel and protection of environment over cost and schedule considerations for Work.

Part 2 Products

2.1 NOT USED

- .1 Not used.

Part 3 Execution

3.1 NOT USED

- .1 Not used.

END OF SECTION

Part 1 GENERAL**1.1 REFERENCES**

- .1 Within text of each specifications section, reference may be made to reference standards.
- .2 Conform to these reference standards, in whole or in part as specifically requested in specifications.
- .3 If there is question as to whether products or systems are in conformance with applicable standards, Departmental Representative reserves right to have such products or systems tested to prove or disprove conformance.
- .4 Cost for such testing will be born by Departmental Representative in event of conformance with Contract Documents or by Contractor in event of non-conformance.

1.2 QUALITY

- .1 Products, materials, equipment and articles incorporated in Work shall be new, not damaged or defective, and of best quality for purpose intended. If requested, furnish evidence as to type, source and quality of products provided.
- .2 Procurement policy is to acquire, in cost effective manner, items containing highest percentage of recycled and recovered materials practicable consistent with maintaining satisfactory levels of competition. Make reasonable efforts to use recycled and recovered materials and in otherwise utilizing recycled and recovered materials in execution of work.
- .3 Defective products, whenever identified prior to completion of Work, will be rejected, regardless of previous inspections. Inspection does not relieve responsibility, but is precaution against oversight or error. Remove and replace defective products at own expense and be responsible for delays and expenses caused by rejection.
- .4 Should disputes arise as to quality or fitness of products, decision rests strictly with Departmental Representative based upon requirements of Contract Documents.
- .5 Unless otherwise indicated in specifications, maintain uniformity of manufacture for any particular or like item throughout building.
- .6 Permanent labels, trademarks and nameplates on products are not acceptable in prominent locations, except where required for operating instructions, or when located in mechanical or electrical rooms.

1.3 STORAGE, HANDLING AND PROTECTION

- .1 Handle and store products in manner to prevent damage, adulteration, deterioration and soiling and in accordance with manufacturer's instructions when applicable.
- .2 Store packaged or bundled products in original and undamaged condition with manufacturer's seal and labels intact. Do not remove from packaging or bundling until required in Work.
- .3 Store products subject to damage from weather in weatherproof enclosures.
- .4 Remove and replace damaged products at own expense and to satisfaction of Departmental Representative.

1.4 TRANSPORTATION

- .1 Pay costs of transportation of products required in performance of Work.

1.5 MANUFACTURER'S INSTRUCTIONS

- .1 Unless otherwise indicated in specifications, install or erect products in accordance with manufacturer's instructions. Do not rely on labels or enclosures provided with products. Obtain written instructions directly from manufacturers.
- .2 Notify Departmental Representative in writing, of conflicts between specifications and manufacturer's instructions, so that Departmental Representative will establish course of action.
- .3 Improper installation or erection of products, due to failure in complying with these requirements, authorizes Departmental Representative to require removal and re-installation at no increase in Contract Price or Contract Time.

1.6 QUALITY OF WORK

- .1 Ensure Quality of Work is of highest standard, executed by workers experienced and skilled in respective duties for which they are employed. Immediately notify Departmental Representative if required Work is such as to make it impractical to produce required results.
- .2 Decisions as to standard or fitness of Quality of Work in cases of dispute rest solely with Departmental Representative, whose decision is final.

1.7 CO-ORDINATION

- .1 Ensure co-operation of workers in laying out Work. Maintain efficient and continuous supervision.
- .2 Be responsible for coordination and placement of openings, sleeves and accessories.

1.8 CONCEALMENT

- .1 In finished areas conceal pipes, ducts and wiring in floors, walls and ceilings, except where indicated otherwise.
- .2 Before installation inform Departmental Representative if there is interference. Install as directed by Departmental Representative.

1.9 PROTECTION OF WORK IN PROGRESS

- .1 Prevent overloading of parts of building. Do not cut, drill or sleeve load bearing structural member, unless specifically indicated without written approval of Departmental Representative.

1.10 EXISTING UTILITIES

- .1 When breaking into or connecting to existing services or utilities, execute Work at times directed by local governing authorities, with minimum of disturbance to Work, and/or building occupants and pedestrian and vehicular traffic.
- .2 Protect, relocate or maintain existing active services. When services are encountered, cap off in manner approved by authority having jurisdiction. Stake and record location of capped service.

Part 2 Products**2.1 NOT USED**

- .1 Not Used.

Part 3	Execution
3.1	NOT USED
.1	Not Used.

END OF SECTION

Part 1 General**1.1 PROJECT CLEANLINESS**

- .1 Maintain Work in tidy condition, free from accumulation of waste products and debris, other than that caused by Owner or other Contractors.
- .2 Remove waste materials from site at daily regularly scheduled times or dispose of as directed by Departmental Representative. Do not burn waste materials on site, unless approved by Departmental Representative.
- .3 Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .4 Provide on-site containers for collection of waste materials and debris.
- .5 Provide and use marked separate bins for recycling.
- .6 Provide adequate ventilation during use of volatile or noxious substances. Use of building ventilation systems is not permitted for this purpose.
- .7 Use only cleaning materials recommended by manufacturer of surface to be cleaned, and as recommended by cleaning material manufacturer.
- .8 Schedule cleaning operations so that resulting dust, debris and other contaminants will not contaminate building systems.

1.2 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate waste materials for reuse and recycling.

Part 2 Products**2.1 NOT USED**

- .1 Not Used.

Part 3 Execution**3.1 NOT USED**

- .1 Not Used.

END OF SECTION

Part 1 General**1.1 ACTION AND INFORMATIONAL SUBMITTALS**

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Two weeks prior to Substantial Performance of the Work, submit to the Departmental Representative, electronic final copy of operating and maintenance manuals in English.
- .3 Provide spare parts, maintenance materials and special tools of same quality and manufacture as products provided in Work.
- .4 Provide evidence, if requested, for type, source and quality of products supplied.

1.2 FORMAT

- .1 Organize data as instructional manual.

1.3 CONTENTS - PROJECT RECORD DOCUMENTS

- .1 Table of Contents for Each Volume: provide title of project;
 - .1 Date of submission;
 - .2 Names addresses, and telephone numbers of Consultant and Contractor with name of responsible parties;
 - .3 Schedule of products and systems, indexed to content of volume.
- .2 For each product or system:
 - .1 List names, addresses and telephone numbers of subcontractors and suppliers, including local source of supplies and replacement parts.
- .3 Product Data: mark each sheet to identify specific products and component parts, and data applicable to installation; delete inapplicable information.
- .4 Drawings: supplement product data to illustrate relations of component parts of equipment and systems, to show control and flow diagrams.

1.4 AS -BUILT DOCUMENTS AND SAMPLES

- .1 Maintain, at site for Departmental Representative one record copy of:
 - .1 Contract Drawings.
 - .2 Specifications.
 - .3 Addenda.
 - .4 Change Orders and other modifications to Contract.
 - .5 Reviewed shop drawings, product data, and samples.
 - .6 Field test records.
 - .7 Inspection certificates.
 - .8 Manufacturer's certificates.
- .2 Store record documents and samples in field office apart from documents used for construction.
 - .1 Provide files, racks, and secure storage.
- .3 Label record documents and file in accordance with Section number listings in List of Contents of this Project Manual.
 - .1 Label each document "PROJECT RECORD" in neat, large, printed letters.
- .4 Maintain record documents in clean, dry and legible condition.
 - .1 Do not use record documents for construction purposes.
- .5 Keep record documents and samples available for inspection by Departmental Representative.

1.5 RECORDING INFORMATION ON PROJECT RECORD DOCUMENTS

- .1 Record information on set of drawings, provided by Departmental Representative.
- .2 Use felt tip marking pens, maintaining separate colours for each major system, for recording information.
- .3 Record information concurrently with construction progress.
 - .1 Do not conceal Work until required information is recorded.
- .4 Contract Drawings and shop drawings: mark each item to record actual construction, including:
 - .1 Measured depths of elements of foundation in relation to finish first floor datum.
 - .2 Measured horizontal and vertical locations of underground utilities and appurtenances, referenced to permanent surface improvements.
 - .3 Measured locations of internal utilities and appurtenances, referenced to visible and accessible features of construction.
 - .4 Field changes of dimension and detail.
 - .5 Changes made by change orders.
 - .6 Details not on original Contract Drawings.
 - .7 References to related shop drawings and modifications.
- .5 Specifications: mark each item to record actual construction, including:
 - .1 Manufacturer, trade name, and catalogue number of each product actually installed, particularly optional items and substitute items.
 - .2 Changes made by Addenda and change orders.

1.6 EQUIPMENT AND SYSTEMS

- .1 For each item of equipment and each system include description of unit or system, and component parts.
 - .1 Give function, normal operation characteristics and limiting conditions.
 - .2 Include performance curves, with engineering data and tests, and complete nomenclature and commercial number of replaceable parts.
- .2 Include installed colour coded wiring diagrams.
- .3 Maintenance Requirements: include routine procedures and guide for trouble-shooting; disassembly, repair, and reassembly instructions; and alignment, adjusting, balancing, and checking instructions.
- .4 Provide servicing and lubrication schedule, and list of lubricants required.
- .5 Include manufacturer's printed operation and maintenance instructions.
- .6 Provide original manufacturer's parts list, illustrations, assembly drawings, and diagrams required for maintenance.
- .7 Provide Contractor's co-ordination drawings, with installed colour coded piping diagrams.
- .8 Provide charts of valve tag numbers, with location and function of each valve, keyed to flow and control diagrams.
- .9 Additional requirements: as specified in individual specification sections.

1.7 DELIVERY, STORAGE AND HANDLING

- .1 Store spare parts, maintenance materials, and special tools in manner to prevent damage or deterioration.
- .2 Store in original and undamaged condition with manufacturer's seal and labels intact.
- .3 Store components subject to damage from weather in weatherproof enclosures.
- .4 Store paints and freezable materials in a heated and ventilated room.

- .5 Remove and replace damaged products at own expense and for review by Departmental Representative.

1.8 WARRANTIES AND BONDS

- .1 Develop warranty management plan to contain information relevant to Warranties.
- .2 Submit warranty management plan, 30 days before planned pre-warranty conference, to Departmental Representative approval.
- .3 Warranty management plan to include required actions and documents to assure that Departmental Representative receives warranties to which it is entitled.
- .4 Provide plan in narrative form and contain sufficient detail to make it suitable for use by future maintenance and repair personnel.
- .5 Submit, warranty information made available during construction phase, to Departmental Representative for approval prior to each monthly pay estimate.
- .6 Respond in timely manner to oral or written notification of required construction warranty repair work.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION

Part 1 General**1.1 SUMMARY**

- .1 Acronyms:
 - .1 AFD - Alternate Forms of Delivery, service provider.
 - .2 BMM - Building Management Manual.
 - .3 Cx - Commissioning.
 - .4 EMCS - Energy Monitoring and Control Systems.
 - .5 O&M - Operation and Maintenance.
 - .6 PI - Product Information.
 - .7 PV - Performance Verification.
 - .8 TAB - Testing, Adjusting and Balancing.

1.2 GENERAL

- .1 Cx is a planned program of tests, procedures and checks carried out systematically on systems and integrated systems of the finished Project. Cx is performed after systems and integrated systems are completely installed, functional and Contractor's Performance Verification responsibilities have been completed and approved. Objectives:
 - .1 Verify installed equipment, systems and integrated systems operate in accordance with Contract Documents and design criteria and intent.
 - .2 Ensure appropriate documentation is compiled into the BMM.
 - .3 Effectively train O&M staff.
- .2 Contractor assists in Cx process, operating equipment and systems, troubleshooting and making adjustments as required.
 - .1 Systems to be operated at full capacity under various modes to determine if they function correctly and consistently at peak efficiency. Systems to be interactively with each other as intended in accordance with Contract Documents and design criteria.
 - .2 During these checks, adjustments to be made to enhance performance to meet environmental or user requirements.
- .3 Design Criteria: as per client's requirements or determined by designer. To meet Project functional and operational requirements.

1.3 COMMISSIONING OVERVIEW

- .1 Section 01 91 31 - Commissioning (Cx) Plan.
- .2 For Cx responsibilities refer to Section 01 91 31 - Commissioning (Cx) Plan.
- .3 Cx to be a line item of Contractor's cost breakdown.
- .4 Cx activities supplement field quality and testing procedures described in relevant technical sections.
- .5 Cx is conducted in concert with activities performed during stage of project delivery. Cx identifies issues in Planning and Design stages which are addressed during Construction and Cx stages to ensure the built systems are constructed and proven to operate satisfactorily under weather, environmental and occupancy conditions to meet functional and operational requirements. Cx activities includes transfer of critical knowledge to facility operational personnel.
- .6 Departmental Representative will issue Interim Acceptance Certificate when:
 - .1 Completed Cx documentation has been received, reviewed for suitability and approved by Departmental Representative.
 - .2 Equipment, components and systems have been commissioned.
 - .3 O&M training has been completed.

1.4 NON-CONFORMANCE TO PERFORMANCE VERIFICATION REQUIREMENTS

- .1 Should equipment, system components, and associated controls be incorrectly installed or malfunction during Cx, correct deficiencies, re-verify equipment and components within the unfunctional system, including related systems as deemed required by Departmental Representative, to ensure effective performance.
- .2 Costs for corrective work, additional tests, inspections, to determine acceptability and proper performance of such items to be borne by Contractor. Above costs to be in form of progress payment reductions or hold-back assessments.

1.5 PRE-CX REVIEW

- .1 Before Construction:
 - .1 Review Contract Documents, confirm by writing to Departmental Representative.
 - .1 Adequacy of provisions for Cx.
 - .2 Aspects of design and installation pertinent to success of Cx.
- .2 During Construction:
 - .1 Co-ordinate provision, location and installation of provisions for Cx.
- .3 Before start of Cx:
 - .1 Have completed Cx Plan up-to-date.
 - .2 Ensure installation of related components, equipment, sub-systems, systems is complete.
 - .3 Fully understand Cx requirements and procedures.
 - .4 Have Cx documentation shelf-ready.
 - .5 Understand completely design criteria and intent and special features.
 - .6 Submit complete start-up documentation to Departmental Representative.
 - .7 Have Cx schedules up-to-date.
 - .8 Ensure systems have been cleaned thoroughly.
 - .9 Complete TAB procedures on systems, submit TAB reports to Departmental Representative for review and approval.
 - .10 Ensure "As-Built" system schematics are available.
- .4 Inform Departmental Representative in writing of discrepancies and deficiencies on finished works.

1.6 CONFLICTS

- .1 Report conflicts between requirements of this section and other sections to Departmental Representative before start-up and obtain clarification.
- .2 Failure to report conflict and obtain clarification will result in application of most stringent requirement.

1.7 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
 - .1 Submit no later than 4 weeks after award of Contract:
 - .1 Name of Contractor's Cx agent.
 - .2 Draft Cx documentation.
 - .3 Preliminary Cx schedule.
 - .2 Request in writing to Departmental Representative for changes to submittals and obtain written approval at least 8 weeks prior to start of Cx.
 - .3 Submit proposed Cx procedures to Departmental Representative where not specified and obtain written approval at least 8 weeks prior to start of Cx.
 - .4 Provide additional documentation relating to Cx process required by Departmental Representative.

1.8 COMMISSIONING DOCUMENTATION

- .1 Refer to Section 01 91 33 - Commissioning (Cx) Forms: Installation Check Lists and Product Information (PI) / Performance Verification (PV) Forms for requirements and instructions for use.
- .2 Departmental Representative to review and approve Cx documentation.
- .3 Provide completed and approved Cx documentation to Departmental Representative.

1.9 COMMISSIONING SCHEDULE

- .1 Provide detailed Cx schedule as part of construction schedule.
- .2 Provide adequate time for Cx activities prescribed in technical sections and commissioning sections including:
 - .1 Approval of Cx reports.
 - .2 Verification of reported results.
 - .3 Repairs, retesting, re-commissioning, re-verification.
 - .4 Training.

1.10 COMMISSIONING MEETINGS

- .1 Convene Cx meetings following project meetings.
- .2 Purpose: to resolve issues, monitor progress, identify deficiencies, relating to Cx.
- .3 Continue Cx meetings on regular basis until commissioning deliverables have been addressed.
- .4 At 60% construction completion stage. Departmental Representative to call a separate Cx scope meeting to review progress, discuss schedule of equipment start-up activities and prepare for Cx. Issues at meeting to include:
 - .1 Review duties and responsibilities of Contractor and subcontractors, addressing delays and potential problems.
 - .2 Determine the degree of involvement of trades and manufacturer's representatives in the commissioning process.
- .5 Thereafter Cx meetings to be held until project completion and as required during equipment start-up and functional testing period.
- .6 Meeting will be chaired by Departmental Representative, who will record and distribute minutes.
- .7 Ensure subcontractors and relevant manufacturer representatives are present at 60% and subsequent Cx meetings and as required.

1.11 STARTING AND TESTING

- .1 Contractor assumes liabilities and costs for inspections. Including disassembly and re-assembly after approval, starting, testing and adjusting, including supply of testing equipment.

1.12 WITNESSING OF STARTING AND TESTING

- .1 Provide 14 days notice prior to commencement.
- .2 Departmental Representative to witness of start-up and testing.
- .3 Contractor's Cx Agent to be present at tests performed and documented by sub-trades, suppliers and equipment manufacturers.

1.13 MANUFACTURER'S INVOLVEMENT

- .1 Obtain manufacturers installation, start-up and operations instructions prior to start-up of components, equipment and systems and review with Departmental Representative.
 - .1 Compare completed installation with manufacturer's published data, record discrepancies, and review with manufacturer.
 - .2 Modify procedures detrimental to equipment performance and review same with manufacturer before start-up.
- .2 Integrity of warranties:
 - .1 Use manufacturer's trained start-up personnel where specified elsewhere in other divisions or required to maintain integrity of warranty.
 - .2 Verify with manufacturer that testing as specified will not void warranties.
- .3 Qualifications of manufacturer's personnel:
 - .1 Experienced in design, installation and operation of equipment and systems.
 - .2 Ability to interpret test results accurately.
 - .3 To report results in clear, concise, logical manner.

1.14 PROCEDURES

- .1 Verify that equipment and systems are complete, clean, and operating in normal and safe manner prior to conducting start-up, testing and Cx.
- .2 Conduct start-up and testing in following distinct phases:
 - .1 Included in delivery and installation:
 - .1 Verification of conformity to specification, approved shop drawings and completion of PI report forms.
 - .2 Visual inspection of quality of installation.
 - .2 Start-up: follow accepted start-up procedures.
 - .3 Operational testing: document equipment performance.
 - .4 System PV: include repetition of tests after correcting deficiencies.
 - .5 Post-substantial performance verification: to include fine-tuning.
- .3 Correct deficiencies and obtain approval from Departmental Representative after distinct phases have been completed and before commencing next phase.
- .4 Document require tests on approved PV forms.
- .5 Failure to follow accepted start-up procedures will result in re-evaluation of equipment by an independent testing agency selected by Departmental Representative. If results reveal that equipment start-up was not in accordance with requirements, and resulted in damage to equipment, implement following:
 - .1 Minor equipment/systems: implement corrective measures approved by Departmental Representative.
 - .2 Major equipment/systems: if evaluation report concludes that damage is minor, implement corrective measures approved by Departmental Representative.
 - .3 If evaluation report concludes that major damage has occurred, Departmental Representative shall reject equipment.
 - .1 Rejected equipment to be remove from site and replace with new.
 - .2 Subject new equipment/systems to specified start-up procedures.

1.15 START-UP DOCUMENTATION

- .1 Assemble start-up documentation and submit to Departmental Representative for approval before commencement of commissioning.
- .2 Start-up documentation to include:
 - .1 Factory and on-site test certificates for specified equipment.
 - .2 Pre-start-up inspection reports.

- .3 Signed installation/start-up check lists.
- .4 Start-up reports,
- .5 Step-by-step description of complete start-up procedures, to permit Departmental Representative to repeat start-up at any time.

1.16 OPERATION AND MAINTENANCE OF EQUIPMENT AND SYSTEMS

- .1 After start-up, operate and maintain equipment and systems as directed by equipment/system manufacturer.
- .2 With assistance of manufacturer develop written maintenance program and submit Departmental Representative for approval before implementation.
- .3 Operate and maintain systems for length of time required for commissioning to be completed.
- .4 After completion of commissioning, operate and maintain systems until issuance of certificate of interim acceptance.

1.17 TEST RESULTS

- .1 If start-up, testing and/or PV produce unacceptable results, repair, replace or repeat specified starting and/or PV procedures until acceptable results are achieved.
- .2 Provide manpower and materials, assume costs for re-commissioning.

1.18 START OF COMMISSIONING

- .1 Notify Departmental Representative at least 21 days prior to start of Cx.
- .2 Start Cx after elements of building affecting start-up and performance verification of systems have been completed.

1.19 INSTRUMENTS / EQUIPMENT

- .1 Submit to Departmental Representative for review and approval:
 - .1 Complete list of instruments proposed to be used.
 - .2 Listed data including, serial number, current calibration certificate, calibration date, calibration expiry date and calibration accuracy.
- .2 Provide the following equipment as required:
 - .1 2-way radios.
 - .2 Ladders.
 - .3 Equipment as required to complete work.

1.20 COMMISSIONING PERFORMANCE VERIFICATION

- .1 Carry out Cx:
 - .1 Under actual operating conditions, over entire operating range, in all modes.
 - .2 On independent systems and interacting systems.
- .2 Cx procedures to be repeatable and reported results are to be verifiable.
- .3 Follow equipment manufacturer's operating instructions.
- .4 EMCS trending to be available as supporting documentation for performance verification.

1.21 WITNESSING COMMISSIONING

- .1 Departmental Representative to witness activities and verify results.

1.22 EXTENT OF VERIFICATION

- .1 Laboratory areas:
 - .1 Provide manpower and instrumentation to verify up to 100% of reported results.
- .2 Number and location to be at discretion of Departmental Representative.
- .3 Conduct tests repeated during verification under same conditions as original tests, using same test equipment, instrumentation.
- .4 Review and repeat commissioning of systems if inconsistencies found in more than 20% of reported results.
- .5 Perform additional commissioning until results are acceptable to Departmental Representative.

1.23 REPEAT VERIFICATIONS

- .1 Assume costs incurred by Departmental Representative for third and subsequent verifications where:
 - .1 Verification of reported results fail to receive Departmental Representative's approval.
 - .2 Repetition of second verification again fails to receive approval.
 - .3 Departmental Representative deems Contractor's request for second verification was premature.

1.24 SUNDRY CHECKS AND ADJUSTMENTS

- .1 Make adjustments and changes which become apparent as Cx proceeds.
- .2 Perform static and operational checks as applicable and as required.

1.25 DEFICIENCIES, FAULTS, DEFECTS

- .1 Correct deficiencies found during start-up and Cx to satisfaction of Departmental Representative.
- .2 Report problems, faults or defects affecting Cx to Departmental Representative in writing. Stop Cx until problems are rectified. Proceed with written approval from Departmental Representative.

1.26 COMPLETION OF COMMISSIONING

- .1 Upon completion of Cx leave systems in normal operating mode.
- .2 Except for warranty and seasonal verification activities specified in Cx specifications, complete Cx prior to issuance of Interim Certificate of Completion.
- .3 Cx to be considered complete when contract Cx deliverables have been submitted and accepted by Departmental Representative.

1.27 ACTIVITIES UPON COMPLETION OF COMMISSIONING

- .1 When changes are made to baseline components or system settings established during Cx process, provide updated Cx form for affected item.

1.28 TRAINING

- .1 In accordance with Section 01 91 41 - Commissioning (Cx) - Training.

1.29 OCCUPANCY

- .1 Cooperate fully with Departmental Representative during stages of acceptance and occupancy of facility.

1.30 INSTALLED INSTRUMENTATION

- .1 Use instruments installed under Contract for TAB and PV if:
 - .1 Accuracy complies with these specifications.
 - .2 Calibration certificates have been deposited with Departmental Representative.
- .2 Calibrated EMCS sensors may be used to obtain performance data provided that sensor calibration has been completed and accepted.

1.31 PERFORMANCE VERIFICATION TOLERANCES

- .1 Application tolerances:
 - .1 Specified range of acceptable deviations of measured values from specified values or specified design criteria. Except for special areas, to be within +/- 10% of specified values.
- .2 Instrument accuracy tolerances:
 - .1 To be of higher order of magnitude than equipment or system being tested.
- .3 Measurement tolerances during verification:
 - .1 Unless otherwise specified actual values to be within +/- 2% of recorded values.

1.32 OWNER'S PERFORMANCE TESTING

- .1 Performance testing of equipment or system by Departmental Representative will not relieve Contractor from compliance with specified start-up and testing procedures.

Part 2 Products**2.1 NOT USED**

- .1 Not Used.

Part 3 Execution**3.1 NOT USED**

- .1 Not Used.

END OF SECTION

Part 1 General**1.1 REFERENCE STANDARDS**

- .1 Public Works and Government Services Canada (PSPC)
 - .1 PSPC - Commissioning Guidelines CP.4 -3rd edition-03.

1.2 GENERAL

- .1 Provide fully functional systems:
 - .1 Systems, equipment and components meet user's functional requirements before date of acceptance, and operate consistently at peak efficiencies and within specified energy budgets under normal loads.
 - .2 Facility personnel have been fully trained in aspects of installed systems.
 - .3 Complete documentation relating to installed equipment and systems.
- .2 Term "Cx" in this section means "Commissioning".
- .3 Use this Cx Plan as master planning document for Cx:
 - .1 Outlines organization, scheduling, allocation of resources, documentation, pertaining to implementation of Cx.
 - .2 Communicates responsibilities of team members involved in Cx Scheduling, documentation requirements, and verification procedures.
 - .3 Sets out deliverables relating to O&M, process and administration of Cx.
 - .4 Describes process of verification of how built works meet design requirements.
 - .5 Produces a complete functional system prior to issuance of Certificate of Occupancy.
 - .6 Management tool that sets out scope, standards, roles and responsibilities, expectations, deliverables, and provides:
 - .1 Overview of Cx.
 - .2 General description of elements that make-up Cx Plan.
 - .3 Process and methodology for successful Cx.
- .4 Acronyms:
 - .1 Cx - Commissioning.
 - .2 BMM - Building Management Manual.
 - .3 EMCS - Energy Monitoring and Control Systems.
 - .4 MSDS - Material Safety Data Sheets.
 - .5 PI - Product Information.
 - .6 PV - Performance Verification.
 - .7 TAB - Testing, Adjusting and Balancing.
 - .8 WHMIS - Workplace Hazardous Materials Information System.
- .5 Commissioning terms used in this Section:
 - .1 Bumping: short term start-up to prove ability to start and prove correct rotation.
 - .2 Deferred Cx - Cx activities delayed for reasons beyond Contractor's control due to lack of occupancy, weather conditions, need for heating/cooling loads.

1.3 DEVELOPMENT OF CX PLAN

- .1 Cx Plan to be updated by Departmental Representative during construction to take into account:
 - .1 Approved shop drawings and product data.
 - .2 Approved changes to contract.
 - .3 Contractor's project schedule.
 - .4 Cx schedule.
 - .5 Contractor's, sub-contractor's, suppliers' requirements.
 - .6 Project construction team's and Cx team's requirements.

1.4 REFINEMENT OF CX PLAN

- .1 During construction phase, Cx Plan will be updated by Departmental Representative to include:
 - .1 Changes resulting from Client program modifications.
 - .2 Approved design and construction changes.

1.5 COMPOSITION, ROLES AND RESPONSIBILITIES OF CX TEAM

- .1 Departmental Representative to maintain overall responsibility for project and is sole point of contact between members of commissioning team.
- .2 Project Manager will select Cx Team consisting of following members:
 - .1 PSPC Design Quality Review Team: during construction, will conduct periodic site reviews to observe general progress.
 - .2 PSPC Quality Assurance Commissioning Manager: ensures Cx activities are carried out to ensure delivery of a fully operational project including:
 - .1 Review of Cx documentation from operational perspective.
 - .2 Review for performance, reliability, durability of operation, accessibility, maintainability, operational efficiency under conditions of operation.
 - .3 Protection of health, safety and comfort of occupants and O&M personnel.
 - .4 Monitoring of Cx activities, training, development of Cx documentation.
 - .5 Work closely with members of Cx Team.
 - .3 Departmental Representative is responsible for:
 - .1 Organizing Cx.
 - .2 Monitoring operations Cx activities.
 - .3 Witnessing, certifying accuracy of reported results.
 - .4 Witnessing and certifying TAB and other tests.
 - .5 Developing BMM.
 - .6 Updating Cx Plan.
 - .7 Ensuring implementation of final Cx Plan.
 - .8 Performing verification of performance of installed systems and equipment.
 - .9 Implementation of Training Plan.
 - .4 Construction Team: contractor, sub-contractors, suppliers and support disciplines, is responsible for construction/installation in accordance with Contract Documents, including:
 - .1 Testing.
 - .2 TAB.
 - .3 Performance of Cx activities.
 - .4 Delivery of training and Cx documentation.
 - .5 Assigning one person as point of contact with Consultant and PSPC Cx Manager for administrative and coordination purposes.
 - .5 Contractor's Cx agent implements specified Cx activities including:
 - .1 Demonstrations.
 - .2 Training.
 - .3 Testing.
 - .4 Preparation, submission of test reports.
 - .6 Property Manager: represents lead role in Operation Phase and onwards and is responsible for:
 - .1 Receiving facility.
 - .2 Day-To-Day operation and maintenance of facility.

1.6 CX PARTICIPANTS

- .1 Employ the following Cx participants to verify performance of equipment and systems:
 - .1 Installation contractor/subcontractor:
 - .1 Equipment and systems except as noted.
- .2 Equipment manufacturer: equipment specified to be installed and started by manufacturer.
 - .1 To include performance verification.
- .3 Specialist subcontractor: equipment and systems supplied and installed by specialist subcontractor.

- .4 Specialist Cx agency:
 - .1 Possessing specialist qualifications and installations providing environments essential to client's program but are outside scope or expertise of Cx specialists on this project.
- .5 Client: responsible for intrusion and access security systems.
- .6 Ensure that Cx participant:
 - .1 Could complete work within scheduled time frame.
- .7 Provide names of participants to Departmental Representative and details of instruments and procedures to be followed for Cx 3 weeks prior to starting date of Cx for review and approval.

1.7 EXTENT OF CX

- .1 Commission mechanical systems and associated equipment:
 - .1 HVAC and exhaust systems with both normal & emergency power:
 - .1 HVAC systems.
 - .2 General exhaust systems.
 - .3 Laboratory fume hoods and related systems.
- .2 Commission electrical systems and equipment:
 - .1 Low voltage below 750 V:
 - .1 Low voltage equipment.
 - .2 Low voltage distribution systems.
 - .3 Electronic data and communications information systems.

1.8 DELIVERABLES RELATING TO O&M PERSPECTIVES

- .1 General requirements:
 - .1 Compile English documentation.
 - .2 Documentation to be computer-compatible format ready for inputting for data management.
- .2 Provide deliverables:
 - .1 Warranties.
 - .2 Project record documentation.
 - .3 Inventory of spare parts, special tools and maintenance materials.
 - .4 Maintenance Management System (MMS) identification system used.
 - .5 WHMIS information.
 - .6 MSDS data sheets.
 - .7 Electrical Panel inventory containing detailed inventory of electrical circuitry for each panel board. Duplicate of inventory inside each panel.

1.9 DELIVERABLES RELATING TO THE CX PROCESS

- .1 General:
 - .1 Start-up, testing and Cx requirements, conditions for acceptance and specifications form part of relevant technical sections of these specifications.
- .2 Definitions:
 - .1 Cx as used in this section includes:
 - .1 Cx of components, equipment, systems, subsystems, and integrated systems.
 - .2 Factory inspections and performance verification tests.
- .3 Deliverables: provide:
 - .1 Start-up, pre-Cx activities and documentation for systems, and equipment.
 - .2 Completed installation checklists (ICL).
 - .3 Completed product information (PI) report forms.
 - .4 Completed performance verification (PV) report forms.
 - .5 Results of Performance Verification Tests and Inspections.

- .6 Description of Cx activities and documentation.
 - .7 Description of Cx of integrated systems and documentation.
 - .8 Training Plans.
 - .9 Cx Reports.
 - .10 Prescribed activities during warranty period.
- .4 Departmental Representative to witness and certify tests and reports of results provided to Departmental Representative.
 - .5 Departmental Representative to participate.

1.10 PRE-CX ACTIVITIES AND RELATED DOCUMENTATION

- .1 Items listed in this Cx Plan include the following:
 - .1 Pre-Start-Up inspections: by Departmental Representative prior to permission to start-up and rectification of deficiencies to Departmental Representative's satisfaction.
 - .2 Departmental Representative to use approved check lists.
- .2 Pre-Cx activities - MECHANICAL:
 - .1 HVAC equipment and systems:
 - .1 At this time, complete pre-start-up checks and complete relevant documentation.
 - .2 After equipment has been started, test related systems in conjunction with control systems on a system-by-system basis.
 - .3 Perform TAB on systems. TAB reports to be approved by Departmental Representative.
 - .2 EMCS:
 - .1 EMCS trending to be available as supporting documentation for performance verification.
 - .2 Perform point-by-point testing in parallel with start-up.
 - .3 Carry out point-by-point verification.
 - .4 Demonstrate performance of systems, to be witnessed by Departmental Representative prior to start of 30 day Final Acceptance Test period.
 - .5 Perform final Cx and operational tests during demonstration period and 30 day test period.
 - .6 Only additional testing after foregoing have been successfully completed to be "Off-Season Tests".

1.11 START-UP

- .1 Start-up components, equipment and systems.
- .2 Equipment manufacturer, supplier, installing specialist sub-contractor, as appropriate, to start-up, under Contractor's direction, following equipment, systems:
 - .1 Sash Retrofit Kit
 - .2 Controls.
- .3 Departmental Representative to monitor some of these start-up activities.
 - .1 Rectify start-up deficiencies to satisfaction of Departmental Representative.
- .4 Performance Verification (PV):
 - .1 Approved Cx Agent to perform.
 - .1 Repeat when necessary until results are acceptable to Departmental Representative.
 - .2 Use procedures modified generic procedures to suit project requirements.
 - .3 Departmental Representative to witness and certify reported results using approved PI and PV forms.
 - .4 Departmental Representative to approve completed PV reports and provide to Departmental Representative.
 - .5 Failure of randomly selected item shall result in rejection of PV report or report of system start-up and testing.

1.12 CX ACTIVITIES AND RELATED DOCUMENTATION

- .1 Perform Cx by specified Cx agency using procedures developed by Departmental Representative and approved by Departmental Representative.
- .2 Departmental Representative to monitor Cx activities.
- .3 Upon satisfactory completion, Cx agency performing tests to prepare Cx Report using approved PV forms.
- .4 Departmental Representative to witness, certify reported results of, Cx activities and forward to Departmental Representative.
- .5 Departmental Representative reserves right to verify a percentage of reported results at no cost to contract.

1.13 INSTALLATION CHECK LISTS (ICL)

- .1 Refer to Section 01 91 33 - Commissioning (Cx) Forms: Installation Check Lists and Product Information (PI)/Performance Verification (PV) Forms.

1.14 PRODUCT INFORMATION (PI) REPORT FORMS

- .1 Refer to Section 01 91 33 - Commissioning (Cx) Forms: Installation Check Lists and Product Information (PI)/Performance Verification (PV) Forms.

1.15 PERFORMANCE VERIFICATION (PV) REPORT

- .1 Refer to Section 01 91 33 - Commissioning (Cx) Forms: Installation Check Lists and Product Information (PI)/Performance Verification (PV) Forms.

1.16 CX SCHEDULES

- .1 Prepare detailed Cx Schedule and submit to Departmental Representative for review and approval same time as project Construction Schedule. Include:
 - .1 Milestones, testing, documentation, training and Cx activities of components, equipment, subsystems, systems and integrated systems, including:
 - .1 Design criteria, design intents.
 - .2 Pre-TAB review: before construction starts.
 - .3 Cx agents' credentials: 30 days before start of Cx.
 - .4 Cx procedures: 3 weeks after award of contract.
 - .5 Cx Report format: 3 weeks after contract award.
 - .6 Submission of list of instrumentation with relevant certificates: 7 days before start of Cx.
 - .7 Notification of intention to start TAB: 7 days before start of TAB.
 - .8 TAB: after successful start-up, correction of deficiencies and verification of normal and safe operation.
 - .9 Notification of intention to start Cx: 14 days before start of Cx.
 - .10 Notification of intention to start Cx of integrated systems: after Cx of related systems is completed 14 days before start of integrated system Cx.
 - .11 Identification of deferred Cx.
 - .12 Implementation of training plans.
 - .13 Cx reports: immediately upon successful completion of Cx.
 - .2 Detailed training schedule to demonstrate no conflicts with testing, completion of project and hand-over to Property Manager.
- .2 After approval, incorporate Cx Schedule into Construction Schedule.
- .3 Consultant, Contractor, Contractor's Cx agent, and Departmental Representative will monitor progress of Cx against this schedule.

1.17 CX REPORTS

- .1 Submit reports of tests, witnessed and certified by Departmental Representative to Departmental Representative who will verify reported results.
- .2 Include completed and certified PV reports in properly formatted Cx Reports.
- .3 Before reports are accepted, reported results to be subject to verification by Departmental Representative.

1.18 ACTIVITIES DURING WARRANTY PERIOD

- .1 Cx activities must be completed before issuance of Interim Certificate, it is anticipated that certain Cx activities may be necessary during Warranty Period, including:
 - .1 Fine tuning of HVAC systems.

1.19 TRAINING PLANS

- .1 Refer to Section 01 91 41 - Commissioning (Cx) - Training.

1.20 FINAL SETTINGS

- .1 Upon completion of Cx to satisfaction of Departmental Representative lock control devices in their final positions, indelibly mark settings marked and include in Cx Reports.

Part 2 Products**2.1 NOT USED**

- .1 Not Used.

Part 3 Execution**3.1 NOT USED**

- .1 Not Used.

END OF SECTION

Part 1 General**1.1 INSTALLATION/START-UP CHECK LISTS**

- .1 Include the following data:
 - .1 Product manufacturer's installation instructions and recommended checks.
 - .2 Special procedures as specified in relevant technical sections.
 - .3 Items considered good installation and engineering industry practices deemed appropriate for proper and efficient operation.
- .2 Equipment manufacturer's installation/start-up check lists are acceptable for use. As deemed necessary by Departmental Representative supplemental additional data lists will be required for specific project conditions.
- .3 Use check lists for equipment installation. Document check list verifying checks have been made, indicate deficiencies and corrective action taken.
- .4 Installer to sign check lists upon completion, certifying stated checks and inspections have been performed. Return completed check lists to Departmental Representative. Check lists will be required during Commissioning and will be included in Building Maintenance Manual (BMM) at completion of project.
- .5 Use of check lists will not be considered part of commissioning process but will be stringently used for equipment pre-start and start-up procedures.

1.2 PRODUCT INFORMATION (PI) REPORT FORMS

- .1 Product Information (PI) forms compiles gathered data on items of equipment produced by equipment manufacturer, includes nameplate information, parts list, operating instructions, maintenance guidelines and pertinent technical data and recommended checks that is necessary to prepare for start-up and functional testing and used during operation and maintenance of equipment. This documentation is included in the BMM at completion of work.
- .2 Prior to Performance Verification (PV) of systems complete items on PI forms related to systems and obtain Departmental Representative's approval.

1.3 PERFORMANCE VERIFICATION (PV) FORMS

- .1 PV forms to be used for checks, running dynamic tests and adjustments carried out on equipment and systems to ensure correct operation, efficiently and function independently and interactively with other systems as intended with project requirements.
- .2 PV report forms include those developed by Contractor records measured data and readings taken during functional testing and Performance Verification procedures.
- .3 Prior to PV of integrated system, complete PV forms of related systems and obtain Departmental Representative's approval.

1.4 SAMPLES OF COMMISSIONING FORMS

- .1 Departmental Representative will develop and provide to Contractor required project-specific Commissioning forms in electronic format complete with specification data (see attached for sample forms).
- .2 Revise items on Commissioning forms to suit project requirements.

1.5 CHANGES AND DEVELOPMENT OF NEW REPORT FORMS

- .1 When additional forms are required, but are not available from Departmental Representative, develop appropriate verification forms and submit to Departmental Representative for approval prior to use.
 - .1 Additional commissioning forms to be in same format as provided by Departmental Representative.

1.6 COMMISSIONING FORMS

- .1 Use Commissioning forms to verify installation and record performance when starting equipment and systems.
- .2 Strategy for Use:
 - .1 Departmental Representative provides Contractor project-specific Commissioning forms with Specification data included.
 - .2 Contractor will provide required shop drawings information and verify correct installation and operation of items indicated on these forms.
 - .3 Confirm operation as per design criteria and intent.
 - .4 Identify variances between design and operation and reasons for variances.
 - .5 Verify operation in specified normal and emergency modes and under specified load conditions.
 - .6 Record analytical and substantiating data.
 - .7 Verify reported results.
 - .8 Form to bear signatures of recording technician and reviewed and signed off by Departmental Representative.
 - .9 Submit immediately after tests are performed.
 - .10 Reported results in true measured SI unit values.
 - .11 Provide Departmental Representative with originals of completed forms.
 - .12 Maintain copy on site during start-up, testing and commissioning period.
 - .13 Forms to be both hard copy and electronic format with typed written results in Building Management Manual in accordance with Section 01 91 51 - Building Management Manual (BMM).

1.7 LANGUAGE

- .1 English.

Part 2 PRODUCTS**2.1 NOT USED**

- .1 Not Used.

Part 3 EXECUTION**3.1 NOT USED**

- .1 Not Used.

END OF SECTION

Sample of Product Information (PI) Report Form/ Échantillon du formulaire de rapport de l'information du Produit (IP)

Project:	775 Brookfield Rd. M&E Work	Project number:	R.082560	Date:	
Projet:		Numéro de projet:	R.082560	Page:	

PRODUCT INFORMATION (PI) INFORMATION SUR LE PRODUIT

Performance Verification (PV) report form accompanies this PI report form: YES
Un formulaire de rapport de vérification de rendement (VR) accompagne ce formulaire de rapport (PI) : OUI

AIR VALVES / VANNES D'AIR	
Description of system/Description du système :	
No. on Contract Drawings/ No. sur le dessin :	MMS Identifier/Identification du SSEP :

PURCAHSING INFORMATION / INFORMATION D'ACHAT					
Vendor/Agent:		Address:			
Vendeur/Agent :		Adresse :			
Purchase order no./No. d'ordre d'achat :		Date:			
Ordered by/					
Commande par :					
Date of manufacture/Date du manufacture :		Date if start-up/Date de la mise en marche			
Details of Warranty :		Commencement:		Expiration:	
Détails de garantie :		Début :			

PRODUCT INFORMATION / INFORMATION SUR LE PRODUIT					
Manufacturer/					
Manufacturier					
Model/Modelé :		Size/Dimension :		Type:	
Serial no./No. de série :				Rated capacity/ Capacité nominale	

Efficiency: [DOP]	[Dust spot]	Number & sizes		Face Area	
Other data Autre données :					

Technician Technicien	Supervisor Superviseur	Date:
Witnessed by Témoïn :	Title: Titre :	Date:

Sample of Performance Verification (PV) Report Form/ Échantillon du formulaire de rapport de Vérification de rendement (VR)

Project:	775 Brookfield Rd. M&E Work	Project number:	R.082560	Date:	
Projet:		Numéro de projet:	R.082560	Page:	

PERFORMANCE VERIFICATION (PV) REPORT / RAPPORT DE VÉRIFICATION DE RENDEMENT (VR)

AIR VALVES / VANNES D'AIR	
Description of system/Description du système :	
No. on Contract Drawings/No. sur le dessin :	MMS Identifier/Identification du SSEP :

AIR VALVES/ VANNES D'AIR	Designed Conception	Shop Drawings Dessins d'atelier	Measured Mesure	Comments Commentaires
Flow rate:/debit: Max.				
Flow rate:/debit: Max.				
PRESSURE DROP:/ BAISSSE DE PRESSION				
1. Max. airflow:/debit d 'air max. :				
2. Min. airflow:/débit d'air min. :				
RESPONSE RATE:/ FREQUENCE DE RESPONSE :				
Time (max. to min.):/Temps (max. au min.) :				
Time (min. to max.): /Temps (min. au max.) :				

Technician Technicien	Supervisor Superviseur	Date:
Witnessed by Témoïn :	Title: Titre :	Date:

END OF SAMPLE PI AND PV REPORT FORMS
FIN DE L'ECHANTILLON DES FORMULAIRES DE RAPPORT IP ET VR

Part 1 General**1.1 TRAINEES**

- .1 Trainees: personnel selected for operating and maintaining this facility. Includes Facility Manager, building operators, maintenance staff, security staff, and technical specialists as required.
- .2 Trainees will be available for training during later stages of construction for purposes of familiarization with systems.

1.2 INSTRUCTORS

- .1 Departmental Representative will provide:
 - .1 Descriptions of systems.
 - .2 Instruction on design philosophy, design criteria, and design intent.
- .2 Contractor and certified factory-trained manufacturers' personnel: to provide instruction on the following:
 - .1 Start-Up, operation, shut-down of equipment, components and systems.
 - .2 Control features, reasons for, results of, implications on associated systems of, adjustment of set points of control and safety devices.
 - .3 Instructions on servicing, maintenance and adjustment of systems, equipment and components.
- .3 Contractor and equipment manufacturer to provide instruction on:
 - .1 Start-up, operation, maintenance and shut-down of equipment they have certified installation, started up and carried out PV tests.

1.3 TRAINING OBJECTIVES

- .1 Training to be detailed and duration to ensure:
 - .1 Safe, reliable, cost-effective, energy-efficient operation of systems in normal and emergency modes under all conditions.
 - .2 Effective on-going inspection, measurements of system performance.
 - .3 Proper preventive maintenance, diagnosis and trouble-shooting.
 - .4 Ability to update documentation.
 - .5 Ability to operate equipment and systems under emergency conditions until appropriate qualified assistance arrives.

1.4 TRAINING MATERIALS

- .1 Instructors to be responsible for content and quality.
- .2 Training materials to include:
 - .1 "As-Built" Contract Documents.
 - .2 Operating Manual.
 - .3 Maintenance Manual.
 - .4 Management Manual.
 - .5 TAB and PV Reports.
- .3 Project Manager, Commissioning Manager and Facility Manager will review training manuals.
- .4 Training materials to be in a format that permits future training procedures to same degree of detail.
- .5 Supplement training materials:
 - .1 Transparencies for overhead projectors.
 - .2 Multimedia presentations.
 - .3 Manufacturer's training videos.
 - .4 Equipment models.

1.5 SCHEDULING

- .1 Include in Commissioning Schedule time for training.
- .2 Deliver training during regular working hours, training sessions to be 3 hours in length.
- .3 Training to be completed prior to acceptance of project.

1.6 RESPONSIBILITIES

- .1 Be responsible for:
 - .1 Implementation of training activities,
 - .2 Coordination among instructors,
 - .3 Quality of training, training materials,
- .2 Departmental Representative will evaluate training and materials.
- .3 Upon completion of training, provide written report, signed by Instructors, witnessed by Departmental Representative.

1.7 TRAINING CONTENT

- .1 Training to include demonstrations by Instructors using the installed equipment and systems.
- .2 Content includes:
 - .1 Review of facility and occupancy profile.
 - .2 Functional requirements.
 - .3 System philosophy, limitations of systems and emergency procedures.
 - .4 Review of system layout, equipment, components and controls.
 - .5 Equipment and system start-up, operation, monitoring, servicing, maintenance and shut-down procedures.
 - .6 System operating sequences, including step-by-step directions for starting up, shut-down, operation of valves, dampers, switches, adjustment of control settings and emergency procedures.
 - .7 Maintenance and servicing.
 - .8 Trouble-shooting diagnosis.
 - .9 Inter-Action among systems during integrated operation.
 - .10 Review of O&M documentation.
- .3 Provide specialized training as specified in relevant Technical Sections of the construction specifications.

1.8 VIDEO-BASED TRAINING

- .1 Manufacturer's video to be used as training tool with Departmental Representative's review and written approval 3 months prior to commencement of scheduled training.
- .2 On-Site training videos:
 - .1 Video training sessions for use during future training.
 - .2 To be performed after systems are fully commissioned.
 - .3 Organize into several short modules to permit incorporation of changes.
- .3 Production methods to be professional quality.

Part 2 Products**2.1 NOT USED**

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

END OF SECTION

Part 1 General**1.1 SUMMARY**

- .1 Section Includes:
 - .1 This section is limited to portions of the Building Management Manual (BMM) provided to Departmental Representative by Contractor.
- .2 Acronyms:
 - .1 BMM - Building Management Manual.
 - .2 Cx - Commissioning.
 - .3 HVAC - Heating, Ventilation and Air Conditioning.
 - .4 PI - Product Information.
 - .5 PV - Performance Verification.
 - .6 TAB - Testing, Adjusting and Balancing.
 - .7 WHMIS - Workplace Hazardous Materials Information System.

1.2 GENERAL REQUIREMENTS

- .1 Standard letter size paper 216 mm x 279 mm.
- .2 Methodology used to facilitate updating.
- .3 Drawings, diagrams and schematics to be professionally developed.
- .4 Electronic copy of data to be in a format accepted and approved by Departmental Representative.

1.3 APPROVALS

- .1 Prior to commencement, co-ordinate requirements for preparation, submission and approval with Departmental Representative.

1.4 GENERAL INFORMATION

- .1 Provide Departmental Representative the following for insertion into appropriate Part and Section of BMM:
 - .1 Complete list of names, addresses and, telephone numbers of contractor, sub-contractors that participated in delivery of project - as indicated in Section 1.2 of BMM.
 - .2 Summary of mechanical and electrical systems installed and commissioned - as indicated in Section 1.4 of BMM.
 - .1 Including sequence of operation as finalized after commissioning is complete as indicated in Section 2.0 of BMM.
 - .3 Description of building operation under conditions of heightened security and emergencies as indicated in Section 2.0 of BMM.
 - .4 System, equipment and components Maintenance Management System (MMS) identification - Section 2.1 of BMM..
 - .5 Information on operation and maintenance of mechanical systems and equipment installed and commissioned - Section 2.0 of BMM.
 - .6 Operating and maintenance manual - Section 3.2 of BMM.
 - .7 Final commissioning plan as actually implemented.
 - .8 Completed commissioning checklists.
 - .9 Commissioning test procedures employed.
 - .10 Completed Product Information (PI) and Performance Verification (PV) report forms, approved and accepted by Departmental Representative.
 - .11 Commissioning reports.

1.5 CONTENTS OF OPERATING AND MAINTENANCE MANUAL

- .1 For detailed requirements refer to Section 01 78 00 - Closeout Submittals.
- .2 Departmental Representative to review and approve format and organization within 12 weeks of award of contract.
- .3 Include original manufactures brochures and written information on products and equipment installed on this project.
- .4 Record and organize for easy access and retrieval of information contained in BMM.
- .5 Include completed PI report forms, data and information from other sources as required.
- .6 Inventory directory relating to information on installed systems, equipment and components.
- .7 Approved project shop-drawings, product and maintenance data.
- .8 Manufacturer's data and recommendations relating: manufacturing process, installation, commissioning, start-up, O&M, shutdown and training materials.
- .9 Inventory and location of spare parts, special tools and maintenance materials.
- .10 Warranty information.
- .11 Inspection certificates with expiration dates, which require on-going re-certification inspections.
- .12 Maintenance program supporting information including:
 - .1 Recommended maintenance procedures and schedule.
 - .2 Information to removal and replacement of equipment including, required equipment, points of lift and means of entry and egress.

1.6 SUPPORTING DOCUMENTATION FOR INSERTION INTO SUPPORTING APPENDICES

- .1 Provide Departmental Representative supporting documentation relating to installed equipment and system, including:
 - .1 General:
 - .1 Finalized commissioning plan.
 - .2 WHMIS information manual.
 - .3 Approved "as-built" drawings and specifications.
 - .4 Procedures used during commissioning.
 - .5 Cross-Reference to specification sections.
 - .2 Mechanical:
 - .1 Installation permits, inspection certificates.
 - .2 Ducting leakage test reports.
 - .3 TAB and PV reports.
 - .4 Copies of posted instructions.
 - .3 Electrical:
 - .1 Installation permits, inspection certificates.
 - .2 TAB and PV reports.
 - .3 Electrical work log book.
 - .4 Charts and schedules.
- .2 Assist Departmental Representative with preparation of BMM.

1.7 LANGUAGE

- .1 English.

1.8 USE OF CURRENT TECHNOLOGY

- .1 Use current technology for production of documentation. Emphasis on ease of accessibility at all times, maintain in up-to-date state, compatibility with user's requirements.
- .2 Obtain Departmental Representative's approval before starting Work.

Part 2 Products

2.1 NOT USED

- .1 Not used.

Part 3 Execution

3.1 NOT USED

- .1 Not used.

END OF SECTION