





KEY PLAN
PLAN-REP?RE

05	ISSUED FOR TENDER/DOCUMENT DE SOUMISSION	2017-06-21
04	ISSUED FOR 100% REVIEW/EMIS POUR 100% REVUE	2017-03-10
03	RE-ISSUED FOR 90% REVIEW/REMISSION POUR 90% REVUE	2017-02-03
02	ISSUED FOR 90% REVIEW/EMIS POUR 90% REVUE	2017-01-20
01	ISSUED FOR 60% REVIEW/EMIS POUR 60% REVUE	2016-12-02

revision		date
----------	--	------


A detail no.
no. du détail
 B location drawing no.
no. de localisation
 C drawing no.
no. du dessin

project	proje
MECHANICAL & ELECTRICAL WORK TO THE RADIATION PROTECTION BUILDING TRAVAUX MÉCANIQUES & ÉLECTRIQUES AU BÂTIMENT DE PROTECTION CONTRE LES RADIATIONS	

775 BROOKFIELD Rd.

MECHANICAL - GROUND FLOOR
HVAC - DEMOLITION WORK
MÉCANIQUE - REZ-DE-CHAUSSÉE
CVAC - TRAVAUX DE DÉMOLITION

designed	S. HAMILTON	concept
date		
drawn	T. REGLI	dessiné
date		
revised		révisé
date	S. HAMILTON	
approved		approuvé
date	S. HAMILTON	
tender		soumission
PWC Project Manager Administrateur de projets TPB		
project no.		no. du projet
R.082560.001		
drawing no.		no. du dessin



KEY PLAN - GROUND FLOOR
PLAN PRINCIPAL - REZ-DE-CHAUSSÉE

2
M4

GROUND FLOOR - HVAC - DEMOLITION WORK
REZ-DE-CHAUSÉE - CVAC - TRAVAUX DE DÉMOLITION

1 RE
M4 1:50

DESCRIPTION OF WORK – DEMOLITION WORK

- 1 REMOVE EXISTING S/A DUCTWORK, AUTOMATIC AIR VALVES (AAV) & DUAL DUCT BOXES (DOB) C/W ASSOCIATED ACCESSORIES & PNEUMATIC CONTROLS. ENSURE PNEUMATIC CONTROL SYSTEM REMAINS OPERATIONAL FOR REMAINDER OF BUILDING.
- 2 REMOVE EXISTING M/A DUCTWORK, MOTORIZED DAMPERS & VAV BOXES C/W ASSOCIATED ACCESSORIES & CONTROLS.
- 3 REMOVE EXISTING FUME HOOD E/A DUCTWORK.
- 4 SPARE
- 5 REMOVE EXISTING LAMINAR DIFFUSER C/W ASSOCIATED DUCTWORK AS INDICATED. RETAIN OUTLET FOR RE-USE IN NEW WORK.

DESCRIPTION DES TRAVAUX – TRAVAUX DE DÉMOLITION

- 1 ENLEVER LES CONDUITS D'AIR D'ALIMENTATION, LES VANNES DE REGULATION DU DEBIT D'AIR (AMV) ET LES BOTES A DEUX CONDUITS (DBD) EXISTANT ANSI QUE LES ACCESSOIRES ET CONTRÔLES PNEUMATIQUES ASSOCIES, S'ASSURER QUE LE SYSTEME DE CONTRÔLE PNEUMATIQUE RESTE OPERATIONNEL POUR LE RESTANT DU BATIMENT.
- 2 ENLEVER LES CONDUITS D'APPONT ET LES BOTES A VOLUME D'AIR VARIABLE EXISTANT ANSI QUE LES ACCESSOIRES ET CONTRÔLES ASSOCIES.
- 3 ENLEVER LES CONDUITS D'EXTRACTION DE LA HOTTE A VAPEUR EXISTANT ANSI QUE LES ACCESSOIRES ASSOCIES.
- 4 RESERVE.
- 5 ENLEVER LES OFFICIEURS D'AR LAMINARE EXISTANT ANSI QUE LES CONDUITS D'AR ASSOCIES TEL QU'UNIQUE. GARDER LES OFFICIEURS POUR LES REUTILISER LORS DES TRAVAUX DE TRAVAIL.