

Part 1 General

1.1 SITE CONDITIONS

- .1 Review "Designated Substance Reports" (DSR) and take precautions to protect the environment. The DSR reports are attached following Section 01 14 25.
- .2 Asbestos is known to be contained in the roof deck, and as such can reasonably be expected to be disturbed during the construction. Refer to the attached DSR reports for instructions on how to proceed with work that may affect the existing roof decking.
- .3 If other material resembling spray or trowel-applied asbestos or other designated substance listed as hazardous be encountered, stop work, take preventative measures, and notify Departmental Representative immediately.
 - .1 Proceed only after receipt of written instructions have been received from Departmental Representative.
- .4 Notify Departmental Representative before disrupting building access or services.

1.2 WASTE MANAGEMENT

- .1 Separate and recycle demolition materials in accordance with 01 00 10 - General Instructions

Part 2 Products

2.1 NOT USED

- .1 Not used.

Part 3 Execution

3.1 EXAMINATION

- .1 Inspect site with Departmental Representative and verify extent and location of items designated for removal, disposal, alternative disposal, recycling, salvage and items to remain.
 - .2 Locate and protect utilities. Preserve active utilities traversing site in operating condition.
 - .3 Notify and obtain approval of utility companies before starting demolition.
-

- .4 Disconnect, cap, plug or divert, as required, existing public utilities within the property where they interfere with the execution of the work, in conformity with the requirements of the authorities having jurisdiction. Mark the location of these and previously capped or plugged services on the site and indicate location (horizontal and vertical) on the record drawings. Support, shore up and maintain pipes and conduits encountered.
 - .1 Immediately notify Departmental Representative and utility company concerned in case of damage to any utility or service
 - .2 Immediately notify the Departmental Representative should uncharted utility or service be encountered, and await instruction in writing regarding remedial action.

3.2 PREPARATION

- .1 Protection of In-Place Conditions:
 - .1 Prevent movement, settlement, or damage to adjacent and parts of building to remain in place. Provide bracing and shoring required.
 - .2 Keep noise, dust, and inconvenience to occupants to minimum. Building must remain fully operational and occupied at all times.
 - .3 Protect building systems, services and equipment.
 - .4 Provide temporary dust screens, covers, railings, supports and other protection as required.
 - .5 Do Work in accordance with Section 01 35 29.06 - Health and Safety Requirements.
 - .6 All floor areas are under negative pressure. Ensure that demolition work does not compromise building indoor environment.
- .2 Demolition/Removal:
 - .1 Remove items as indicated.
 - .2 Remove parts of existing building to permit new construction.
 - .3 Trim edges of partially demolished building and elements to suit new work.
 - .4 Carefully cut and remove existing insulated metal cladding at both end walls of the existing Hangar T-58, along with return panels at the corners all as indicated. Do not remove or damage the existing steel girt panel supports.
 - .5 All conduits (electrical, gas, communication, etc.) currently supported either on the interior face or exterior face of the exterior metal panels, are to be removed complete with their supports, temporarily supported and reinstated onto the new insulated metal exterior wall panels.
 - .6 Completely remove all existing mechanical, electrical, communications, gas lines, walkways, etc. presently located on the existing roofs to allow the re-roofing work to proceed. Reinstall all existing systems/materials temporarily removed after completion of the re-roofing work.

3.3 CLEANING

- .1 Leave Work area clean at end of each day.

END OF SECTION

Part 1 General**1.1 SUMMARY**

- .1 Comply with requirements of this Section when performing following work:
 - .1 Removal of non-friable asbestos-containing material, if the material is removed without being broken, cut, drilled, abraded, ground, sanded or vibrated.
 - .2 Removal of non-friable asbestos-containing materials if the material is removed by breaking, cutting, drilling, abrading, grinding or vibrating, if the material is wetted to control the spread of dust and fibres, and the work is only done by non-powered hand-held tools.
- .2 Refer to the Specification Section 01 14 25 – Designated Substance Report for details on asbestos-containing materials.

1.2 RELATED SECTIONS

- .1 Section 01 14 25 – Designated Substances
- .2 Section 02 89 00 – Silica Precautionary Measures

1.3 REFERENCES

- .1 *Canadian General Standards Board (CGSB).*
 - .1 *CAN/CGSB-1.205-03, Sealer for Application of Asbestos-Fibre Releasing Materials.*
- .2 *Department of Justice Canada (Jus).*
 - .1 *Canadian Environmental Protection Act, 1999 (CEPA).*
- .3 *Health Canada/Workplace Hazardous Materials Information System (WHMIS).*
 - .1 *Material Safety Data Sheets (MSDS).*
- .4 *Transport Canada (TC).*
 - .1 *Transportation of Dangerous Goods Act, 1992 (TDGA).*
- .5 *Ontario Environmental Protection Act, R.R.O 1990,*
 - .1 *General – Waste Management, O. Reg. 347/90, as amended.*
- .6 *Underwriters' Laboratories of Canada (ULC).*
- .7 *National Joint Council (NJC).*
 - .1 *Part XI – Hazardous Substances.*
- .8 *Ontario Ministry of Labour (MoL).*
 - .1 *Occupational Health and Safety Act, R.S.O 1990, c. O1 (OSHA)*
 - .1 *O.Reg. 278/05 – Designated Substance – Asbestos on Construction Projects and in Buildings and Repair Operations, as amended*
 - .2 *Ontario Occupational Health and Safety Act, R.S.O. 1990, Regulation 490/09 “Designated Substances”, as amended.*
 - .3 *O.Reg. 213/91 - “Construction Projects”, as amended.*

1.4 DEFINITIONS

- .1 HEPA vacuum: DOP tested High Efficiency Particulate Air filtered vacuum equipment with filter system capable of collecting and retaining fibres greater than 0.3 microns in any direction at 99.97% efficiency.
- .2 Amended Water: water with non-ionic surfactant wetting agent added to reduce surface tension of water to allow thorough wetting of fibres.
- .3 Asbestos-Containing Materials (ACMs): materials that contain 0.5 percent or more asbestos by dry weight, identified under Existing Conditions including fallen materials and settled dust.
- .4 Asbestos Work Area: area where work takes place which will, or may, disturb ACMs.
- .5 Authorized Visitors: Departmental Representative, and representative(s) of regulatory agencies.
- .6 Competent worker: in relation to specific work, means a worker who:
 - .1 Is qualified because of knowledge, training and experience to perform the work.
 - .2 Is familiar with the provincial laws and with the provisions of the regulations that apply to the work.
 - .3 Has knowledge of all potential or actual danger to health or safety in the work.
- .7 DOP Test: testing method used to determine integrity of unit using Dispersed Oil Particulate (DOP) HEPA-filter leak test.
- .8 Friable material: means material that:
 - .1 When dry, can be crumbled, pulverized or powdered by hand pressure, or is crumbled, pulverized or powdered.
- .9 Hazardous Material Workplan: A brief report identifying the location and quantities of hazardous materials and the methods that will be used to remove, store, transport and dispose of them.
- .10 Non-Friable Material: material that when dry cannot be crumbled, pulverized or powdered by hand pressure.
- .11 Occupied Area: any area of the building or work site that is outside Asbestos Work Area.
- .12 Polyethylene: rip-proof polyethylene sheeting with tape along edges, around penetrating objects, over cuts and tears, and elsewhere as required to provide protection and isolation.
- .13 Sprayer: garden reservoir type sprayer or airless spray equipment capable of producing mist or fine spray. Sprayer must have appropriate capacity for work.

1.5 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit proof satisfactory to the Departmental Representative that suitable arrangements have been made to dispose of asbestos-containing waste in accordance with requirements of authority having jurisdiction.
- .2 Submit Provincial/Territorial and/or local requirements for Notice of Project Form.

- .3 Submit proof of Contractor's Asbestos Liability Insurance.
- .4 Submit to the Departmental Representative necessary permits for transportation and disposal of asbestos-containing waste and proof that asbestos-containing waste has been received and properly disposed.
- .5 Submit proof that all asbestos workers and/or supervisor have received appropriate training and education by a competent person in the hazards of asbestos exposure, good personal hygiene and work practices while working in Asbestos Work Areas, and the use, cleaning and disposal of respirators and protective clothing.
- .6 Submit proof satisfactory to Departmental Representative that employees have appropriate respirator fitting and testing (fit test certificates). Workers must be fit-tested (qualitative as a minimum) with respirator that is personally issued.
- .7 Asbestos abatement section within Hazardous Material Work Plan.

1.6 QUALITY ASSURANCE

- .1 Regulatory Requirements: comply with Federal, Provincial/Territorial, and local requirements pertaining to asbestos, provided that in case of conflict among these requirements or with these specifications, more stringent requirement applies. Comply with regulations in effect at time Work is performed.
- .2 Health and Safety:
 - Safety Requirements: worker protection.
 - .1 Protective equipment and clothing to be worn by workers while in Asbestos Work Area include:
 - .1 As a minimum, air purifying half-mask respirator with N-100, R-100 or P-100 particulate filter, personally issued to worker and marked as to efficiency and purpose, suitable for protection against asbestos and acceptable to Provincial Authority having jurisdiction. The respirator to be fitted so that there is an effective seal between the respirator and the worker's face, unless the respirator is equipped with a hood or helmet. The respirator to be cleaned, disinfected and inspected after use on each shift, or more often if necessary, when issued for the exclusive use of one worker, or after each use when used by more than one worker. The respirator to have damaged or deteriorated parts replaced prior to being used by a worker; and, when not in use, to be stored in a convenient, clean and sanitary location. The employer to establish written procedures regarding the selection, use and care of respirators, and a copy of the procedures to be provided to and reviewed with each worker who is required to wear a respirator. A worker not to be assigned to an operation requiring the use of a respirator unless he or she is physically able to perform the operation while using the respirator.
 - .2 Disposable-type protective clothing (high-density polyethylene protective clothing (Tyvek or similar, as approved by Departmental Representative) that does not readily retain or permit penetration of asbestos fibres. Protective clothing to be provided by the employer and worn by every worker who enters the work area, and the protective clothing shall consist of a head

covering and full body covering that fits snugly at the ankles, wrists and neck, in order to prevent asbestos fibres from reaching the garments and skin under the protective clothing to include suitable footwear, and to be repaired or replaced if torn.

- .2 Eating, drinking, chewing, and smoking are not permitted in Asbestos Work Area.
- .3 Before leaving Asbestos Work Area, the worker can decontaminate his or her protective clothing by using a vacuum equipped with a HEPA filter, or by damp wiping, before removing the protective clothing, or, if the protective clothing will not be reused, place it in a container for dust and waste. The container to be dust tight, suitable for asbestos waste, impervious to asbestos, identified as asbestos waste, cleaned with a damp cloth or a vacuum equipped with a HEPA filter immediately before removal from the work area, and removed from the work area frequently and at regular intervals.
- .4 Facilities for washing hands and face shall be provided within or close to the Asbestos Work Area.
- .5 Ensure workers wash hands and face when leaving Asbestos Work Area.
- .6 Ensure that no person required to enter an Asbestos Work Area has facial hair that affects seal between respirator and face.

1.7 WASTE MANAGEMENT AND DISPOSAL

- .1 Remove from site and dispose of packaging materials at appropriate recycling facilities.
- .2 Collect and separate for disposal paper, plastic, polystyrene, corrugated cardboard, packaging material in appropriate on-site bins for recycling in accordance with Waste Management Plan.
- .3 Separate for reuse, and recycling and place in designated containers steel, metal, plastic waste in accordance with Waste Management Plan.
- .4 Place materials defined as hazardous or toxic in designated containers. Location and transportation of all on-site waste containers must be approved by Departmental Representative in writing prior to work.
- .5 Handle and dispose of hazardous materials in accordance with the CEPA, TDGA, Regional and Municipal regulations.
- .6 Fold up metal banding, flatten and place in designated area for recycling.
- .7 Disposal of asbestos waste generated by removal activities must comply with Federal, Provincial, Territorial and Municipal regulations. Dispose of asbestos waste in sealed double thickness 0.15 mm thick bags or leak proof drums. Label containers with appropriate warning labels.
- .8 Provide waste manifests describing and listing waste created. Transport containers by approved means to licensed landfill for burial. All waste landfill manifests are to be provided to the Departmental Representative at the end of the project.

1.8 EXISTING CONDITIONS

- .1 Refer to the Specification Section 01 14 25 – Designated Substance Report for details on asbestos-containing materials.
- .2 Notify Departmental Representative of asbestos-containing material discovered during Work and not apparent from drawings, specifications, or report pertaining to Work. Do not disturb such material pending instructions from Departmental Representative.

1.9 SCHEDULING

- .1 Hours of Work: perform work involving asbestos abatement located at the Building during hours specified by Departmental Representative. **The work schedule must be approved in writing by the Departmental Representative in advance of work.** Contractor shall be available to work continuously from beginning to end of project.

1.10 PERSONNEL TRAINING

- .1 Before beginning Work, provide Departmental Representative with satisfactory proof that every worker has had instruction and training in hazards of asbestos exposure, in personal hygiene and work practices, and in use, cleaning, and disposal of respirators and protective clothing.
- .2 Instruction and training related to respirators includes, following minimum requirements:
 - .1 Fitting of equipment.
 - .2 Inspection and maintenance of equipment.
 - .3 Disinfecting of equipment.
 - .4 Limitations of equipment.
- .3 Instruction and training must be provided by a competent, qualified person.

Part 2 Products**2.1 MATERIALS**

- .1 Drop Sheets:
 - .1 Polyethylene: 0.15 mm thick.
 - .2 FR polyethylene: 0.15 mm thick woven fibre reinforced fabric bonded both sides with polyethylene.
- .2 Wetting Agent: 50% polyoxyethylene ester and 50% polyoxyethylene ether mixed with water in a concentration to provide thorough wetting of asbestos-containing material.
- .3 Asbestos waste containers: Metal or fibre - type acceptable to dump operator with tightly fitting covers and 0.15 mm minimum thickness sealable polyethylene liners.
 - .1 Inner container: 0.15 mm thick sealable polyethylene waste bag.
 - .2 Outer container: sealable metal or fibre type where there are sharp objects included in waste material; otherwise outer container may be

sealable metal or fibre type or second 0.15 mm thick sealable polyethylene bag.

- .3 Label containers in accordance with applicable Regulations. Label in both official languages.

Part 3 Execution

3.1 SUPERVISION

- .1 Minimum of one Supervisor for every ten workers is required inside the asbestos work areas at all times.
- .2 Approved Supervisor must remain within Asbestos Work Area during disturbance, removal, or other handling of asbestos-containing materials.

3.2 PROCEDURES

- .1 Before beginning Work, isolate Asbestos Work Area using, at a minimum, preprinted cautionary asbestos warning signs in both official languages that are visible at access routes to Asbestos Work Area.
 - .1 Remove visible dust from surfaces in the work area where dust is likely to be disturbed during course of work.
 - .2 Use HEPA vacuum, or damp cloths where damp cleaning does not create a hazard and is otherwise appropriate.
 - .3 Do not use compressed air to clean up or remove dust from any surface.
- .2 Prevent spread of dust from Asbestos Work Area using measures appropriate to work to be done.
 - .1 Use FR polyethylene drop sheets over flooring such as carpeting that absorbs dust and over flooring in Asbestos Work Area where dust and contamination cannot otherwise be safely contained.
- .3 Wet materials containing asbestos to be cut, ground, abraded, scraped, drilled, or otherwise disturbed unless wetting creates hazard or causes damage.
 - .1 Use garden reservoir type low - velocity fine - mist sprayer.
 - .2 Perform Work to reduce dust creation to lowest levels practicable.
 - .3 Work will be subject to visual inspection.
 - .4 Contamination of surrounding areas indicated by visual inspection or air monitoring will require complete enclosure and clean-up of affected areas.
- .4 Cutting, shaping, grinding, drilling, abrading or otherwise disturbing non-friable asbestos-containing materials shall be executed using non-powered hand-tools only.
- .5 Clean-Up:
 - .1 Frequently during Work and immediately after completion of Work, clean up dust and asbestos-containing waste using HEPA vacuum or by damp mopping.
 - .2 Place dust and asbestos-containing waste in sealed dust-tight waste bags. Treat drop sheets and disposable protective clothing as asbestos waste; wet and fold these items to contain dust, then place in plastic bags.

ASBESTOS ABATEMENT - MINIMUM PRECAUTIONSPage 7 of 7

- .3 Clean exterior of each waste-filled bag using damp cloths or HEPA vacuum and place in second clean waste bag immediately prior to removal from Asbestos Work Area.
- .4 Seal waste bags and remove from site. Dispose of in accordance with requirements of Provincial and Federal Authority having jurisdiction. Supervise dumping and ensure that dump operator is fully aware of hazardous nature of material to be dumped and that guidelines and regulations for asbestos disposal are followed.
- .5 Perform final thorough clean-up of Work areas and adjacent areas affected by Work using HEPA vacuum.

3.3 INSPECTION

- .1 Perform inspection of Asbestos Work Area to confirm compliance with specification and governing authority requirements. Deviation(s) from these requirements that have not been approved in writing by Departmental Representative may result in Work stoppage, at no cost to Owner.
- .2 Departmental Representative may inspect Work at any time during the project for:
 - .1 Adherence to specific procedures and materials.
 - .2 Final cleanliness and completion.
 - .3 No additional costs will be allowed by Contractor for additional labour or materials required to provide specified performance level.
- .3 When asbestos leakage from Asbestos Work Area has occurred or is likely to occur Departmental Representative may order Work shutdown.
- .4 No additional costs will be allowed by the Contractor for additional labour or materials required to provide specified performance level.

END OF SECTION

Part 1 General**1.1 SUMMARY**

- .1 This section specifies requirements and procedures for silica precautionary measures. This section conforms to the requirements of the Ontario Occupational Health and Safety Act, R.S.O. 1990, Regulation 490/09 "Designated Substances".
- .2 Comply with the requirements of this Section when performing the following work:
 - .1 Work at site which may involve contact with silica dust generated through such processes as sawing, cutting, grinding, blasting and/or breaking of the silica containing material.
 - .2 Refer to the following documentation for details on silica-containing materials:
 - .1 Specification Section 01 14 25 – Designated Substances.

1.2 RELATED SECTIONS

- .1 Section 01 14 25 – Designated Substances
- .2 Section 02 82 00.01 – Asbestos Abatement: Minimum Precautions

1.3 REFERENCES

- .1 Comply with current Federal, Provincial, and local requirements pertaining to silica, provided that in case of conflict among these requirements or with these specifications the more stringent requirement applies. Comply with regulations in effect at time work is performed.
- .2 Federal Legislation
 - .1 Canada Labour Code and associated regulations.
- .3 Provincial legislation
 - .1 Ontario Occupational Health and Safety Act, R.S.O. 1990, Regulation 490/09 "Designated Substances".

1.4 DEFINITIONS

- .1 **Dangerous Goods:** product, substance, or organism that is specifically listed or meets hazard criteria established in Transportation of Dangerous Goods Regulations.
- .2 **Hazardous Material:** product, substance, or organism that is used for its original purpose; and that is either dangerous goods or a material that may cause adverse impact to environment or adversely affect health of persons, animals, or plant life when released into the environment.
- .3 **Hazardous Material Workplan:** A brief report identifying the location and quantities of hazardous materials and the methods that will be used to remove, store, transport and dispose of them.

- .4 **Workplace Hazardous Materials Information System (WHMIS):** Canada-wide system designed to give employers and workers information about hazardous materials used in workplace. Under WHMIS, information on hazardous materials is provided on container labels, material safety data sheets (MSDS), and worker education programs. WHMIS is put into effect by combination of federal and provincial laws.

1.5 SUBMITTALS

- .1 Silica abatement section within Hazardous Material Work Plan.

1.6 PRECAUTIONARY MEASURES AND PROCEDURES

- .1 Execute work by methods to minimize raising silica dust from demolition operations. Where practical, wet methods or a dust collection system should be used to reduce dust.
- .2 Adequate ventilation, including local exhaust ventilation, should be maintained to prevent the accumulation and recirculation of harmful concentrations of free crystalline silica in the work area.
- .3 As practical, processes that generate silica dust should be completed in enclosed areas wherever possible to prevent the spread of silica dust outside of the work area.
- .4 Implement and maintain silica dust control measures during work to ensure that silica levels do not exceed allowable limits.
- .5 Departmental Representative may stop work at any time when release of silica dust to adjacent area is suspected. Contractor must discuss procedures that Contractor proposes to resolve problem. Make all necessary changes to operations prior to resuming any demolition activities that may cause release of silica dust at no extra cost to the Departmental Representative.
- .6 Silica dust should be cleaned from machinery and work surfaces by wet sweeping, the use of sweeping compounds or vacuum cleaners fitted with a HEPA filter to prevent the recirculation of dusty air. Cleaning methods such as blowing with compressed air or dry sweeping should be avoided. Where exposure to free crystalline silica occurs, protective work clothing should be vacuumed before removal.
- .7 Store material containing silica dust in closed containers or use other appropriate means to prevent dust from becoming airborne.

1.7 PERSONAL PROTECTIVE EQUIPMENT

- .1 Anticipated minimum levels of personal protection based on work activity involving silica dust are listed below and are in addition to the personal protective equipment required for the completion of the demolition activities. Personal protection are dependent on the work practices and associated silica exposure risks.
 - .1 Air purifying half-mask respirator equipped with HEPA filter cartridges or supplied-air type, personally issued to the worker and marked as to efficiency and purpose, and acceptable to the Provincial Authority having jurisdiction as suitable for silica and the level of silica exposure in the

Work Area. If disposable type filters are used, provide sufficient filters so that workers can install new filters following disposal of used filters and before re-entering contaminated areas.

- .2 Eye Protection: Goggles, Safety glasses with side shields, or Face shield.
- .3 If requested by a worker,
 - .1 Hand Protection: Gloves
 - .2 Clothing: Full body protective clothing

1.8 AIR MONITORING

- .1 If air monitoring shows that work areas contain crystalline silica above the specified action levels, these areas shall be cleaned by previously outlined methods at no additional cost to the Departmental Representative.

1.9 PERMITS

- .1 Contractor is responsible to obtain all necessary permits, licenses and approvals to conduct the abatement (e.g. Ontario Ministry of the Environment (MOE) waste generating number, etc.).

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION