

PART 1 - GENERAL

- | | | |
|---|----|--|
| <u>1.1 DESCRIPTION OF WORK</u> | .1 | This section covers the provision of power for door locks and conduit for 24 VDC hardware wiring. |
| | .2 | Door lock equipment and hardware equipment provided by the door hardware supplier. Refer to architectural specification sections. |
| | .3 | Low voltage (24 VDC) wiring supplied and installed by the door hardware supplier. |
| <u>1.2 EQUIPMENT SUPPLIED BY DIVISION</u> | .1 | Provide all 120 VAC wiring in conduit system for power supply as indicated. |
| | .2 | Provide an empty conduit system with pull cords for installation of 24 VDC wiring by door hardware supplier. |
| <u>1.3 COORDINATION</u> | .1 | Co-ordinate with door hardware supplier to ensure that equipment, boxes, wiring and conduit are located correctly. |
| <u>1.4 CONNECTION TO FIRE ALARM PANEL</u> | .1 | Where scheduled, door power supplies shall be wired to normally closed contacts in the fire alarm panel to release door locks on activation of fire alarm. |
| <u>1.5 CERTIFICATE OF COMPLIANCE</u> | .1 | Provide a letter of verification stating that the system has been checked out and is operational in advance of the Substantial Completion inspection. |
-

PART 2 - PRODUCTS

2.1 NOT USED .1 Not Used.

PART 3 - EXECUTION

3.1 EXECUTION .1 Install 120 VAC power to door power supplies.
.2 Install empty conduit system complete with
pull cords for 24 VDC wiring.