

PART 1 - GENERAL

- 1.1 SUMMARY
- .1 TAB is used throughout this Section to describe the process, methods and requirements of testing, adjusting and balancing for HVAC.
 - .2 TAB means to test, adjust and balance to perform in accordance with requirements of Contract Documents and to do other work as specified in this section.
- 1.2 QUALIFICATIONS OF TAB PERSONNEL
- .1 Submit names of personnel to perform TAB to Departmental Representative within 90 days of award of contract.
 - .2 Provide documentation confirming qualifications, successful experience.
 - .3 TAB: performed in accordance with the requirements of standard under which TAB Firm's qualifications are approved:
 - .1 Associated Air Balance Council, (AABC) National Standards for Total System Balance, MN-1-2002.
 - .2 National Environmental Balancing Bureau (NEBB) TABES, Procedural Standards for Testing, Adjusting, Balancing of Environmental Systems-1998.
 - .3 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA), HVAC TAB HVAC Systems - Testing, Adjusting and Balancing-2002.
 - .4 Recommendations and suggested practices contained in the TAB Standard: mandatory.
 - .5 Use TAB Standard provisions, including checklists, and report forms to satisfy Contract requirements.
 - .6 Use TAB Standard for TAB, including qualifications for TAB Firm and Specialist and calibration of TAB instruments.
 - .7 Where instrument manufacturer calibration recommendations are more stringent than those
-

- 1.2 QUALIFICATIONS OF TAB PERSONNEL (Cont'd) .7 (Cont'd)
listed in TAB Standard, use manufacturer's recommendations.
- .8 TAB Standard quality assurance provisions such as performance guarantees form part of this contract.
.1 For systems or system components not covered in TAB Standard, use TAB procedures developed by TAB Specialist.
.2 Where new procedures, and requirements, are applicable to Contract requirements have been published or adopted by body responsible for TAB Standard used (AABC, NEBB, or TABB), requirements and recommendations contained in these procedures and requirements are mandatory.
- 1.3 PURPOSE OF TAB .1 Test to verify proper and safe operation, determine actual point of performance, evaluate qualitative and quantitative performance of equipment, systems and controls at design, average and low loads using actual or simulated loads
- .2 Adjust and regulate equipment and systems to meet specified performance requirements and to achieve specified interaction with other related systems under normal and emergency loads and operating conditions.
- .3 Balance systems and equipment to regulate flow rates to match load requirements over full operating ranges.
- 1.4 EXCEPTIONS .1 TAB of systems and equipment regulated by codes, standards to satisfaction of authority having jurisdiction.
- 1.5 CO-ORDINATION .1 Schedule time required for TAB (including repairs, re-testing) into project construction and completion schedule to ensure completion before acceptance of project.
-

- 1.9 START OF TAB
(Cont'd)
- .5 Pressure, leakage, other tests specified elsewhere Division 23.
 - .6 Provisions for TAB installed and operational.
 - .7 Start-up, verification for proper, normal and safe operation of mechanical and associated electrical and control systems affecting TAB including but not limited to:
 - .1 Proper thermal overload protection in place for electrical equipment.
 - .2 Air systems:
 - .1 Filters in place, clean.
 - .2 Duct systems clean.
 - .3 Ducts, air shafts, ceiling plenums are airtight to within specified tolerances.
 - .4 Correct fan rotation.
 - .5 Fire, smoke, volume control dampers installed and open.
 - .6 Coil fins combed, clean.
 - .7 Access doors, installed, closed.
 - .8 Outlets installed, volume control dampers open.
 - .3 Liquid systems:
 - .1 Flushed, filled, vented.
 - .2 Correct pump rotation.
 - .3 Strainers in place, baskets clean.
 - .4 Isolating and balancing valves installed, open.
 - .5 Calibrated balancing valves installed, at factory settings.
- 1.10 APPLICATION
TOLERANCES
- .1 Do TAB to following tolerances of design values:
 - .1 HVAC systems: plus 5%, minus 5%.
 - .2 Hydronic systems: plus or minus 10%.
- 1.11 ACCURACY
TOLERANCES
- .1 Measured values accurate to within plus or minus 2% of actual values.
-

- 1.12 INSTRUMENTS .1 Prior to TAB, submit to Departmental Representative list of instruments used together with serial numbers.
- .2 Calibrate in accordance with requirements of most stringent of referenced standard for either applicable system or HVAC system.
- .3 Calibrate within 3 months of TAB. Provide certificate of calibration to Departmental Representative.
- 1.13 ACTION AND INFORMATIONAL SUBMITTALS .1 Submit, prior to commencement of TAB:
- .2 Proposed methodology and procedures for performing TAB if different from referenced standard.
- 1.14 PRELIMINARY TAB REPORT .1 Submit for checking and approval of Departmental Representative, prior to submission of formal TAB report, sample of rough TAB sheets. Include:
- .1 Details of instruments used.
- .2 Details of TAB procedures employed.
- .3 Calculations procedures.
- .4 Summaries.
- 1.15 TAB REPORT .1 Format in accordance with referenced standard.
- .2 TAB report to show results in SI units and to include:
- .1 Project record drawings.
- .2 System schematics.
- .3 Submit 6 copies of TAB Report to Departmental Representative for verification and approval, in both official languages in D-ring binders, complete with index tabs.
-

- 1.16 VERIFICATION .1 Reported results subject to verification by Departmental Representative.
- .2 Provide personnel and instrumentation to verify up to 30% of reported results.
- .3 Number and location of verified results as directed by Departmental Representative.
- .4 Pay costs to repeat TAB as required to satisfaction of Departmental Representative.
-
- 1.17 SETTINGS .1 After TAB is completed to satisfaction of Departmental Representative, replace drive guards, close access doors, lock devices in set positions, ensure sensors are at required settings.
- .2 Permanently mark settings to allow restoration at any time during life of facility. Do not eradicate or cover markings.
-
- 1.18 COMPLETION OF TAB .1 TAB considered complete when final TAB Report received and approved by Departmental Representative.
-
- 1.19 AIR SYSTEMS .1 Standard: TAB to most stringent of this section or TAB standards of AABC NEBB SMACNA ASHRAE.
- .2 Do TAB of systems, equipment, components, controls specified Division 23.
- .3 Qualifications: personnel performing TAB current member in good standing of AABC or NEBB.
- .4 Quality assurance: perform TAB under direction of supervisor qualified to standards of AABC or NEBB.
- .5 Measurements: to include as appropriate for systems, equipment, components, controls: air velocity, static pressure, flow rate, pressure
-

- 1.19 AIR SYSTEMS
(Cont'd)
- .5 Measurements: (Cont'd)
drop (or loss), temperatures (dry bulb, wet bulb, dewpoint), duct cross-sectional area, RPM, electrical power, voltage, noise, vibration.
- .6 Locations of equipment measurements: to include as appropriate:
.1 Inlet and outlet of dampers, filter, coil, fan, other equipment causing changes in conditions.
.2 At controllers, controlled device.
- .7 Locations of systems measurements to include as appropriate: main ducts, main branch, sub-branch, run-out (or grille, register or diffuser).
- 1.20 OTHER TAB
REQUIREMENTS
- .1 General requirements applicable to work specified this paragraph:
.1 Qualifications of TAB personnel: as for air systems specified this section.
.2 Quality assurance: as for air systems specified this section.
- .2 Building pressure conditions:
.1 Adjust HVAC systems, equipment, controls to ensure specified pressure conditions at all times.
- .3 Zone pressure differences:
.1 Adjust HVAC systems, equipment, controls to establish specified air pressure differentials, with systems in every possible combinations of normal operating modes.
- 1.21 POST-OCCUPANCY
TAB
- .1 Measure air velocity, air flow patterns, NC levels, in occupied zones.
- .2 Emergency evacuation: participate in full scale emergency evacuation exercises.
- .3 Participate in systems checks twice during Warranty Period - #1 approximately 3 months after acceptance and #2 within 1 month of termination of Warranty Period.
-

PART 2 - PRODUCTS

2.1 NOT USED .1 Not used.

PART 3 - EXECUTION

3.1 NOT USED .1 Not used.