



- NOTES:
1. COLUMN FINISH: 2 LAYERS OF 6 mm GYPSUM BOARD ON 41 mm METAL STUDS @ 300 OC. OUTSIDE DIAMETER OF COLUMN TO BE 350 mm ±.
  2. PROVIDE/INSTALL FRP PANEL ON WALL BEHIND JANITOR'S SINK TO MINIMUM 200 mm PAST SINK, AND TO MINIMUM 900 mm ABOVE FLOOR. PROVIDE/INSTALL MOP RACK ABOVE JANITOR'S SINK.
  3. 100 mm THICK CONCRETE PAD FOR HOT WATER TANK (LENGTH AND WIDTH TO SUIT).


E	ISSUED FOR TENDER	JUL 11 2017
D	ISSUED FOR TENDER	JUN 28 2017
C	ISSUED FOR 99% REVIEW	MAY 25 2017
B	ISSUED FOR CLIENT REVIEW	APR 24 2017
A	ISSUED FOR 66% REVIEW	MAR 24 2017
revisions		date

MCTS CENTRE AND  
C&P BUILDING

PLACENTIA


MCTS CENTRE  
FLOOR AND  
CEILING PLANS

designed	conçu
date	JULY 11, 2017
drawn	DVF
date	JULY 11, 2017
approved	approuvé
date	JULY 11, 2017
Tender	Submission
PWSSC Project Manager	Administrateur de projets TPSSC
project number	no. du projet
R.081781.004	
drawing no.	no. du dessin
A2	




FLOOR PLAN - LEVEL 1

SCALE : 1:100




FLOOR PLAN - LEVEL 2

SCALE : 1:100



CEILING PLAN - LEVEL 1

SCALE : 1:100



CEILING PLAN - LEVEL 2

SCALE : 1:100