



- NOTES:**
- FOR NOTES AND TYPICAL DETAILS SEE DRAWING S1.
  - ELEVATIONS BASED ON T.O. SLAB ELEVATION 100.0m NOMINAL ELEVATION. SEE CIVIL DRAWINGS FOR ACTUAL ELEVATION.
- BRACING NOTE:**
- ALL HSS 102x102 BRACING DESIGNED FOR:  
Cf = Tr = 100kN  
HORIZONTAL Vt = 20kN
- DOOR OPENING DEMOLITION NOTES:**
- VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS PRIOR TO STARTING ANY DEMOLITION.
  - REPORT ANY DISCREPANCIES TO THE DEPARTMENTAL REPRESENTATIVE.
  - PROVIDE SHORING TO EXISTING ROOF PRIOR TO ANY DEMOLITION.
  - PROVIDE DRAWING OF PROPOSED SHORING STAMPED BY A REGISTERED PROFESSIONAL ENGINEER FOR THE PROVINCE OF NEWFOUNDLAND AND LABRADOR.

D	ISSUED FOR TENDER	JUN 28 2017
C	ISSUED FOR 99% REVIEW	MAY 25 2017
B	ISSUED FOR CLIENT REVIEW	APR 24 2017
A	ISSUED FOR 66% REVIEW	MAR 24 2017
revisions		date

**MCTS CENTRE AND C&P BUILDING**  
**PLACENTIA**

**ITS STORAGE BUILDING**

**STRUCTURAL SECTIONS ELEVATIONS AND DETAILS**

designed	conçu
date JUN.28.2017	
drawn	dessiné
date JUN.28.2017	
approved	approuvé
date JUN.28.2017	
Tender	Soumission
PWSSC Project Manager	Administrateur de projets (PSGC)
project number	no. du projet
R.081781.004	
drawing no.	no. du dessin
S16	