

Breakwater Construction and  
Floating Docks  
Petite Forte, NL  
P/N: R.714115

Page 1  
2016-02-01

PART 1 - GENERAL

1.1 SECTION  
INCLUDES

- .1 Barriers.
- .2 Traffic Controls.

1.2 INSTALLATION  
AND REMOVAL

- .1 Provide temporary controls in order to execute work expeditiously.
- .2 Remove from site all such work after use.

1.3 HOARDING

- .1 Erect temporary site enclosure using new 1.2 m high snow fence wired to rolled steel "T" bar fence posts spaced at 2.4 m centres. Provide one lockable truck gate. Maintain fence in good repair.

1.4 GUARD RAILS  
AND BARRICADES

- .1 Provide secure, rigid guard rails and barricades around open excavations.
- .2 Provide barricades along wharf structure when wheelguard is removed.
- .3 Provide as required by governing authorities.

1.5 ACCESS TO SITE

- .1 Provide and maintain access to adjacent harbour facilities.

1.6 PUBLIC  
TRAFFIC FLOW

- .1 Provide and maintain competent signal flag operators, traffic signals, barricades and flares, lights, or lanterns as required to perform work and protect the public.

---

TEMPORARY BARRIERS AND  
ENCLOSURES

Section 01 56 00

Breakwater Construction and  
Floating Docks  
Petite Forte, NL  
P/N: R.714115

Page 2  
2016-02-01

---

1.7 FIRE ROUTES

- .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

1.8 PROTECTION FOR  
OFF-SITE AND PUBLIC  
PROPERTY

- .1 Protect surrounding private and public property from damage during performance of work.
- .2 Be responsible for damage incurred.