

GENERAL NOTES:

1. ALL STUB CONDUITS TO BE 35mm UNLESS OTHERWISE NOTED.
2. CONDUIT PENETRATION THROUGH FIRE-RATED WALL AND FLOOR TO BE FIRE SEALED.
3. CONDUIT PENETRATION THROUGH WALLS SHALL BE SEALED TO MAINTAIN THE STC RATING OF THE WALL.
4. STUB CONDUIT TO BE BONDED IN THE CABLE TRAY.
5. CABLE TRAY GROUND WIRE TO BE INSTALLED OUTSIDE THE CABLE TRAY. GROUND WIRE TO BE COPPER COLOUR, GREEN INSULATED.
6. INSTALLATION OF CABLE TRAY SHALL BE COORDINATED WITH MECHANICAL CONTRACTOR TO ENSURE CABLE TRAY IS ACCESSIBLE AS PER CEC.
7. CABLE TRAY TO BE PROVIDED WITH ONE METAL CABLE BARRIER.
8. CONTRACTOR TO INSTALL OWNER SUPPLIED MONITOR IN ROOMS 406, 407, 462.

DRAWING KEYNOTES:


- 1 EXISTING 300x50mm BASKET STYLE CABLE TRAY LOCATED IN RAISED FLOOR.
- 2 EXISTING 457x50mm BASKET STYLE CABLE TRAY LOCATED IN RAISED FLOOR.
- 3 NEW LOCATION OF RELOCATED CABLE TRAY LOCATED IN RAISED FLOOR.
- 4 NEW 300mm x 100mm CABLE TRAY LOCATED IN RAISED FLOOR.
- 5 EXISTING 2 POST RACK TO REMAIN
- 6 EXISTING CABLE TRAY TO REMAIN
- 7 EXISTING FIBER OPTIC PANEL TO REMAIN
- 8 EXISTING 100" EMT TO REMAIN
- 9 TELEPHONE AND DATA OUTLET
- 10 EQUIPMENT RACK
- 11 19mm PLYWOOD BACKBOARD PAINTED ON ALL SIX SIDES WITH COLOUR WHITE FIRE RETARDANT PAINT.
- 12 MOUNTED ABOVE REFRIGERATOR
- 13 MOUNTED ABOVE COUNTER.
- 14 MOUNTED @ 1200mm AFF
- 15 MOUNTED @ 400mm AFF THE SAME HEIGHT AS THE ADJACENT ELECTRICAL RECEPTACLE
- 16 STUB CONDUIT TYPICAL
- 17 2x53mm EMT CONDUIT
- 18 2x100mm EMT CONDUIT
- 19 VOICE DATA OUTLET LOCATED ON FURNITURE. SSC TO UTILIZE FLOOR MOUNTED CABLE PASS-THRU SHARED WITH ELECTRICAL.
- 20 MOUNTED BEHIND LCD MONITOR
- 21 PROVIDE 27mm EMT CONDUIT FROM CEILING SPACE DOWN TO CABLE TRAY THROUGH WALL CAVITY C/W DEVICE BOX. IN ROOM 462 LOCATE DEVICE BOX IN ACCESSIBLE CEILING SPACE. IN ROOM 407 MOUNT DEVICE BOX AT 300mm BELOW CEILING SPACE.

REPUBLIC
ARCHITECTURE
INC

374 Donald Street, First Floor
Winnipeg, MB R3B 2J2

T 204 989 0102
F 204 989 0094
www.republicarchitecture.ca

HDK CONSULTING INCORPORATED
2633 Portage Avenue
Winnipeg, Manitoba
Canada, R3J 0P7
T: 204.818.0390
F: 204.818.0388
www.hdkconsulting.com
info@hdkconsulting.com
Mechanical | Electrical | Communications | Security Engineering



5		
4		
3	ISSUED FOR CONSTRUCTION	May 19, 2017
2	ISSUED FOR REVIEW 99% CONSTRUCTION DOCUMENTS	Apr. 25, 2017
1	66% CD SUBMISSION	Feb. 24, 2017
0	DESIGN DEVELOPMENT SUBMISSION	Jan. 20, 2017
Revision	Description	Date
Client		client

PSPC/SPAC
5th Floor, 10025 Jasper Avenue
Edmonton, AB

Project title
5101 50th Avenue
Yellowknife, NWT

4th Floor Tenant Fit-Up
Greenstone Building

Designed by JS	Conçu par
Drawn by IS	Dessiné par
Approved by KO	Approuvé par
PWOSC Project Manager Brenda Embury	Administrateur de Projets TPSGC
Drawing title	Titre du dessin

NEW
TELECOMMUNICATIONS
LAYOUT

Project no./No. du projet R.060383	Drawing no./No. du dessin T2.1 OF 8	Revision no. 3
---------------------------------------	---	-------------------