



1 EXISTING/DEMOLITION TELECOMMUNICATIONS LAYOUT
T1.1 1:125

- GENERAL NOTES:
1. CONTRACTOR IS RESPONSIBLE FOR THE REMOVAL OF ALL EXISTING CABLES AND CABLE TRAY LOCATED IN THE 4TH FLOOR. ALL CABLES SHALL BE REMOVED BACK TO SOURCE. BACKBONE CABLE FROM 4TH FLOOR TO BASEMENT TO REMAIN. SHARED SERVICES CANADA (SSC) IS RESPONSIBLE FOR THE REMOVAL OF PATCH PANEL.
 2. EXISTING 100mm BACKBONE CONDUIT AND 100mm HORIZONTAL CONDUIT TO REMAIN AND WILL BE REUSED.
 3. ALL EXISTING DEVICES DENOTED BY "E" SHALL REMAIN. EXISTING CABLES AFFECTED BY THE RELOCATION OF CABLE TRAY SHALL BE PROTECTED AND RELOCATED TO THE NEW LOCATION OF CABLE TRAY.

- DRAWING KEYNOTES:
- 1 EXISTING CABLE TRAY TO REMAIN.
 - 2 EXISTING 2-POST RACK TO REMAIN.
 - 3 EXISTING 100mm EMT TO REMAIN.
 - 4 EXISTING FIBRE OPTIC PANEL TO REMAIN.
 - 5 EXTENT OF EXISTING CABLE TRAY TO BE RELOCATED.

REPUBLIC
ARCHITECTURE
INC

374 Donald Street, First Floor
Winnipeg, MB R3B 2J2
T 204 989 0102
F 204 989 0094
www.republicarchitecture.ca

HDK CONSULTING INCORPORATED
2633 Portage Avenue
Winnipeg, Manitoba
Canada, R3J 0P7
T: 204.818.0390 F: 204.818.0388
www.hdkconsulting.com
info@hdkconsulting.com
Mechanical | Electrical | Communications | Security Engineering



PERMIT TO PRACTICE
HDK CONSULTING INCORPORATED
Signature _____
Date MAY 19, 2017
PERMIT NUMBER: P 1060
NT/NU Association of Professional Engineers and Geoscientists

5		
4		
3	ISSUED FOR CONSTRUCTION	May 19, 2017
2	ISSUED FOR REVIEW 99% CONSTRUCTION DOCUMENTS	Apr. 25, 2017
1	66% CD SUBMISSION	Feb. 24, 2017
0	DESIGN DEVELOPMENT SUBMISSION	Jan. 20, 2017
Revision	Description	Date

Client client

PSPC/SPAC
5th Floor, 10025 Jasper Avenue
Edmonton, AB

Project title
5101 50th Avenue
Yellowknife, NWT
4th Floor Tenant Fit-Up
Greenstone Building

Designed by JS
Drawn by IS
Approved by KO
PWSC Project Manager Brenda Embury
Administrateur de Projets TPSCG

EXISTING/DEMOLITION
TELECOMMUNICATIONS
LAYOUT

Project no./No. du projet	Drawing no./No. du dessin	Revision no.
R.060383	T1.1 OF 8	3