




1 POWER DEMOLITION LAYOUT  
E1.3 1:125



2 EXISTING ELECTRICAL ROOM LAYOUT  
E1.3 1:20

GENERAL NOTES:

1. MAINTAIN THE INTEGRITY OF ALL EXISTING SYSTEMS REQUIRED TO REMAIN OPERATIONAL. IDENTIFY ALL CIRCUIT BREAKERS, WIRING, JUNCTION BOXES AND DEVICES PRIOR TO PROCEEDING WITH WORK. CONTACT DEPARTMENTAL REPRESENTATIVE IF UNSURE BEFORE SHUTDOWNS, DEMOLITION, OR RELOCATION OF ANY DEVICES.
2. ALL ITEMS SHOWN DASHED WITH AN 'E' ARE EXISTING AND ARE TO REMAIN. ITEMS SHOWN DASHED WITH A 'D' ARE TO BE DISCONNECTED AND REMOVED AND HAVE ALL ASSOCIATED WIRE AND CONDUIT REMOVED BACK TO SOURCE.
3. WIRE AND CONDUIT SERVING DEVICES REQUIRED TO REMAIN IN USE SHALL BE RE-ROUTED AND DIVERTED AS REQUIRED TO MAINTAIN OPERATION. EXTEND, RE-ROUTE, RE-WIRE AND RE-CONNECT AS REQUIRED. CONFIRM EXISTING ON SITE.
4. PROVIDE NEW BLANK STAINLESS STEEL COVERPLATES FOR ALL ABANDONED OUTLETS.
5. REPORT ANY DISCREPANCIES BETWEEN THE CONTRACT DOCUMENTS AND SITE OBSERVATIONS TO DEPARTMENTAL REPRESENTATIVE.
6. NOT ALL DEVICES AND ELECTRICAL EQUIPMENT IS BEING SHOWN ON ELECTRICAL DRAWINGS. REMOVE ALL EXISTING ELECTRICAL DEVICES SHOWN OR NOT LOCATED ON INDICATED WALLS OR PORTIONS OF THE BUILDING BEING DEMOLISHED OR MODIFIED. MAINTAIN INTEGRITY OF ALL EXISTING ELECTRICAL SYSTEMS IN AREAS NOT INCLUDED IN THIS PROJECT AND IN PARTS OF THE BUILDING WITHIN RENOVATION THAT ARE NOT SUBJECTED TO ANY DEMOLITION WORK.
7. REFER TO SYMBOL SCHEDULE FOR ELECTRICAL SYMBOLS AND LETTER DESIGNATIONS.
8. ALL EXISTING DEVICES ON WALLS, FLOORS OR CEILING NOT BEING AFFECTED BY RENOVATION ARE TO REMAIN.
9. SYSTEMS AND DEVICES IN AREAS OF LIMITED SCOPE OF WORK AREAS TO REMAIN OPERATIONAL. PROVIDE ALL MODIFICATIONS TO ACCOMMODATE SCOPE OF WORK.
10. EXISTING PHOTOCELL CONTROLS TO BE DISCONNECTED AND REMOVED TO ACCOMMODATE NEW LIGHTING CONTROL DEVICES. CONFIRM REMOVAL OF PHOTOCELL CONTROLS ON SITE PRIOR TO REMOVAL.

REPUBLIC  
ARCHITECTURE  
INC

374 Donald Street, First Floor  
Winnipeg, MB R3B 2J2

T 204 989 0102  
F 204 989 0094  
www.republicarchitecture.ca

HDK CONSULTING INCORPORATED  
2633 Portage Avenue  
Winnipeg, Manitoba  
Canada, R3J 0P7  
T: 204.818.0390  
F: 204.818.0388  
www.hdkconsulting.com  
info@hdkconsulting.com  
Mechanical | Electrical | Communications | Security Engineering



PERMIT TO PRACTICE  
HDK CONSULTING INCORPORATED  
Signature: [Signature]  
Date: May 19, 2017  
PERMIT NUMBER: P 1060  
NTNU Association of Professional Engineers and Geoscientists

5		
4		
3	ISSUED FOR CONSTRUCTION	May 19, 2017
2	ISSUED FOR REVIEW 99% CONSTRUCTION DOCUMENTS	Apr. 25, 2017
1	66% CD SUBMISSION	Feb. 24, 2017
0	DESIGN DEVELOPMENT SUBMISSION	Jan. 20, 2017
Revision	Description	Date

Client client

PSPC/SPAC

5th Floor, 10025 Jasper Avenue  
Edmonton, AB

Project title Projet

5101 50th Avenue  
Yellowknife, NWT

4th Floor Tenant Fit-Up  
Greenstone Building

Designed by Conçu par

PL

Drawn by Dessiné par

RD

Approved by Approuvé par

HCC

PWSSC Project Manager Administrateur de Projets TPSSC

Brenda Embury

Drawing title Titre du dessin

POWER DEMOLITION LAYOUT

Project no./No. du projet Drawing no./No. du dessin Revision no.

R.060383

E1.3

3

OF 13