



1 LIGHTING DEMOLITION LAYOUT
E1.1 1:125

GENERAL NOTES:

1. MAINTAIN THE INTEGRITY OF ALL EXISTING SYSTEMS REQUIRED TO REMAIN OPERATIONAL. IDENTIFY ALL CIRCUIT BREAKERS, WIRING, JUNCTION BOXES AND DEVICES PRIOR TO PROCEEDING WITH WORK. CONTACT DEPARTMENTAL REPRESENTATIVE IF UNSURE BEFORE SHUTDOWNS, DEMOLITION, OR RELOCATION OF ANY DEVICES.
2. ALL ITEMS SHOWN DASHED WITH AN 'E' ARE EXISTING AND ARE TO REMAIN. ITEMS SHOWN DASHED WITH A 'D' ARE TO BE DISCONNECTED AND DEMOLISHED/REMOVED AND TRANSPORTED TO DESIGNATED SITE TO BE CONFIRMED BY DEPARTMENTAL REPRESENTATIVE. INCLUDE ALL COSTS IN BASE BID. REMOVED AND HAVE ALL ASSOCIATED WIRE AND CONDUIT REMOVED BACK TO SOURCE. RE-LABEL BREAKER AS SPARE IF NOT RE-USED.
3. EXTEND, RE-ROUTE, RE-WIRE AND RE-CONNECT ALL EXISTING DEVICES TO BE RELOCATED.
4. WIRE AND CONDUIT SERVING DEVICES REQUIRED TO REMAIN IN USE SHALL BE RE-ROUTED AND DIVERTED AS REQUIRED TO MAINTAIN OPERATION. EXTEND, RE-ROUTE, RE-WIRE AND RE-CONNECT AS REQUIRED. CONFIRM EXISTING ON SITE.
5. NOT ALL DEVICES AND ELECTRICAL EQUIPMENT IS BEING SHOWN ON ELECTRICAL DRAWINGS. REMOVE ALL EXISTING ELECTRICAL DEVICES SHOWN OR NOT LOCATED ON INDICATED WALLS OR PORTIONS OF THE BUILDING BEING DEMOLISHED OR MODIFIED. MAINTAIN INTEGRITY OF ALL EXISTING ELECTRICAL SYSTEMS IN AREAS NOT INCLUDED IN THIS PROJECT AND IN PARTS OF THE BUILDING WITHIN RENOVATION THAT ARE NOT SUBJECTED TO ANY DEMOLITION WORK.
6. REFER TO SYMBOL SCHEDULE FOR ELECTRICAL SYMBOLS AND LETTER DESIGNATIONS.
7. EXISTING LUMINAIRES IN AREAS NOT DIRECTLY INCLUDED IN RENOVATION AREA TO REMAIN.
8. REPORT ANY DISCREPANCIES BETWEEN CONTRACT DOCUMENTS AND SITE OBSERVATION TO DEPARTMENTAL REPRESENTATIVE IN TIMELY MANNER.
9. ALL EXISTING LUMINAIRES IN AREA OF RENOVATION TO BE DISCONNECTED FROM EXISTING DOUGLAS PANEL AND RETURNED TO OWNER'S DESIGNATED LOCATION. ALLOW FOR DISPOSAL OF UNUSED EQUIPMENT AND DEVICES.
10. SYSTEMS AND DEVICES IN AREAS OF LIMITED SCOPE OF WORK AREAS TO REMAIN OPERATIONAL. PROVIDE ALL MODIFICATIONS TO ACCOMMODATE SCOPE OF WORK.

REPUBLIC
ARCHITECTURE
INC

374 Donald Street, First Floor
Winnipeg, MB R3B 2J2

T 204 989 0102
F 204 989 0094
www.republicarchitecture.ca

HDK CONSULTING
INCORPORATED
2633 Portage Avenue
Winnipeg, Manitoba
Canada, R3J 0P7
T: 204.818.0390
F: 204.818.0388
www.hdkconsulting.com
info@hdkconsulting.com
Mechanical | Electrical | Communications | Security Engineering



PERMIT TO PRACTICE
HDK CONSULTING INCORPORATED
Signature
Date
PERMIT NUMBER: P 1060
NTNU Association of Professional
Engineers and Geoscientists

5		
4		
3	ISSUED FOR CONSTRUCTION	May 19, 2017
2	ISSUED FOR REVIEW 99% CONSTRUCTION DOCUMENTS	Apr. 25, 2017
1	66% CD SUBMISSION	Feb. 24, 2017
0	DESIGN DEVELOPMENT SUBMISSION	Jan. 20, 2017
Revision	Description	Date
Client		client

PSPC/SPAC

5th Floor, 10025 Jasper Avenue
Edmonton, AB

Project title
5101 50th Avenue
Yellowknife, NWT

4th Floor Tenant Fit-Up
Greenstone Building

Designed by PL	Conçu par
Drawn by RD	Dessiné par
Approved by HCC	Approuvé par
PWSSC Project Manager Brenda Embury	Administrateur de Projets TPSSC
Drawing title	Titre du dessin

LIGHTING DEMOLITION LAYOUT

Project no./No. du projet	Drawing no./No. du dessin	Revision no.
R.060383	E1.1 OF 13	3