

**Part 1            General**

**1.1            ACTION AND INFORMATIONAL SUBMITTALS**

- .1    Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2    Product Data:
  - .1    Submit manufacturer's instructions, printed product literature and data sheets and include product characteristics, performance criteria, physical size, finish and limitations.
- .3    Shop Drawings:
  - .1    Indicate on drawings:
    - .1    Mounting arrangements.
    - .2    Operating and maintenance clearances.
  - .2    Shop drawings and product data accompanied by:
    - .1    Detailed drawings of bases, supports, and anchor bolts.
    - .2    Acoustical sound power data, where applicable.
    - .3    Points of operation on performance curves.
    - .4    Manufacturer to certify current model production.
    - .5    Certification of compliance to applicable codes.
  - .3    In addition to transmittal letter referred to in Section 01 33 00 - Submittal Procedures: use MCAC "Shop Drawing Submittal Title Sheet". Identify section and paragraph number.

**1.2            CLOSEOUT SUBMITTALS**

- .1    Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2    Operation and Maintenance Data: submit operation and maintenance data for incorporation into manual.
  - .1    Operation and maintenance manual approved by, and final copies deposited with, Departmental Representative before final inspection.
  - .2    Operation data to include:
    - .1    Control schematics for systems including environmental controls.
    - .2    Description of systems and their controls.
    - .3    Description of operation of systems at various loads together with reset schedules and seasonal variances.
    - .4    Operation instruction for systems and component.
    - .5    Description of actions to be taken in event of equipment failure.
    - .6    Valves schedule and flow diagram.
    - .7    Colour coding chart.
  - .3    Maintenance data to include:
    - .1    Servicing, maintenance, operation and trouble-shooting instructions for each item of equipment.

- .2 Data to include schedules of tasks, frequency, tools required and task time.
- .4 Performance data to include:
  - .1 Equipment manufacturer's performance datasheets with point of operation as left after commissioning is complete.
  - .2 Equipment performance verification test results.
  - .3 Special performance data as specified.
  - .4 Testing, adjusting and balancing reports as specified in Section 23 05 93 - Testing, Adjusting and Balancing for HVAC.
- .5 Approvals:
  - .1 Submit 2 copies of draft Operation and Maintenance Manual to Departmental Representative for approval. Submission of individual data will not be accepted unless directed by Departmental Representative.
  - .2 Make changes as required and re-submit as directed by Departmental Representative.
- .6 Additional data:
  - .1 Prepare and insert into operation and maintenance manual additional data when need for it becomes apparent during specified demonstrations and instructions.
- .7 Site records:
  - .1 Departmental Representative will provide 1 set of reproducible mechanical drawings. Provide sets of white prints as required for each phase of work. Mark changes as work progresses and as changes occur. Include changes to existing mechanical systems, control systems and low voltage control wiring.
  - .2 Transfer information weekly to reproducibles, revising reproducibles to show work as actually installed.
  - .3 Use different colour waterproof ink for each service.
  - .4 Make available for reference purposes and inspection.
- .8 As-built drawings:
  - .1 Prior to start of Testing, Adjusting and Balancing for HVAC, finalize production of as-built drawings.
  - .2 Identify each drawing in lower right hand corner in letters at least 12 mm high as follows: - "AS BUILT DRAWINGS: THIS DRAWING HAS BEEN REVISED TO SHOW MECHANICAL SYSTEMS AS INSTALLED" (Signature of Contractor) (Date).
  - .3 Submit to Departmental Representative for approval and make corrections as directed.
  - .4 Perform testing, adjusting and balancing for HVAC using as-built drawings.
  - .5 Submit completed reproducible as-built drawings with Operating and Maintenance Manuals.
- .9 Submit copies of as-built drawings for inclusion in final TAB report.

### **1.3 MAINTENANCE MATERIAL SUBMITTALS**

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Furnish spare parts as follows:
  - .1 One set of packing for each pump.
  - .2 One casing joint gasket for each size pump.
  - .3 One head gasket set for each heat exchanger.
  - .4 One glass for each gauge glass.
  - .5 One filter cartridge or set of filter media for each filter or filter bank in addition to final operating set.
- .3 Provide one set of special tools required to service equipment as recommended by manufacturers.
- .4 Furnish one commercial quality grease gun, grease and adapters to suit different types of grease and grease fittings.

### **1.4 DELIVERY, STORAGE AND HANDLING**

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
  - .1 Store materials indoors in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
  - .2 Store and protect equipment from nicks, scratches, and blemishes.
  - .3 Replace defective or damaged materials with new.
- .4 Packaging Waste Management: remove pallets, crates, padding, and packaging materials from site.

## **Part 2 Products**

### **2.1 MATERIALS**

- .1 HVAC and R Equipment:
  - .1 Refrigerant:
    - .1 HCFC based refrigerant.
    - .2 HFC based refrigerant.

**Part 3 Execution**

**3.1 EXAMINATION**

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for installation in accordance with manufacturer's written instructions.
  - .1 Visually inspect substrate in presence of Departmental Representative.
  - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
  - .3 Proceed with installation only after unacceptable conditions have been remedied.

**3.2 SYSTEM CLEANING**

- .1 Clean interior and exterior of all systems. Vacuum interior of ductwork and air handling units.

**3.3 FIELD QUALITY CONTROL**

- .1 Site Tests: conduct following tests in accordance with Section 01 45 00 - Quality Control and submit report as described in PART 1 - ACTION AND INFORMATIONAL SUBMITTALS.
- .2 Manufacturer's Field Services:
  - .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Manufacturer's Field Reports as described in PART 1 - ACTION AND INFORMATIONAL SUBMITTALS.
  - .2 Provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.

**3.4 DEMONSTRATION**

- .1 Departmental Representative will use equipment and systems for test purposes prior to acceptance. Supply labour, material, and instruments required for testing.
- .2 Supply tools, equipment and personnel to demonstrate and instruct operating and maintenance personnel in operating, controlling, adjusting, trouble-shooting and servicing of all systems and equipment during regular work hours, prior to acceptance.
- .3 Use operation and maintenance manual, as-built drawings, and audio visual aids as part of instruction materials.
- .4 Instruction duration time requirements as specified in appropriate sections.

**3.5 CLEANING**

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
  - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.

- .3 Waste Management: separate waste materials for recycling.
  - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

**3.6 PROTECTION**

- .1 Protect equipment and systems openings from dirt, dust, and other foreign materials with materials appropriate to system.

**END OF SECTION**

**Part 1 General**

**1.1 USE OF SYSTEMS**

- .1 Use of new or existing permanent heating and ventilating systems for supplying temporary heat and ventilation is permitted only under following conditions:
  - .1 Entire system is complete, pressure tested, cleaned, flushed out.
  - .2 There is no possibility of damage.
  - .3 Supply ventilation systems are protected by 60 % filters, inspected daily, changed every week 2 weeks or more frequently as required.
  - .4 Return systems have approved filters over openings, inlets, outlets.
  - .5 Systems will be:
    - .1 Operated as per manufacturer's recommendations and instructions.
    - .2 Operated by Contractor.
    - .3 Monitored continuously by Contractor.
  - .6 Warranties and guarantees are not relaxed.
  - .7 Regular preventive and other manufacturers recommended maintenance routines are performed by Contractor at own expense and under supervision of Departmental Representative.
  - .8 Refurbish entire system before static completion; clean internally and externally, restore to "as- new" condition, replace filters in air systems.
- .2 Filters specified in this Section are over and above those specified in other Sections of this project.
- .3 Exhaust systems are not included in approvals for temporary heating ventilation.

**Part 2 Products**

**2.1 NOT USED**

- .1 Not Used.

**Part 3 Execution**

**3.1 NOT USED**

- .1 Not Used.

**END OF SECTION**

**Part 1 General**

**1.1 ACTION AND INFORMATIONAL SUBMITTALS**

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
  - .1 Provide manufacturer's printed product literature, specifications and datasheets for piping and equipment and include product characteristics, performance criteria, physical size, finish and limitations.

**1.2 QUALITY ASSURANCE**

- .1 Sustainability Standards Certification:
  - .1 Low-Emitting Materials: provide listing of sealants coatings used in building, comply with VOC and chemical component limits or restriction requirements.

**1.3 DELIVERY, STORAGE AND HANDLING**

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements:
  - .1 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Packaging Waste Management: remove from site pallets, crates, padding and packaging materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

**Part 2 Products**

**2.1 MATERIAL**

- .1 Paint: zinc-rich to CAN/CGSB-1.181.
  - .1 Primers, paints and coating: in accordance with manufacturer's recommendations for surface conditions.
  - .2 Primer: maximum VOC limit 250 g/L to Standard GS-11.
  - .3 Paints: maximum VOC limit 150 g/L to Standard GS-11.
- .2 Sealants: in accordance with Section 07 92 00 - Joint Sealants.
  - .1 Sealants: maximum VOC limit to SCAQMD Rule 1168.
- .3 Sealants: maximum VOC limit to SCAQMD Rule 1168.
- .4 Adhesives: maximum VOC limit to SCAQMD Rule 1168.

**Part 3            Execution**

**3.1                APPLICATION**

- .1        Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

**3.2                CONNECTIONS TO EQUIPMENT**

- .1        In accordance with manufacturer's instructions unless otherwise indicated.
- .2        Use valves and either unions or flanges for isolation and ease of maintenance and assembly.
- .3        Use double swing joints when equipment mounted on vibration isolation and when piping subject to movement.

**3.3                CLEARANCES**

- .1        Provide clearance around systems, equipment and components for observation of operation, inspection, servicing, maintenance and as recommended by manufacturer and National Fire Code of Canada and CSA B139.
- .2        Provide space for disassembly, removal of equipment and components as recommended by manufacturer and CSA B139 without interrupting operation of other system, equipment, components.

**3.4                DRAINS**

- .1        Install piping with grade in direction of flow except as indicated.
- .2        Install drain valve at low points in piping systems, at equipment and at section isolating valves.
- .3        Pipe each drain valve discharge separately to above floor drain.
  - .1        Discharge to be visible.
- .4        Drain valves: NPS 3/4 gate or globe valves unless indicated otherwise, with hose end male thread, cap and chain.

**3.5                AIR VENTS**

- .1        Install manual air vents to CSA B139 and at high points in piping systems.
- .2        Install isolating valve at each automatic air valve.
- .3        Install drain piping to approved location and terminate where discharge is visible.

**3.6                DIELECTRIC COUPLINGS**

- .1        General: compatible with system, to suit pressure rating of system.
- .2        Locations: where dissimilar metals are joined.
- .3        NPS 2 and under: isolating unions or bronze valves.
- .4        Over NPS 2: isolating flanges.



### **3.7 PIPEWORK INSTALLATION**

- .1 Install pipework to CSA B139.
- .2 Screwed fittings jointed with Teflon tape.
- .3 Protect openings against entry of foreign material.
- .4 Install to isolate equipment and allow removal without interrupting operation of other equipment or systems.
- .5 Assemble piping using fittings manufactured to ANSI standards.
- .6 Saddle type branch fittings may be used on mains if branch line is no larger than half size of main.
  - .1 Hole saw (or drill) and ream main to maintain full inside diameter of branch line prior to welding saddle.
- .7 Install exposed piping, equipment, rectangular cleanouts and similar items parallel or perpendicular to building lines.
- .8 Install concealed pipework to minimize furring space, maximize headroom, conserve space.
- .9 Slope piping, except where indicated, in direction of flow for positive drainage and venting.
- .10 Install, except where indicated, to permit separate thermal insulation of each pipe.
- .11 Group piping wherever possible and as indicated.
- .12 Ream pipes, remove scale and other foreign material before assembly.
- .13 Use eccentric reducers at pipe size changes to ensure positive drainage and venting.
- .14 Provide for thermal expansion as indicated.
- .15 Valves:
  - .1 Install in accessible locations.
  - .2 Remove interior parts before soldering.
  - .3 Install with stems above horizontal position unless indicated.
  - .4 Valves accessible for maintenance without removing adjacent piping.
  - .5 Install globe valves in bypass around control valves.
  - .6 Use butterfly valves at branch take-offs for isolating purposes except where specified.
  - .7 Install butterfly valves between weld neck flanges to ensure full compression of liner.
  - .8 Use chain operators on valves NPS 2 1/2 and larger where installed more than 2400 mm above floor in Mechanical Rooms.

### **3.8 SLEEVES**

- .1 General: install where pipes pass through masonry, concrete structures, fire rated assemblies, and as indicated.
- .2 Material: schedule 40 black steel pipe.

- .3 Construction: use annular fins continuously welded at mid-point at foundation walls and where sleeves extend above finished floors.
- .4 Sizes: 6 mm minimum clearance between sleeve and uninsulated pipe or between sleeve and insulation.
- .5 Installation:
  - .1 Concrete, masonry walls, concrete floors on grade: terminate flush with finished surface.
  - .2 Other floors: terminate 25 mm above finished floor.
  - .3 Before installation, paint exposed exterior surfaces with heavy application of zinc-rich paint to CAN/CGSB-1.181.
- .6 Sealing:
  - .1 Foundation walls and below grade floors: fire retardant, waterproof non-hardening mastic.
  - .2 Elsewhere:
    - .1 Provide space for firestopping.
    - .2 Maintain fire rating integrity.
  - .3 Sleeves installed for future use: fill with lime plaster or other easily removable filler.
  - .4 Ensure no contact between copper pipe or tube and sleeve.

### **3.9 ESCUTCHEONS**

- .1 Install on pipes passing through walls, partitions, floors, and ceilings in finished areas.
- .2 Construction: one piece type with set screws.
  - .1 Chrome or nickel plated brass or type 302 stainless steel..
- .3 Sizes: outside diameter to cover opening or sleeve.
  - .1 Inside diameter to fit around pipe or outside of insulation if so provided.

### **3.10 PREPARATION FOR FIRE STOPPING**

- .1 Install firestopping within annular space between pipes, ducts, insulation and adjacent fire separation.
- .2 Uninsulated unheated pipes not subject to movement: no special preparation.
- .3 Uninsulated heated pipes subject to movement: wrap with non-combustible smooth material to permit pipe movement without damaging firestopping material or installation.
- .4 Insulated pipes and ducts: ensure integrity of insulation and vapour barriers.

### **3.11 FLUSHING OUT OF PIPING SYSTEMS**

- .1 Flush system in accordance with Section 23 08 02 - Cleaning and Start-up of Mechanical Piping Systems.
- .2 Before start-up, clean interior of piping systems in accordance with requirements of Section 01 74 11 - Cleaning.

- .3 Preparatory to acceptance, clean and refurbish equipment and leave in operating condition, including replacement of filters in piping systems.

### **3.12 PRESSURE TESTING OF EQUIPMENT AND PIPEWORK**

- .1 Advise Departmental Representative 48 hours minimum prior to performance of pressure tests.
- .2 Pipework: test as specified in relevant sections of heating, ventilating and air conditioning work.
- .3 Maintain specified test pressure without loss for 4 hours minimum unless specified for longer period of time in relevant mechanical sections.
- .4 Prior to tests, isolate equipment and other parts which are not designed to withstand test pressure or media.
- .5 Conduct tests in presence of Departmental Representative.
- .6 Pay costs for repairs or replacement, retesting, and making good. Departmental Representative to determine whether repair or replacement is appropriate.
- .7 Insulate or conceal work only after approval and certification of tests by Departmental Representative.

### **3.13 EXISTING SYSTEMS**

- .1 Connect into existing piping systems at times approved by Departmental Representative.
- .2 Request written approval by Departmental Representative 10 days minimum, prior to commencement of work.
- .3 Be responsible for damage to existing plant by this work.

### **3.14 CLEANING**

- .1 Clean in accordance with Section 01 74 11 - Cleaning.
  - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.
- .2 Waste Management: separate waste materials for recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

**END OF SECTION**

**Part 1 General**

**1.1 REFERENCES**

- .1 American National Standards Institute (ANSI)/American Society of Mechanical Engineers (ASME)
  - .1 ANSI/ASME B1.20.1-1983(R2006), Pipe Threads, General Purpose (Inch).
  - .2 ANSI/ASME B16.18-2001, Cast Copper Alloy Solder Joint Pressure Fittings.
- .2 ASTM International
  - .1 ASTM A276-08, Standard Specification for Stainless Steel Bars and Shapes.
  - .2 ASTM B62-02, Standard Specification for Composition Bronze or Ounce Metal Castings.
  - .3 ASTM B505/B505M-08a, Standard Specification for Copper-Base Alloy Continuous Castings.
- .3 Manufacturers Standardization Society of the Valve and Fittings Industry, Inc. (MSS)
  - .1 MSS-SP-25-1998, Standard Marking System for Valves, Fittings, Flanges and Unions.
  - .2 MSS-SP-80-2008, Bronze Gate Globe, Angle and Check Valves.
  - .3 MSS-SP-110-1996, Ball Valves, Threaded, Socket-Welding, Solder Joint, Grooved and Flared Ends.

**1.2 ACTION AND INFORMATIONAL SUBMITTALS**

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
  - .1 Provide manufacturer's printed product literature and data sheets for equipment and systems and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
  - .1 Submit drawings as per Section 01 33 00, Submittal Procedures.
  - .2 Submit data for valves specified in this Section.

**1.3 CLOSEOUT SUBMITTALS**

- .1 Provide maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

**1.4 MAINTENANCE MATERIAL SUBMITTALS**

- .1 Extra Materials/Spare Parts:
  - .1 Furnish following spare parts:
    - .1 Valve seats: one for every 10 valves each size, minimum 1.
    - .2 Discs: one for every 10 valves, each size. Minimum 1.
    - .3 Stem packing: one for every 10 valves, each size. Minimum 1.

- .4 Valve handles: 2 of each size.
- .5 Gaskets for flanges: one for every 10 flanged joints.
- .2 Tools:
  - .1 Furnish special tools for maintenance of systems and equipment.
  - .2 Include following:
    - .1 Lubricant gun for expansion joints.

## **1.5 DELIVERY, STORAGE AND HANDLING**

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements:
  - .1 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Packaging Waste Management: remove from site pallets, crates, padding and packaging materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

## **Part 2 Products**

### **2.1 MATERIALS**

- .1 Valves:
  - .1 Except for specialty valves, to be single manufacturer.
  - .2 Products to have CRN registration numbers.
- .2 End Connections:
  - .1 Connection into adjacent piping/tubing:
    - .1 Steel pipe systems: screwed ends to ANSI/ASME B1.20.1.
    - .2 Copper tube systems: grooved ends to ANSI/ASME B16.18.
- .3 Lockshield Keys:
  - .1 Where lockshield valves are specified, provide 10 keys of each size: malleable iron cadmium plated.
- .4 Gate Valves:
  - .1 Requirements common to gate valves, unless specified otherwise:
    - .1 Standard specification: MSS SP-80.
    - .2 Bonnet: union with hexagonal shoulders.
    - .3 Connections: screwed with hexagonal shoulders.
    - .4 Inspection and pressure testing: to MSS SP-80. Tests to be hydrostatic.
    - .5 Packing: non-asbestos.
    - .6 Handwheel: non-ferrous.
    - .7 Handwheel Nut: bronze to ASTM B62.

- .2 NPS 2 and under, non-rising stem, solid wedge disc, Class 125
  - .1 Body: with long disc guides, screwed bonnet with stem retaining nut.
  - .2 Operator: Handwheel.
- .3 NPS 2 and under, non-rising stem, solid wedge disc, Class 150:
  - .1 Body: with long disc guides, screwed bonnet with stem retaining nut.
  - .2 Operator: handwheel.
- .4 NPS 2 and under, rising stem, split wedge disc, Class 125:
  - .1 Body: with long disc guides, screwed bonnet.
  - .2 Disc: split wedge, bronze to ASTM B283, loosely secured to stem.
  - .3 Operator: handwheel lockshield.
- .5 NPS 2 and under, rising stem, solid wedge disc, Class 125:
  - .1 Body: with long disc guides, screwed bonnet.
  - .2 Operator: handwheel.
- .6 NPS 2 and under, rising stem, solid wedge disc, Class 150:
  - .1 Body: with long disc guides, screwed bonnet.
  - .2 Operator: handwheel.
- .5 Globe Valves:
  - .1 Requirements common to globe valves, unless specified otherwise:
    - .1 Standard specification: MSS SP-80.
    - .2 Bonnet: union with hexagonal shoulders.
    - .3 Connections: screwed with hexagonal shoulders.
    - .4 Pressure testing: to MSS SP-80. Tests to be hydrostatic.
    - .5 Stuffing box: threaded to bonnet with gland follower, packing nut, high grade non-asbestos packing.
    - .6 Handwheel: non-ferrous.
    - .7 Handwheel Nut: bronze to ASTM B62.
  - .2 NPS 2 and under, composition disc, Class 125:
    - .1 Body and bonnet: screwed bonnet.
    - .2 Disc and seat: renewable rotating PTFE disc composition to suit service conditions, regrindable bronze seat, loosely secured to bronze stem to ASTM B505.
    - .3 Operator: handwheel.
  - .3 NPS 2 and under, composition disc, Class 150:
    - .1 Body and bonnet: union bonnet.
    - .2 Disc and seat: renewable rotating PTFE disc in easily removable disc holder, regrindable bronze seat, loosely secured to bronze stem to ASTM B505.
    - .3 Operator: handwheel.

- .4 NPS 2 and under, plug disc, Class 150, screwed ends:
  - .1 Body and bonnet: union bonnet.
  - .2 Disc and seat ring: tapered plug type with disc stem ring of AISI S420 stainless steel to ASTM A276, loosely secured to stem.
  - .3 Operator: handwheel.
- .5 Angle valve, NPS 2 and under, composition disc, Class 150:
  - .1 Body and bonnet: union bonnet.
  - .2 Disc and seat: renewable rotating PTFE disc in slip-on easily removable disc holder having integral guides, regrindable bronze seat, loosely secured to stem.
  - .3 Operator: handwheel.
- .6 Check Valves:
  - .1 Requirements common to check valves, unless specified otherwise:
    - .1 Standard specification: MSS SP-80.
    - .2 Connections: screwed with hexagonal shoulders.
  - .2 NPS 2 and under, swing type, bronze disc, Class 125:
    - .1 Body: Y-pattern with integral seat at 45 degrees, screw-in cap with hex head.
    - .2 Disc and seat: renewable rotating disc, two-piece hinge disc construction; seat: regrindable.
  - .3 NPS 2 and under, swing type, bronze disc:
    - .1 Body: Y-pattern with integral seat at 45 degrees, screw-in cap with hex head.
    - .2 Disc and seat: renewable rotating disc, two-piece hinge disc construction; seat: regrindable.
  - .4 NPS 2 and under, swing type, composition disc, Class 200:
    - .1 Body: Y-pattern with integral seat at 45 degrees, screw-in cap with hex head.
    - .2 Disc: renewable rotating disc of number 6 composition to suit service conditions, bronze two-piece hinge disc construction.
  - .5 NPS 2 and under, horizontal lift type, composition disc, Class 150:
    - .1 Body: with integral seat, union bonnet ring with hex shoulders, cap.
    - .2 Disc: renewable PTFE no. 6 composition rotating disc in disc holder having guides top and bottom, of bronze to ASTM B62.
  - .6 NPS 2 and under, vertical lift type, bronze disc, Class 125:
    - .1 Disc: rotating disc having guides top and bottom, disc guides, retaining rings.
- .7 Silent Check Valves:
  - .1 NPS 2 and under:
    - .1 Body: cast high tensile bronze to ASTM B62 with integral seat.
    - .2 Pressure rating: Class 125.
    - .3 Connections: screwed ends to ANSI B1.20.1 and with hex. shoulders.

- .4 Disc and seat: renewable rotating disc.
  - .5 Stainless steel spring, heavy duty.
  - .6 Seat: regrindable.
- .8 Ball Valves:
  - .1 NPS 2 and under:
    - .1 Body and cap: cast high tensile bronze to ASTM B62.
    - .2 Pressure rating: Class125.
    - .3 Connections: screwed ends to ANSI B1.20.1 and with hexagonal shoulders.
    - .4 Stem: tamperproof ball drive.
    - .5 Stem packing nut: external to body.
    - .6 Ball and seat: replaceable stainless steel solid ball and Teflon seats.
    - .7 Stem seal: TFE with external packing nut.
    - .8 Operator: removable lever handle.
- .9 Butterfly Valves:
  - .1 NPS 2 1/2 through NPS 6, 2068 kPa with grooved ends.
    - .1 Body: cast bronze, with copper-tube dimensioned grooved ends.
    - .2 Disc: elastomer coated ductile iron with integrally cast stem.
    - .3 Operator: lever handwheel.

### **Part 3 Execution**

#### **3.1 INSTALLATION**

- .1 Install rising stem valves in upright position with stem above horizontal.
- .2 Remove internal parts before soldering.
- .3 Install valves with unions at each piece of equipment arranged to allow servicing, maintenance, and equipment removal.

#### **3.2 CLEANING**

- .1 Clean in accordance with Section 01 74 11 - Cleaning.
  - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.
- .2 Waste Management: separate waste materials for recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

**END OF SECTION**



**Part 1 General**

**1.1 REFERENCES**

- .1 ASTM International
  - .1 ASTM A125-1996(2007), Standard Specification for Steel Springs, Helical, Heat-Treated.
  - .2 ASTM A563-07a, Standard Specification for Carbon and Alloy Steel Nuts.
- .2 Factory Mutual (FM)
- .3 Manufacturer's Standardization Society of the Valves and Fittings Industry (MSS)
  - .1 MSS SP58-2002, Pipe Hangers and Supports - Materials, Design and Manufacture.
  - .2 MSS SP69-2003, Pipe Hangers and Supports - Selection and Application.
  - .3 MSS SP89-2003, Pipe Hangers and Supports - Fabrication and Installation Practices.
- .4 Underwriter's Laboratories of Canada (ULC)
- .5 ASME B16.5, Pipe Flanges and Flanged Fittings or B31, Power & Process Piping.

**1.2 ACTION AND INFORMATIONAL SUBMITTALS**

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
  - .1 Provide manufacturer's printed product literature and data sheets for hangers and supports and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
  - .1 Submit drawings stamped as per 01 3300, Submittal Procedures.
  - .2 Submit shop drawings for:
    - .1 Bases, hangers and supports.
    - .2 Connections to equipment and structure.
    - .3 Structural assemblies.
- .4 Certificates:
  - .1 Submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .5 Manufacturers' Instructions:
  - .1 Provide manufacturer's installation instructions.
    - .1 Departmental Representative will make available 1 copy of systems supplier's installation instructions.

### **1.3 CLOSEOUT SUBMITTALS**

- .1 Provide maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

### **1.4 DELIVERY, STORAGE AND HANDLING**

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements:
  - .1 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Packaging Waste Management: remove from site pallets, crates, padding and packaging materials in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

## **Part 2 Products**

### **2.1 SYSTEM DESCRIPTION**

- .1 Design Requirements:
  - .1 Construct pipe hanger and support to manufacturer's recommendations utilizing manufacturer's regular production components, parts and assemblies.
  - .2 Base maximum load ratings on allowable stresses prescribed by ASME B31.1 or MSS SP58.
  - .3 Ensure that supports, guides, anchors do not transmit excessive quantities of heat to building structure.
  - .4 Design hangers and supports to support systems under conditions of operation, allow free expansion and contraction, prevent excessive stresses from being introduced into pipework or connected equipment.
  - .5 Provide for vertical adjustments after erection and during commissioning. Amount of adjustment in accordance with MSS SP58.

### **2.2 GENERAL**

- .1 Fabricate hangers, supports and sway braces in accordance with MSS SP58.

### **2.3 PIPE HANGERS**

- .1 Finishes:
  - .1 Pipe hangers and supports: galvanized after manufacture.
  - .2 Use hot dipped galvanizing process.
  - .3 Ensure steel hangers in contact with copper piping are epoxy coated.

- .2 Upper attachment structural: suspension from lower flange of I-Beam:
  - .1 Cold piping NPS 2 maximum: malleable iron C-clamp with hardened steel cup point setscrew, locknut carbon steel retaining clip.
    - .1 Rod: 9 mm UL listed.
  - .2 Cold piping NPS 2 1/2 or greater, hot piping: malleable iron beam clamp, eye rod, jaws and extension with carbon steel retaining clip, tie rod, nuts and washers, UL listed to MSS-SP58.
- .3 Upper attachment structural: suspension from upper flange of I-Beam:
  - .1 Cold piping NPS 2 maximum: ductile iron top-of-beam C-clamp with hardened steel cup point setscrew, locknut and carbon steel retaining clip, UL listed and to MSS SP69.
  - .2 Cold piping NPS 2 1/2 or greater, hot piping: malleable iron top-of-beam jaw-clamp with hooked rod, spring washer, plain washer and nut UL listed.
- .4 Upper attachment to concrete:
  - .1 Ceiling: carbon steel welded eye rod, clevis plate, clevis pin and cotters with weldless forged steel eye nut. Ensure eye 6 mm minimum greater than rod diameter.
  - .2 Concrete inserts: wedge shaped body with knockout protector plate UL listed to MSS SP69.
- .5 Shop and field-fabricated assemblies:
  - .1 Trapeze hanger assemblies.
  - .2 Steel brackets.
- .6 Hanger rods: threaded rod material to MSS SP58:
  - .1 Ensure that hanger rods are subject to tensile loading only.
  - .2 Provide linkages where lateral or axial movement of pipework is anticipated.
  - .3 Do not use 22 mm rod.
- .7 Pipe attachments: material to MSS SP58:
  - .1 Attachments for steel piping: carbon steel galvanized.
  - .2 Attachments for copper piping: copper plated black steel.
  - .3 Use insulation shields for hot pipework.
  - .4 Oversize pipe hangers and supports.
- .8 Adjustable clevis: material to MSS SP69 UL listed FM approved, clevis bolt with nipple spacer and vertical adjustment nuts above and below clevis.
  - .1 Ensure "U" has hole in bottom for rivetting to insulation shields.
- .9 Yoke style pipe roll: carbon steel yoke, rod and nuts with cast iron roll, to MSS SP69.
- .10 U-bolts: carbon steel to MSS SP69 with 2 nuts at each end to ASTM A563.
  - .1 Finishes for steel pipework: galvanized.

- .2 Finishes for copper, glass, brass or aluminum pipework: galvanized , with formed portion plastic coated.
- .11 Pipe rollers: cast iron roll and roll stand with carbon steel rod to MSS SP69.

## **2.4 INSULATION PROTECTION SHIELDS**

- .1 Insulated cold piping:
  - .1 64 kg/m<sup>3</sup> density insulation plus insulation protection shield to: MSS SP69, galvanized sheet carbon steel. Length designed for maximum 3 m span.
- .2 Insulated hot piping:
  - .1 Curved plate 300 mm long, with edges turned up, welded-in centre plate for pipe sizes NPS 12 and over, carbon steel to comply with MSS SP69.

## **2.5 CONSTANT SUPPORT SPRING HANGERS**

- .1 Springs: alloy steel to ASTM A125, shot peened, magnetic particle inspected, with +/-5% spring rate tolerance, tested for free height, spring rate, loaded height and provided with Certified Mill Test Report (CMTR).
- .2 Load adjustability: 10% minimum adjustability each side of calibrated load. Adjustment without special tools. Adjustments not to affect travel capabilities.
- .3 Provide upper and lower factory set travel stops.
- .4 Provide load adjustment scale for field adjustments.
- .5 Total travel to be actual travel + 20%. Difference between total travel and actual travel 25 mm minimum.
- .6 Individually calibrated scales on each side of support calibrated prior to shipment, complete with calibration record.

## **2.6 HOUSE-KEEPING PADS**

- .1 Provide 100 mm high concrete housekeeping pads for base-mounted equipment; size pads 50 mm larger than equipment; chamfer pad edges.
- .2 Concrete: to Section 03 30 00 - Cast-in-Place Concrete.

## **2.7 OTHER EQUIPMENT SUPPORTS**

- .1 Fabricate equipment supports from structural grade steel.

## **Part 3 Execution**

### **3.1 MANUFACTURER'S INSTRUCTIONS**

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

### 3.2 INSTALLATION

- .1 Install in accordance with:
  - .1 Manufacturer's instructions and recommendations.
- .2 Use approved constant support type hangers where:
  - .1 Vertical movement of pipework is 13 mm or more,
  - .2 Transfer of load to adjacent hangers or connected equipment is not permitted.
- .3 Use variable support spring hangers where:
  - .1 Transfer of load to adjacent piping or to connected equipment is not critical.
  - .2 Variation in supporting effect does not exceed 25 % of total load.

### 3.3 HANGER SPACING

- .1 Plumbing piping: to Canadian Plumbing Code, Provincial Code and authority having jurisdiction.
- .2 Gas and fuel oil piping: up to NPS 1/2: every 1.8 m.
- .3 Copper piping: up to NPS 1/2: every 1.5 m.
- .4 Flexible joint roll groove pipe: in accordance with table below for steel, but not less than one hanger at joints. Table listings for straight runs without concentrated loads and where full linear movement is not required.
- .5 Within 300 mm of each elbow.

Maximum Pipe Size : NPS	Maximum Spacing Steel	Maximum Spacing Copper
up to 1-1/4	2.4 m	1.8 m
1-1/2	3.0 m	2.4 m
2	3.0 m	2.4 m
2-1/2	3.7 m	3.0 m
3	3.7 m	3.0 m
3-1/2	3.7 m	3.3 m
4	3.7 m	3.6 m
5	4.3 m	
6	4.3 m	
8	4.3 m	
10	4.9 m	
12	4.9 m	

- .6 Pipework greater than NPS 12: to MSS SP69.

### 3.4 HANGER INSTALLATION

- .1 Install hanger so that rod is vertical under operating conditions.
- .2 Adjust hangers to equalize load.
- .3 Support from structural members. Where structural bearing does not exist or inserts are not in suitable locations, provide supplementary structural steel members.

### **3.5 HORIZONTAL MOVEMENT**

- .1 Angularity of rod hanger resulting from horizontal movement of pipework from cold to hot position not to exceed 4 degrees from vertical.
- .2 Where horizontal pipe movement is less than 13 mm, offset pipe hanger and support so that rod hanger is vertical in the hot position.

### **3.6 FINAL ADJUSTMENT**

- .1 Adjust hangers and supports:
  - .1 Ensure that rod is vertical under operating conditions.
  - .2 Equalize loads.
- .2 Adjustable clevis:
  - .1 Tighten hanger load nut securely to ensure proper hanger performance.
  - .2 Tighten upper nut after adjustment.
- .3 C-clamps:
  - .1 Follow manufacturer's recommended written instructions and torque values when tightening C-clamps to bottom flange of beam.
- .4 Beam clamps:
  - .1 Hammer jaw firmly against underside of beam.

### **3.7 FIELD QUALITY CONTROL**

- .1 Site Tests: conduct following tests in accordance with Section 01 45 00 - Quality Control and submit report as described in PART 1 - ACTION AND INFORMATIONAL SUBMITTALS.
- .2 Manufacturer's Field Services:
  - .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Manufacturer's Field Reports as described in PART 1 - ACTION AND INFORMATIONAL SUBMITTALS.
  - .2 Provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.
  - .3 Schedule site visits, to review Work, as directed in PART 1 - QUALITY ASSURANCE.
- .3 Verification requirements in accordance with Section 01 47 17 - Sustainable Requirements: Contractor's Verification, include:
  - .1 Materials and resources.
  - .2 Storage and collection of recyclables.
  - .3 Construction waste management.
  - .4 Resource reuse.
  - .5 Recycled content.

- .6 Local/regional materials.
- .7 Certified wood.
- .8 Low-emitting materials.

### **3.8 CLEANING**

- .1 Clean in accordance with Section 01 74 11 - Cleaning.
  - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.
- .2 Waste Management: separate waste materials for recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

**END OF SECTION**

**Part 1 General**

**1.1 REFERENCES**

- .1 Canadian Gas Association (CGA)
  - .1 CSA/CGA B149.1-05, Natural Gas and Propane Installation Code.
- .2 Canadian General Standards Board (CGSB)
  - .1 CAN/CGSB-24.3-92, Identification of Piping Systems.

**1.2 ACTION AND INFORMATIONAL SUBMITTALS**

- .1 Product Data:
- .2 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .3 Product data to include paint colour chips, other products specified in this section.
- .4 Samples:
  - .1 Submit samples in accordance with Section 01 33 00 - Submittal Procedures.
  - .2 Samples to include nameplates, labels, tags, lists of proposed legends.

**1.3 QUALITY ASSURANCE**

- .1 Quality assurance submittals: submit following in accordance with Section 01 33 00 - Submittal Procedures.

**1.4 DELIVERY, STORAGE, AND HANDLING**

- .1 Packing, shipping, handling and unloading:
  - .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
  - .2 Deliver, store and handle materials in accordance with manufacturer's written instructions.
- .2 Waste Management and Disposal:
  - .1 Construction/Demolition Waste Management and Disposal: separate waste materials for recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.
  - .2 Dispose of unused paint material at official hazardous material collections site approved by Departmental Representative.
  - .3 Do not dispose of unused paint and coating material into sewer system, into streams, lakes, onto ground or in locations where it will pose health or environmental hazard.

**Part 2 Products**

**2.1 MANUFACTURER'S EQUIPMENT NAMEPLATES**

- .1 Metal or plastic laminate nameplate mechanically fastened to each piece of equipment by manufacturer.



- .2 Lettering and numbers raised or recessed.
- .3 Information to include, as appropriate:
  - .1 Equipment: manufacturer's name, model, size, serial number, capacity.
  - .2 Motor: voltage, Hz, phase, power factor, duty, frame size.

## 2.2 SYSTEM NAMEPLATES

- .1 Colours:
  - .1 Hazardous: red letters, white background.
  - .2 Elsewhere: black letters, white background (except where required otherwise by applicable codes).
- .2 Construction:
  - .1 3 mm thick laminated plastic white anodized aluminum, matte finish, with square corners, letters accurately aligned and machine engraved into core.
- .3 Sizes:
  - .1 Conform to following table:

Size # mm	Sizes (mm)	No. of Lines	Height of Letters (mm)
1	10 x 50	1	3
2	13 x 75	1	5
3	13 x 75	2	3
4	20 x 100	1	8
5	20 x 100	2	5
6	20 x 200	1	8
7	25 x 125	1	12
8	25 x 125	2	8
9	35 x 200	1	20
  - .2 Use maximum of 25 letters/numbers per line.
- .4 Locations:
  - .1 Terminal cabinets, control panels: use size # 5.
  - .2 Equipment in Mechanical Rooms: use size # 9.
- .5 Identification for PWGSC Preventive Maintenance Support System (PMSS):
  - .1 Use arrangement of Main identifier, Source identifier, Destination identifier.
  - .2 Equipment in Mechanical Room:
    - .1 Main identifier: size #9.
    - .2 Source and Destination identifiers: size #6.
    - .3 Terminal cabinets, control panels: size #5.
  - .3 Equipment elsewhere: sizes as appropriate.

## 2.3 EXISTING IDENTIFICATION SYSTEMS

- .1 Apply existing identification system to new work.

- .2 Where existing identification system does not cover for new work, use identification system specified this section.
- .3 Before starting work, obtain written approval of identification system from Departmental Representative.

## 2.4 PIPING SYSTEMS GOVERNED BY CODES

- .1 Identification:
  - .1 Natural gas: to CSA/CGA B149.1 and authority having jurisdiction.

## 2.5 IDENTIFICATION OF PIPING SYSTEMS

- .1 Identify contents by background colour marking, pictogram (as necessary), legend; direction of flow by arrows. To CAN/CGSB 24.3 except where specified otherwise.
- .2 Legend:
  - .1 Block capitals to sizes and colours listed in CAN/CGSB 24.3.
- .3 Arrows showing direction of flow:
  - .1 Outside diameter of pipe or insulation less than 75 mm: 100 mm long x 50 mm high.
  - .2 Outside diameter of pipe or insulation 75 mm and greater: 150 mm long x 50 mm high.
  - .3 Use double-headed arrows where flow is reversible.
- .4 Colours and Legends:
  - .1 Where not listed, obtain direction from Departmental Representative.
  - .2 Colours for legends, arrows: to following table:

Background colour:	Legend, arrows:
Yellow	BLACK
Green	WHITE
Red	WHITE

- .3 Background colour marking and legends for piping systems:

Contents	Background colour marking	Legend
** Add design temperature		
++ Add design temperature and pressure		
Hot water heating supply	Yellow	HEATING SUPPLY
Hot water heating return	Yellow	HEATING RETURN
Safety valve vent	Yellow	STEAM VENT
Plumbing vent	Green	SAN. VENT
Refrigeration liquid	Yellow	REF. LIQUID
Natural gas	to Codes	
Gas regulator vents	to Codes	

## **2.6 IDENTIFICATION DUCTWORK SYSTEMS**

- .1 50 mm high stencilled letters and directional arrows 150 mm long x 50 mm high.
- .2 Colours: back, or co-ordinated with base colour to ensure strong contrast.

## **2.7 VALVES, CONTROLLERS**

- .1 Brass tags with 12 mm stamped identification data filled with black paint.
- .2 Include flow diagrams for each system, of approved size, showing charts and schedules with identification of each tagged item, valve type, service, function, normal position, location of tagged item.

## **2.8 CONTROLS COMPONENTS IDENTIFICATION**

- .1 Identify all systems, equipment, components, controls, sensors with system nameplates specified in this section.
- .2 Inscriptions to include function and (where appropriate) fail-safe position.

## **2.9 LANGUAGE**

- .1 Identification in English.

## **Part 3 Execution**

### **3.1 MANUFACTURER'S INSTRUCTIONS**

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

### **3.2 INSTALLATION**

- .1 Perform work in accordance with CAN/CGSB-24.3 except as specified otherwise.
- .2 Identify systems, equipment to conform to PWGSC PMSS.

### **3.3 NAMEPLATES**

- .1 Locations:
  - .1 In conspicuous location to facilitate easy reading and identification from operating floor.
- .2 Standoffs:
  - .1 Provide for nameplates on hot and/or insulated surfaces.
- .3 Protection:
  - .1 Do not paint, insulate or cover.

### **3.4 LOCATION OF IDENTIFICATION ON PIPING AND DUCTWORK SYSTEMS**

- .1 On long straight runs in open areas in boiler rooms, equipment rooms, galleries, tunnels: at not more than 17 m intervals and more frequently if required to ensure that at least one is visible from any one viewpoint in operating areas and walking aisles.
- .2 Adjacent to each change in direction.
- .3 At least once in each small room through which piping or ductwork passes.
- .4 On both sides of visual obstruction or where run is difficult to follow.
- .5 On both sides of separations such as walls, floors, partitions.
- .6 Where system is installed in pipe chases, ceiling spaces, galleries, confined spaces, at entry and exit points, and at access openings.
- .7 At beginning and end points of each run and at each piece of equipment in run.
- .8 At point immediately upstream of major manually operated or automatically controlled valves, and dampers. Where this is not possible, place identification as close as possible, preferably on upstream side.
- .9 Identification easily and accurately readable from usual operating areas and from access points.
  - .1 Position of identification approximately at right angles to most convenient line of sight, considering operating positions, lighting conditions, risk of physical damage or injury and reduced visibility over time due to dust and dirt.

### **3.5 VALVES, CONTROLLERS**

- .1 Valves and operating controllers, except at plumbing fixtures, radiation, or where in plain sight of equipment they serve: Secure tags with non-ferrous chains or closed "S" hooks.
- .2 Install one copy of flow diagrams, valve schedules mounted in frame behind non-glare glass where directed by Departmental Representative. Provide one copy (reduced in size if required) in each operating and maintenance manual.
- .3 Number valves in each system consecutively.

### **3.6 CLEANING**

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

**END OF SECTION**

**Part 1 General**

**1.1 QUALIFICATIONS OF TAB PERSONNEL**

- .1 Provide documentation confirming qualifications, successful experience.
- .2 TAB: performed in accordance with the requirements of standard under which TAB Firm's qualifications are approved:
  - .1 Associated Air Balance Council, (AABC) National Standards for Total System Balance, MN-1-2002.
  - .2 National Environmental Balancing Bureau (NEBB) TABES, Procedural Standards for Testing, Adjusting, Balancing of Environmental Systems-1998.
  - .3 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA), HVAC TAB HVAC Systems - Testing, Adjusting and Balancing-2002.
- .3 Recommendations and suggested practices contained in the TAB Standard: mandatory.
- .4 Use TAB Standard provisions, including checklists, and report forms to satisfy Contract requirements.
- .5 Use TAB Standard for TAB, including qualifications for TAB Firm and Specialist and calibration of TAB instruments.
- .6 Where instrument manufacturer calibration recommendations are more stringent than those listed in TAB Standard, use manufacturer's recommendations.
- .7 TAB Standard quality assurance provisions such as performance guarantees form part of this contract.
  - .1 For systems or system components not covered in TAB Standard, use TAB procedures developed by TAB Specialist.
  - .2 Where new procedures, and requirements, are applicable to Contract requirements have been published or adopted by body responsible for TAB Standard used (AABC, NEBB, or TABB), requirements and recommendations contained in these procedures and requirements are mandatory.

**1.2 PURPOSE OF TAB**

- .1 Test to verify proper and safe operation, determine actual point of performance, evaluate qualitative and quantitative performance of equipment, systems and controls at design, average and low loads using actual or simulated loads
- .2 Adjust and regulate equipment and systems to meet specified performance requirements and to achieve specified interaction with other related systems under normal and emergency loads and operating conditions.
- .3 Balance systems and equipment to regulate flow rates to match load requirements over full operating ranges.

**1.3 EXCEPTIONS**

- .1 TAB of systems and equipment regulated by codes, standards to satisfaction of authority having jurisdiction.

#### **1.4 CO-ORDINATION**

- .1 Schedule time required for TAB (including repairs, re-testing) into project construction and completion schedule to ensure completion before acceptance of project.
- .2 Do TAB of each system independently and subsequently, where interlocked with other systems, in unison with those systems.

#### **1.5 START-UP**

- .1 Follow start-up procedures as recommended by equipment manufacturer unless specified otherwise.
- .2 Follow special start-up procedures specified elsewhere in Division 23.

#### **1.6 OPERATION OF SYSTEMS DURING TAB**

- .1 Operate systems for length of time required for TAB and as required by Departmental Representative for verification of TAB reports.

#### **1.7 START OF TAB**

- .1 Notify Departmental Representative 7 days prior to start of TAB.
- .2 Start TAB when building is essentially completed, including:
- .3 Installation of ceilings, doors, windows, other construction affecting TAB.
- .4 Application of weatherstripping, sealing, and caulking.
- .5 Pressure, leakage, other tests specified elsewhere Division 23.
- .6 Provisions for TAB installed and operational.
- .7 Start-up, verification for proper, normal and safe operation of mechanical and associated electrical and control systems affecting TAB including but not limited to:
  - .1 Proper thermal overload protection in place for electrical equipment.
  - .2 Air systems:
    - .1 Filters in place, clean.
    - .2 Duct systems clean.
    - .3 Ducts, air shafts, ceiling plenums are airtight to within specified tolerances.
    - .4 Correct fan rotation.
    - .5 Fire, smoke, volume control dampers installed and open.
    - .6 Coil fins combed, clean.
    - .7 Access doors, installed, closed.
    - .8 Outlets installed, volume control dampers open.

#### **1.8 ACCURACY TOLERANCES**

- .1 Measured values accurate to within plus or minus 2 % of actual values.

## **1.9 INSTRUMENTS**

- .1 Calibrate in accordance with requirements of most stringent of referenced standard for either applicable system or HVAC system.
- .2 Calibrate within 3 months of TAB. Provide certificate of calibration to Departmental Representative.

## **1.10 ACTION AND INFORMATIONAL SUBMITTALS**

- .1 Submit, prior to commencement of TAB:
- .2 Proposed methodology and procedures for performing TAB if different from referenced standard.

## **1.11 PRELIMINARY TAB REPORT**

- .1 Submit for checking and approval of Departmental Representative, prior to submission of formal TAB report, sample of rough TAB sheets. Include:
  - .1 Details of instruments used.
  - .2 Details of TAB procedures employed.
  - .3 Calculations procedures.
  - .4 Summaries.

## **1.12 TAB REPORT**

- .1 Format in accordance with referenced standard.
- .2 TAB report to show results in SI units and to include:
  - .1 Project record drawings.
  - .2 System schematics.
- .3 Submit 6 copies of TAB Report to Departmental Representative for verification and approval, in English in D-ring binders, complete with index tabs.

## **1.13 VERIFICATION**

- .1 Reported results subject to verification by Departmental Representative.
- .2 Provide personnel and instrumentation to verify up to 30 % of reported results.
- .3 Pay costs to repeat TAB as required to satisfaction of Departmental Representative.

## **1.14 SETTINGS**

- .1 After TAB is completed to satisfaction of Departmental Representative, replace drive guards, close access doors, lock devices in set positions, ensure sensors are at required settings.
- .2 Permanently mark settings to allow restoration at any time during life of facility. Do not eradicate or cover markings.

**1.15 COMPLETION OF TAB**

- .1 TAB considered complete when final TAB Report received and approved by Departmental Representative.

**1.16 AIR SYSTEMS**

- .1 Standard: TAB to most stringent of TAB standards of AABC, NEBB, SMACNA and ASHRAE.
- .2 Qualifications: personnel performing TAB qualified to standards of AABC and NEBB.
- .3 Measurements: to include as appropriate for systems, equipment, components, controls: air velocity, static pressure, flow rate, pressure drop (or loss), temperatures (dry bulb, wet bulb, dewpoint), duct cross-sectional area, RPM, electrical power, voltage, noise, vibration.
- .4 Locations of equipment measurements: to include as appropriate:
  - .1 Inlet and outlet of dampers, filter, coil, humidifier, fan, other equipment causing changes in conditions.
  - .2 At controllers, controlled device.
- .5 Locations of systems measurements to include as appropriate: main ducts, main branch, sub-branch, run-out (or grille, register or diffuser).

**1.17 OTHER TAB REQUIREMENTS**

- .1 General requirements applicable to work specified this paragraph:
  - .1 Qualifications of TAB personnel: as for air systems specified this section.
  - .2 Quality assurance: as for air systems specified this section.
- .2 Building pressure conditions:
  - .1 Adjust HVAC systems, equipment, controls to ensure specified pressure conditions at all times during winter summer design conditions.
- .3 Zone pressure differences:
  - .1 Adjust HVAC systems, equipment, controls to establish specified air pressure differentials, with systems in every possible combinations of normal operating modes.

**Part 2 Products**

**2.1 NOT USED**

- .1 Not used.



**Part 3            Execution**

**3.1                NOT USED**

.1            Not used.

**END OF SECTION**

## **Part 1            General**

### **1.1                REFERENCES**

- .1 American Society of Heating, Refrigeration and Air Conditioning Engineers (ASHRAE)
  - .1 ASHRAE Standard 90.1-01, Energy Standard for Buildings Except Low-Rise Residential Buildings (IESNA co-sponsored; ANSI approved; Continuous Maintenance Standard).
- .2 American Society for Testing and Materials International (ASTM)
  - .1 ASTM B209M-04, Standard Specification for Aluminum and Aluminum Alloy Sheet and Plate Metric.
  - .2 ASTM C335-04, Standard Test Method for Steady State Heat Transfer Properties of Horizontal Pipe Insulation.
  - .3 ASTM C411-04, Standard Test Method for Hot-Surface Performance of High-Temperature Thermal Insulation.
  - .4 ASTM C449/C449M-00, Standard Specification for Mineral Fiber-Hydraulic-Setting Thermal Insulating and Finishing Cement.
  - .5 ASTM C533-2004, Calcium Silicate Block and Pipe Thermal Insulation.
  - .6 ASTM C547-2003, Mineral Fiber Pipe Insulation.
  - .7 ASTM C795-03, Standard Specification for Thermal Insulation for Use in Contact with Austenitic Stainless Steel.
  - .8 ASTM C921-03a, Standard Practice for Determining the Properties of Jacketing Materials for Thermal Insulation.
- .3 Canadian General Standards Board (CGSB)
  - .1 CGSB 51-GP-52Ma-89, Vapour Barrier, Jacket and Facing Material for Pipe, Duct and Equipment Thermal Insulation.
  - .2 CAN/CGSB-51.53-95, Poly (Vinyl Chloride) Jacketting Sheet, for Insulated Pipes, Vessels and Round Ducts
- .4 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
  - .1 Material Safety Data Sheets (MSDS).
- .5 Manufacturer's Trade Associations
  - .1 Thermal Insulation Association of Canada (TIAC): National Insulation Standards (Revised 2004).
- .6 Underwriters' Laboratories of Canada (ULC)
  - .1 CAN/ULC-S102-03, Surface Burning Characteristics of Building Materials and Assemblies.
  - .2 CAN/ULC-S701-01, Thermal Insulation, Polystyrene, Boards and Pipe Covering.
  - .3 CAN/ULC-S702-1997, Thermal Insulation, Mineral Fibre, for Buildings
  - .4 CAN/ULC-S702.2-03, Thermal Insulation, Mineral Fibre, for Buildings, Part 2: Application Guidelines.

## **1.2 DEFINITIONS**

- .1 For purposes of this section:
  - .1 "CONCEALED" - insulated mechanical services in suspended ceilings and non-accessible chases and furred-in spaces.
  - .2 "EXPOSED" - will mean "not concealed" as specified.
- .2 TIAC ss:
  - .1 CRF: Code Rectangular Finish.
  - .2 CPF: Code Piping Finish.

## **1.3 ACTION AND INFORMATIONAL SUBMITTALS**

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
  - .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00 - Submittal Procedures. Include product characteristics, performance criteria, and limitations.
    - .1 Submit two copies of Workplace Hazardous Materials Information System (WHMIS) Material Safety Data Sheets (MSDS) in accordance with Section 01 33 00 - Submittal Procedures.
- .3 Shop Drawings:
  - .1 Submit shop drawings in accordance with Section 01 33 00 - Submittal Procedures.
    - .1 Shop drawings: submit drawings stamped and signed.

## **1.4 QUALITY ASSURANCE**

- .1 Qualifications:
- .2 Installer: specialist in performing work of this Section, and have at least 3 years successful experience in this size and type of project, qualified to standards member of TIAC.
- .3 Health and Safety:
  - .1 Do construction occupational health and safety in accordance with Section 01 35 29.06 - Health and Safety Requirements.

## **1.5 DELIVERY, STORAGE AND HANDLING**

- .1 Packing, shipping, handling and unloading:
  - .1 Deliver, store and handle in accordance with manufacturer's written instructions and Section 01 61 00 - Common Product Requirements.
  - .2 Deliver, store and handle materials in accordance with manufacturer's written instructions.
  - .3 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.

- .2 Storage and Protection:
  - .1 Protect from weather, construction traffic.
  - .2 Protect against damage.
  - .3 Store at temperatures and conditions required by manufacturer.
- .3 Waste Management and Disposal:
  - .1 Construction/Demolition Waste Management and Disposal: separate waste materials for recycling and remove from site.
  - .2 Place excess or unused insulation and insulation accessory materials in designated containers.
  - .3 Divert unused metal materials from landfill to metal recycling facility.
  - .4 Dispose of unused adhesive material at official hazardous material collections site.

## **Part 2 Products**

### **2.1 FIRE AND SMOKE RATING**

- .1 In accordance with CAN/ULC-S102.
  - .1 Maximum flame spread rating: 25.
  - .2 Maximum smoke developed rating: 50.

### **2.2 INSULATION**

- .1 Mineral fibre specified includes glass fibre, rock wool, slag wool.
- .2 Thermal conductivity ("k" factor) not to exceed specified values at 24 degrees C mean temperature when tested in accordance with ASTM C335.
- .3 TIAC Code A-1: rigid moulded mineral fibre without factory applied vapour retarder jacket.
  - .1 Mineral fibre: to CAN/ULC-S702 and ASTM C547.
  - .2 Maximum "k" factor: to CAN/ULC-S702.
- .4 TIAC Code A-3: rigid moulded mineral fibre with factory applied vapour retarder jacket.
  - .1 Mineral fibre: to CAN/ULC-S702 and ASTM C547.
  - .2 Jacket: to CGSB 51-GP-52Ma.
  - .3 Maximum "k" factor: to CAN/ULC-S702 and ASTM C547.
- .5 TIAC Code C-2: mineral fibre blanket faced with factory applied vapour retarder jacket (as scheduled in PART 3 of this section).
  - .1 Mineral fibre: to CAN/ULC-S702 and ASTM C547.
  - .2 Jacket: to CGSB 51-GP-52Ma.
  - .3 Maximum "k" factor: to CAN/ULC-S702 and ASTM C547.
- .6 TIAC Code A-6: flexible unicellular tubular elastomer.
  - .1 Insulation: with vapour retarder jacket.

- .2 Jacket: to CGSB 51-GP-52Ma.
- .3 Maximum "k" factor: CAN/ULC-S702 and ASTM C547.
- .4 Certified by manufacturer: free of potential stress corrosion cracking corrodants.

### **2.3 INSULATION SECUREMENT**

- .1 Tape: self-adhesive, aluminum, reinforced, 50 mm wide minimum.
- .2 Contact adhesive: quick setting.
- .3 Canvas adhesive: washable.
- .4 Tie wire: 1.5 mm diameter stainless steel.
- .5 Bands: stainless steel, 19 mm wide, 0.5 mm thick.

### **2.4 VAPOUR RETARDER LAP ADHESIVE**

- .1 Water based, fire retardant type, compatible with insulation.

### **2.5 INDOOR VAPOUR RETARDER FINISH**

- .1 Vinyl emulsion type acrylic, compatible with insulation.

### **2.6 OUTDOOR VAPOUR RETARDER FINISH**

- .1 Vinyl emulsion type acrylic, compatible with insulation.
- .2 Reinforcing fabric: fibrous glass, untreated 305 g/m<sup>2</sup>.

### **2.7 JACKETS**

- .1 Polyvinyl Chloride (PVC):
  - .1 One-piece moulded type and sheet to CAN/CGSB-51.53 with pre-formed shapes as required.
  - .2 Colours: to match adjacent finish paint.
  - .3 Minimum service temperatures: -20 degrees C.
  - .4 Maximum service temperature: 65 degrees C.
  - .5 Moisture vapour transmission: 0.02 perm.
  - .6 Thickness: 10.59 mm.
  - .7 Fastenings:
    - .1 Use solvent weld adhesive compatible with insulation to seal laps and joints.
    - .2 Tacks.
    - .3 Pressure sensitive vinyl tape of matching colour.
  - .8 Special requirements:
    - .1 Outdoor: UV rated material at least 0.5 mm thick.

### **2.8 WEATHERPROOF CAULKING FOR JACKETS INSTALLED OUTDOORS**

- .1 Caulking to: Section 07 92 00 - Joint Sealants.

**Part 3            Execution**

**3.1                MANUFACTURER'S INSTRUCTIONS**

- .1        Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

**3.2                PRE-INSTALLATION REQUIREMENT**

- .1        Pressure testing of piping systems and adjacent equipment to be complete, witnessed and certified.
- .2        Surfaces clean, dry, free from foreign material.

**3.3                INSTALLATION**

- .1        Install in accordance with TIAC National Standards.
- .2        Apply materials in accordance with manufacturer's instructions and this specification.
- .3        Use two layers with staggered joints when required nominal wall thickness exceeds 75 mm.
- .4        Maintain uninterrupted continuity and integrity of vapour retarder jacket and finishes.
  - .1            Install hangers, supports outside vapour retarder jacket.
- .5        Supports, Hangers:
  - .1            Apply high compressive strength insulation, suitable for service, at oversized saddles and shoes where insulation saddles have not been provided.

**3.4                REMOVABLE, PRE-FABRICATED, INSULATION AND ENCLOSURES**

- .1        Application: at expansion joints, valves, primary flow measuring elements flanges and unions at equipment.
- .2        Design: to permit movement of expansion joint to permit periodic removal and replacement without damage to adjacent insulation.
- .3        Insulation:
  - .1            Insulation, fastenings and finishes: same as system.
  - .2            Jacket: aluminum PVC .

**3.5                INSTALLATION OF ELASTOMERIC INSULATION**

- .1        Insulation to remain dry. Overlaps to manufacturer's instructions. Ensure tight joints.
- .2        Provide vapour retarder as recommended by manufacturer.

**3.6                PIPING INSULATION SCHEDULES**

- .1        Includes valves, valve bonnets, strainers, flanges and fittings unless otherwise specified.
- .2        TIAC Code: A-1.
  - .1            Securements: Tape bands at 300 mm on centre.

- .2 Seals: lap seal adhesive, lagging adhesive.
- .3 Installation: TIAC Code 1501-H.
- .3 TIAC Code: A-3.
  - .1 Securements: Tape bands at 300 mm on centre.
  - .2 Seals: VR lap seal adhesive, VR lagging adhesive.
  - .3 Installation: TIAC Code: 1501-C.
- .4 TIAC Code: C-2 with vapour retarder jacket.
  - .1 Insulation securements: tape.
  - .2 Seals: lap seal adhesive, lagging adhesive.
  - .3 Installation: TIAC Code: 1501-C.
- .5 TIAC Code: A-2.
  - .1 Insulation securements: tape
  - .2 Seals: lap seal adhesive, lagging adhesive.
  - .3 Installation: TIAC Code: 1501-H.
- .6 Thickness of insulation as listed in following table.
  - .1 Run-outs to individual units and equipment not exceeding 4000 mm long.
  - .2 Do not insulate exposed runouts to plumbing fixtures, chrome plated piping, valves, fittings.

Application	Temp degrees C	TIAC code	Pipe sizes (NPS) and insulation thickness (mm)										
Run out	to 1	1 1/4 to 2	2 1/2 to 4	5 to 6	8	up to 175	A-1	38	50	65	75	90	90
Refrigeranthot gas liquid suction	4 - 13	A-6	25	25	25	25	25	25					
Cooling Coil cond. drain	C-2	25	25	25	25	25	25						

- .7 Finishes:
  - .1 Exposed indoors: aluminum PVC jacket.
  - .2 Concealed, indoors: canvas on valves, fittings. No further finish.
  - .3 Use vapour retarder jacket on TIAC code A-3 insulation compatible with insulation.
  - .4 Outdoors: water-proof aluminum jacket.
  - .5 Finish attachments: bands, at 150 mm on centre. Seals: closed.
  - .6 Installation: to appropriate TIAC code CRF/1 through CPF/5.

**3.7 CLEANING**

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

**END OF SECTION**