

PART 1 - GENERAL

- |  |              |   |
|--|--------------|---|
| <u>1.1 SECTION<br/>INCLUDES</u>                                | .1<br><br>.2 | Barriers.<br><br>Traffic Controls.  |
| <u>1.2 INSTALLATION<br/>AND REMOVAL</u>                        | .1<br><br>.2 | Provide temporary controls in order to<br>execute work expeditiously.<br><br>Remove from site all such work after use.  |
| <u>1.3 HOARDING</u>  | .1           | Erect temporary site enclosure using new<br>1.2 m high snow fence wired to rolled steel<br>"T" bar fence posts spaced at 2.4 m centres.<br>Provide one lockable truck gate. Maintain<br>fence in good repair. |
| <u>1.4 GUARD RAILS<br/>AND BARRICADES</u>                      | .1           | Provide as required by governing authorities<br>and to approval of Departmental<br>Representative.  |
| <u>1.5 ACCESS TO SITE</u>                                      | .1           | Provide and maintain access to adjacent<br>harbour facilities.  |
| <u>1.6 PUBLIC<br/>TRAFFIC FLOW</u>                             | .1           | Provide and maintain competent signal flag<br>operators, traffic signals, barricades and<br>flares, lights, or lanterns as required to<br>perform work and protect the public.                                |
| <u>1.7 FIRE ROUTES</u>   | .1           | Maintain access to property including<br>overhead clearances for use by emergency<br>response vehicles.   |
| <u>1.8 PROTECTION FOR<br/>OFF-SITE AND PUBLIC<br/>PROPERTY</u> | .1<br><br>.2 | Protect surrounding private and public<br>property from damage during performance of<br>work.<br><br>Be responsible for damage incurred.  |