



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Bid Receiving Public Works and Government
Services Canada/Réception des soumissions Travaux
publics et Services gouvernementaux Canada
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British Columbia
V6Z 0B9
Bid Fax: (604) 775-9381

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise
indicated, all other terms and conditions of the Solicitation
remain the same.

Ce document est par la présente révisé; sauf indication contraire,
les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada - Pacific
Region
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British C
V6Z 0B9

Title - Sujet Washroom Buildings	
Solicitation No. - N° de l'invitation EZ899-172848/A	Amendment No. - N° modif. 013
Client Reference No. - N° de référence du client	Date 2017-07-26
GETS Reference No. - N° de référence de SEAG PW-\$PWY-015-8080	
File No. - N° de dossier PWY-7-40015 (015)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2017-07-27	Time Zone Fuseau horaire Pacific Daylight Saving Time PDT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Chan (PWY), Scarlett	Buyer Id - Id de l'acheteur pwy015
Telephone No. - N° de téléphone (604) 369-7853 ()	FAX No. - N° de FAX (604) 775-6633
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: Parks Canada (PCA) - Pacific Rim National Park - Tofino, BC	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation No. - N° de l'invitation
EZ899-172848/A

Amd. No. - N° de la modif.
013

Buyer ID - Id de l'acheteur
pwy015

Client Ref. No. - N° de réf. du client

File No. - N° du dossier
PWY-7-40015

CCC No./N° CCC - FMS No/ N° VME

Solicitation Amendment 013

This solicitation amendment is raised to include Addendum #8. All other terms and conditions remain unchanged.

ADDENDUM #8

Date: July 26, 2017

PACIFIC RIM NATIONAL PARK
WASHROOM BUILDINGS
TOFINO, B.C.
Project No: R.078666.001

The following revisions supersede the information contained in the original drawings and specification issued for the above named project, and shall become part thereof. No consideration will be allowed for extras due to the contractor or any subcontractor not being familiar with this Addendum.

1.0 MECHANICAL SPECIFICATIONS & DRAWINGS

Delete :

2.0 Mechanical Specification and 3.0 Mechanical Drawings in addendum 7 dated July 24, 2017.

3.0 QUESTIONS AND ANSWERS

Q1. Do you have quantities for these plazas? Can you break the quantities down to each plaza? Do you know the spacing of the sawcuts? Do you know what joint filler they want? Do you know if it's reinforced? When is this work to be completed? What type of surface sealant do they specify for the plaza? What type of stamp?

A1. Approximate quantities of stamp concrete :

Incinerator Rock : 690sm
Wickaninnish Beach : 320sm
Long Beach North : 450sm
Long Beach South : 600sm

Note that these areas are for reference only. The extent shown on drawings issued in addendum 3 will take precedence over these quantities.

Control joint to be saw cut joint without any joint filler. Joints to be at 6m on centre in both directions. Exact location is to be determined during shop drawings submission. Joint filler will only be required between the exterior concrete slab and the new building.

Slab to be 100mm THICK EXTERIOR S.O.G. R/W 15M@300 E.W. ON 300mm THK.COMPACTED GRANULAR FILL AS PER SOIL REPORT for all plaza. Detail as per TYPICAL SLAB DETAIL FOR INTERIOR AND EXTERIOR SLAB DETAIL on structural drawings S201, S301, S401 and S501.

Stamp concrete to be Ashlar cut slate pattern or approved equal, grey color, sealed with acrylic based stain and water resistance, UV resistant, non-yellowing, natural finish concrete sealer (no sheen).

Contractor to provide shop drawings showing stamp pattern, location of control joints, and manufacturer's product data for review prior to installation of a mock up. A 3m x 3m mock-up is required to be installed at one washroom location only to be reviewed by Departmental Representative.

END OF ADDENDUM #8

CHERNOFF THOMPSON ARCHITECTS

07/26/2017
Addendum #8

PROJECT NO.: R 078666.001
CTA Project #35030