

Lighthouse Restoration Phase 2 Machias Seal Island R.080316.001	Environmental Procedures	SECTION 01 35 43  PAGE 1 July 2017
--	-----------------------------	---

## **PART 1 GENERAL**

### **1.01 RELATED REQUIREMENTS**

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 01 35 29.06 - Health and Safety Requirements.
- .3 Section 01 74 11 - Cleaning.
- .4 Section 01 74 21 - Construction Demolition Waste Management and Disposal

### **1.02 REFERENCES**

- .1 Definitions:
  - .1 Environmental Pollution and Damage: presence of chemical, physical, biological elements or agents which adversely affect human health and welfare; unfavourably alter ecological balances of importance to human life; affect other species of importance to humans; or degrade environment aesthetically, culturally and/or historically.
  - .2 Environmental Protection: prevention/control of pollution and habitat or environment disruption during construction.
- .2 Reference Standards:
  - .1 U.S. Environmental Protection Agency (EPA)/Office of Water
    - .1 EPA 832/R-92-005-92, Storm Water Management for Construction Activities, Chapter 3.
    - .2 EPA General Construction Permit (GCP) 2012.
  - .2 Migratory Birds Convention Act, 1994
  - .3 Fisheries Act
  - .4 Canadian Environmental Protection Act (CEPA).
  - .5 Emergency Preparedness and Response CAN/CSA-Z&31-03
- .3 Limited Hazardous Building Materials Assessment, Machias Island Lighthouse.

### **1.03 ACTION AND INFORMATIONAL SUBMITTALS**

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
  - .1 Submit manufacturer's instructions, printed product

literature and data sheets and include product characteristics, performance criteria, physical size, finish and limitations.

.2 Submit electronic copies of WHMIS MSDS in accordance with Section 01 35 29.06 - Health and Safety Requirements.

.3 Before commencing construction activities or delivery of materials to site, submit Environmental Protection Plan for review by Departmental Representative.

.4 Environmental Protection Plan must include comprehensive overview of known or potential environmental issues to be addressed during construction.

.5 Address topics at level of detail commensurate with environmental issue and required construction tasks.

.6 Include in Environmental Protection Plan:

.1 Name of person responsible for ensuring adherence to Environmental Protection Plan.

.2 Name and qualifications of person responsible for manifesting hazardous waste to be removed from site.

.3 Name and qualifications of person responsible for training site personnel.

.4 Descriptions of environmental protection personnel training program.

.5 Drawings indicating locations of proposed temporary excavations or embankments for haul roads, stream crossings, material storage areas, structures, sanitary facilities, and stockpiles of excess or spoil materials including methods to control runoff and to contain materials on site.

.7 Traffic Control Plans including measures to reduce erosion of temporary roadbeds by construction traffic, especially during wet weather.

.8 Work area plan showing proposed activity in each portion of area and identifying areas of limited use or non-use.

.1 Plan to include measures for marking limits of use areas and methods for protection of features to be preserved within authorized work areas.

.9 Spill Control Plan to include procedures, instructions, and reports to be used in event of unforeseen spill of regulated substance.

.10 Non-Hazardous solid waste disposal plan identifying

methods and locations for solid waste disposal including clearing debris.

.11 Air pollution control plan detailing provisions to assure that dust, debris, materials, and trash, are contained on project site.

.12 Contaminant Prevention Plan identifying potentially hazardous substances to be used on job site; intended actions to prevent introduction of such materials into air, water, or ground; and detailing provisions for compliance with Federal, Provincial, and Municipal laws and regulations for storage and handling of these materials.

.13 Waste Water Management Plan identifying methods and procedures for management and discharge of waste waters which are directly derived from construction activities, such as concrete curing water, clean-up water, dewatering of ground water, disinfection water, hydrostatic test water, and water used in flushing of lines.

.14 Historical, archaeological, cultural resources biological resources and wetlands plan that defines procedures for identifying and protecting historical, archaeological, cultural resources, biological resources and wetlands.

.15 Pesticide treatment plan to be included and updated, as required.

#### **1.04 DRAINAGE**

.1 Develop and submit erosion and Sediment Control Plan (ESC) identifying type and location of erosion and sediment controls provided. Plan to include monitoring and reporting requirements to assure that control measures are in compliance with erosion and sediment control plan, Federal, Provincial, and Municipal laws and regulations, EPA 832/R-92-005, Chapter 3.

.2 Storm Water Pollution Prevention Plan (SWPPP) to be substituted for erosion and sediment control plan.

.3 Provide temporary drainage and pumping required to keep excavations and site free from water.

.4 Ensure pumped water into waterways, sewer or drainage systems is free of suspended materials.

.5 Control disposal or runoff of water containing suspended

materials or other harmful substances in accordance with local authority requirements.

#### **1.05 SITE CLEARING AND PLANT PROTECTION**

.1 Protect trees and plants on site and adjacent properties as indicated.

.2 Protect trees and shrubs adjacent to construction work, storage areas and trucking lanes, and encase with protective wood framework from grade level to height of [2] m minimum.

.3 Protect roots of designated trees to dripline during excavation and site grading to prevent disturbance or damage.

.1 Avoid unnecessary traffic, dumping and storage of materials over root zones.

.4 Minimize stripping of topsoil and vegetation.

#### **1.06 WORK ADJACENT TO WATERWAYS**

.1 Construction equipment to be operated on land only.

.2 Waterways to be kept free of excavated fill, waste material and debris.

.3 Design and construct temporary crossings to minimize erosion to waterways.

.4 Do not skid logs or construction materials across waterways.

.5 Avoid indicated spawning beds when constructing temporary crossings of waterways.

#### **1.07 POLLUTION CONTROL**

.1 Maintain temporary erosion and pollution control features installed under this Contract.

.2 Control emissions from equipment and plant in accordance with local authorities' emission requirements.

.3 Prevent sandblasting and other extraneous materials from contaminating air and waterways beyond application area.

.1 Provide temporary enclosures where directed by Departmental Representative.

.4 Cover or wet down dry materials and rubbish to prevent blowing dust and debris. Provide dust control for temporary roads.

#### **1.08 HISTORICAL/ARCHAEOLOGICAL CONTROL**

.1 Provide historical, archaeological, cultural resources, biological resources, and wetlands plan that defines procedures for identifying and protecting historical, archaeological, cultural resources, biological resources and wetlands known to be on project site: and identifies procedures to be followed if historical archaeological, cultural resources, biological resources and wetlands not previously known to be onsite or in area are discovered during construction.

.2 Plan: include methods to assure protection of known or discovered resources and identify lines of communication between Contractor personnel and Departmental Representative.

#### **1.09 ANIMAL CONTROL**

.1 Machias Seal Island is a migratory bird sanctuary, all work must be done in compliance with Environment Canada requirements and regulations.

.2 The Construction Zone must be separated at all times from the wildlife on the island.

#### **1.10 NOTIFICATION**

.1 Departmental Representative will notify Contractor in writing of observed noncompliance with Federal, Provincial or Municipal environmental laws or regulations, permits, and other elements of Contractor's Environmental Protection plan.

.2 Contractor: after receipt of such notice, inform Departmental Representative of proposed corrective action and take such action for approval by Departmental Representative.

.1 Take action only after receipt of written approval by Departmental Representative.

.3 Departmental Representative will issue stop order of work until satisfactory corrective action has been taken.

.4 No time extensions granted or equitable adjustments allowed to Contractor for such suspensions.

## **PART 2 PRODUCTS**

### **2.01 NOT USED**

.1 Not used.

## **PART 3 EXECUTION**

### **3.01 CLEANING**

.1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.

.1 Leave Work area clean at end of each day.

.2 Ensure public waterways, storm and sanitary sewers remain free of waste and volatile materials disposal.

.3 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.

.4 Waste Management: separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction Demolition Waste Management and Disposal.

.1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

**END OF SECTION**