

Lighthouse Restoration Phase 2 Machias Seal Island R.080316.001	Construction/ Demolition Waste Management & Disposal	SECTION 01 74 21 PAGE 1 July 2017
--	--	---

PART 1 GENERAL

1.01 RELATED REQUIREMENTS

.1 Prior to start of Work conduct meeting with Departmental Representative to review and discuss PWGSC's Waste Management Plan and Goals.

.2 PWGSC's Waste Management Goal 50 percent of total Project Waste to be diverted from landfill sites. Provide Departmental Representative documentation certifying that waste management, recycling, reuse of recyclable and reusable materials have been extensively practiced.

.3 Accomplish maximum control of solid construction waste.

.4 Preserve environment and prevent pollution and environment damage.

1.02 RELATED REQUIREMENTS

.1 Section 01 33 00 - Submittal Procedures

.2 Section 01 73 00 - Execution Requirements

1.03 DEFINITIONS

.1 Class III: non-hazardous waste - construction renovation and demolition waste

.2 Inert Fill: inert waste - exclusively asphalt and concrete.

.3 Materials Source Separation Program (MSSP): consists of series of ongoing activities to separate reusable and recyclable waste material into material categories from other types of waste at point of generation.

.4 Recyclable: ability of product or material to be recovered at end of its life cycle and re-manufactured into new product for reuse.

.5 Recycle: process by which waste and recyclable materials are transformed or collected for purpose of being transferred into new products.

Lighthouse Restoration Phase 2 Machias Seal Island R.080316.001	Construction/ Demolition Waste Management & Disposal	SECTION 01 74 21 PAGE 2 July 2017
--	---	--

.6 Recycling: process of sorting, cleansing, treating and reconstituting solid waste and other discarded materials for purpose of using in altered form. Recycling does not include burning, incinerating, or thermally destroying waste.

.7 Reuse: repeated use of product in same form but not necessarily for same purpose. Reuse includes:

- .1 Salvaging reusable materials from re-modelling projects, before demolition stage, for resale, reuse on current project or for storage for use on future projects.

- .2 Returning reusable items including pallets or unused products to vendors.

.8 Salvage: removal of structural and non-structural materials from deconstruction/disassembly projects for purpose of reuse or recycling.

.9 Separate Condition: refers to waste sorted into individual types.

.10 Source Separation: acts of keeping different types of waste materials separate beginning from first time they became waste.

.11 Waste Management Co-ordinator (WMC): contractor representative responsible for supervising waste management activities as well as coordinating related, required submittal and reporting requirements.

1.04 DOCUMENTS

.1 Maintain at job site, one copy of following documents:

- .1 Waste Management Plan.

1.05 ACTION AND INFORMATIONAL SUBMITTALS

.1 Submittals in accordance with Section 01 33 00 - Submittal Procedures.

.2 Prepare and submit following 10 days prior to project start-up onsite:

- .1 Waste Management Plan that describes the location and methods of disposal for material removed from the site.

.3 Within 10 days of Substantial Performance - Submit completed project summary to verify destination and quantities on a material-by-material basis as identified in Waste Management Plan.

1.06 WASTE MANAGEMENT PLAN

.1 Prepare WMP and have ready for use prior to project start-up.

.2 Implement MSSP for waste generated on project in compliance with approved methods and as reviewed by Departmental Representative.

.3 Provide on-site facilities for collection, handling, and storage of anticipated quantities of reusable and recyclable materials.

.4 Provide containers to deposit reusable and recyclable materials.

.5 Locate containers in locations, to facilitate deposit of materials without hindering daily operations.

.6 Locate separated material[s] in area[s] which minimize material damage.

.7 Collect, handle, store on-site, and transport off-site, salvaged materials in separate condition.

.1 Transport to approved and authorized recycling facility.

.9 Prevent contamination of materials to be salvaged and recycled and handle materials in accordance with requirements for acceptance by designated facilities.

.1 On-site source separation is recommended.

.2 Remove co-mingled materials to off-site processing facility for separation.

.3 Provide waybills for separated materials.

1.07 DISPOSAL OF WASTES

.1 Do not bury rubbish or waste materials.

.2 Do not dispose of waste, volatile materials, mineral spirits, oil, paint thinner, etc, into waterways, storm, or sanitary sewers.

.3 Keep records of construction waste including:

.1 Number and size of bins.

.2 Waste type of each bin.

.3 Total tonnage generated.

.4 Tonnage reused or recycled.

.5 Reused or recycled waste destination.

.4 Remove materials from deconstruction as deconstruction/disassembly Work progresses.

.5 Prepare project summary to verify destination and quantities on a material-by-material basis as identified in Waste Management Plan.

.6 All demolished materials are to be disposed at an approved disposal location in accordance with all applicable guidelines and/or requirements by authorities having jurisdiction.

1.08 SCHEDULING

.1 Co-ordinate Work with other activities at site to ensure timely and orderly progress of Work.

PART 2 PRODUCTS

2.01 NOT USED

.1 Not used.

PART 3 EXECUTION

3.01 APPLICATION

.1 Do Work in compliance with WPM.

Lighthouse Restoration Phase 2 Machias Seal Island R.080316.001	Construction/ Demolition Waste Management & Disposal	SECTION 01 74 21 PAGE 5 July 2017
--	--	---

.2 Handle waste materials not reused, salvaged, or recycled in accordance with appropriate regulations and codes.

3.02 CLEANING

.1 Remove tools and waste materials on completion of Work, and leave work area in clean and orderly condition.

.2 Clean-up work area as work progresses.

.3 Source separate materials to be reused/recycled into specified sort areas.

END OF SECTION