

Lighthouse	Work Restrictions	SECTION 01 14 00
Restoration Phase 2		
Machias Seal Island		PAGE 1
R.080316.001		July 2017

PART 1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Section 01 56 00 - Temporary Barriers and Enclosures
- .2 Section 01 32 16.07 - Construction Progress Schedule

1.02 ACCESS AND EGRESS

- .1 Design, construct and maintain temporary "access to" and "egress from" work areas, including stairs, runways, ramps or ladders and scaffolding, independent of finished surfaces and in accordance with relevant municipal, provincial and other regulations.

1.03 USE OF SITE AND FACILITIES

- .1 Execute work with least possible interference or disturbance to normal use of premises. Make arrangements with Departmental Representative to facilitate work as stated.
- .2 Maintain existing services to building.
- .3 Where security is reduced by work provide temporary means to maintain security.
- .4 Contractor is responsible for the temporary provision of sanitary facilities for use by Contractor's personnel. Keep facilities clean.
- .5 Closures: protect work temporarily until permanent enclosures are completed.
- .6 Coordinate all work activities and temporary enclosures to allow for the continuous operation and 360 degree sightlines of the existing lantern light.

1.04 ALTERATIONS, ADDITIONS OR REPAIRS TO EXISTING BUILDING

- .1 Execute work with least possible interference or disturbance to building operations and normal use of premises. Arrange with Departmental Representative to facilitate execution of work.

Lighthouse	Work Restrictions	SECTION 01 14 00
Restoration Phase 2		
Machias Seal Island		PAGE 2
R.080316.001		July 2017

1.05 EXISTING SERVICES

.1 Notify, Departmental Representative and utility companies of intended interruption of services and obtain required permission.

.2 Where Work involves breaking into or connecting to existing services, give Departmental Representative 48 hours of notice for necessary interruption of mechanical or electrical service throughout course of work. Keep duration of interruptions minimum. Carry out interruptions after normal working hours of occupants, preferably on weekends.

.3 The Contractor is responsible for the provision of potable water onsite.

.4 The Contractor is responsible for the provision of temporary power and lights as required to complete the work.

.5 Construct barriers in accordance with Section 01 56 00 - Temporary Barriers and Enclosures.

1.06 SPECIAL REQUIREMENTS

.1 Submit schedule in accordance with Section 01 32 16.07 - Construction Progress Schedule.

.2 Ensure Contractor's personnel employed on site become familiar with and obey regulations including safety, fire, traffic and security regulations.

.3 Submit a written method statement outlining temporary protection and coordination measures related to the continuous operation of the lantern.

1.07 BUILDING SMOKING ENVIRONMENT

.1 Comply with smoking restrictions. Smoking is not permitted.

2 PRODUCTS

2.01 NOT USED

.1 Not Used.

Lighthouse	Work Restrictions	SECTION 01 14 00
Restoration Phase 2		
Machias Seal Island		PAGE 3
R.080316.001		July 2017

3 EXECUTION

3.01 NOT USED

.1 Not Used.

END OF SECTION