

**Amend Specification as follows:**

Section 01 11 02

Delete: Clause 1.9.3

Insert: New Clause, 1.9.3

Unit Price Table Scenario A is for all work as shown on the drawings within Area A including work with the limits of new asphalt in Area B.

Section 02 41 14

Delete: Clause 1.2.1 and Clause 1.2.7

Insert: New Clause, 1.2.1

Asphalt pavement and concrete removal shall be measured by the linear metre and shall include all labour, materials and equipment necessary to complete the work within Area A and Area B for Scenario A and Scenario B with the exception that Scenario A does not include the removal of the existing concrete parapet within Area B.

Insert: New Clause, 1.2.7

Electrical power pedestal removal including concrete footings, conduits, junction boxes and wiring shall be measured by each pedestal removed and shall include all labour, materials and equipment necessary to complete the work within Area A and Area B for Scenario A and Scenario B. Reinstallation of the salvaged power pedestals salvaged wiring including new concrete footings, and conduit shall be considered included in the removals and will not be measured separately for payment.

Section 31 23 11

Delete: Clause 1.5.1

Insert: New Clause, 1.5.1

Excavated materials to subgrade depth shall be measured by the linear metre and shall include all labour materials and equipment necessary to excavate within Area A and Area B for Scenario A and Scenario B and dispose surplus material off site.

Section 31 32 19.13

Delete: Clause 1.1.1

Insert: New Clause, 1.1.1

Geogrid shall be measured in square metres of surface covered by material and shall include all labour materials and equipment necessary to complete the work within Area A and Area B for Scenario A and Scenario B. An allowance has been made for placing the geogrid in the existing steel sheet pile outpans and inpans and side slope. No allowance will be made for seams and overlaps.

Section 32 12 17

Delete: Clause 1.3.1, Clause 1.3.2 and Clause 1.3.3

Insert: New Clause, 1.3.1

Asphalt base course will be measured by the tonne and shall include all labour, materials and equipment necessary to complete the work within Area A and Area B for Scenario A and Scenario B.

Insert: New Clause, 1.3.2

Asphalt base course will be measured by the tonne and shall include all labour, materials and equipment necessary to complete the work within Area A and Area B for Scenario A and Scenario B.

Insert: New Clause, 1.3.3

Granular A base will be measured in tonnes of aggregate incorporated into the work within Area A and Area B for Scenario A and Scenario B. Compaction is considered incidental to the work and will not be measured separately for payment.

**Amend Unit Price Tables as follows:**

Delete: Unit Price Table Scenario A and Unit Price Table Scenario B

Insert: New Unit Price Table Scenario A and New Unit Price Table Scenario B

**Amend Drawings as follows:**

Delete: Drawings MA-00, MA-04, MA-06 and MA-11

Insert: Drawings MA-00 Revised Details July 25, 2017, MA-04, Revised Details July 25, 2017, MA-06, Revised Details July 25, 2017 and MA-11, Revised Details July 25, 2017

**NOTE: UNIT PRICE TABLE & DRAWINGS TO FOLLOW**